

Notes

1. All adoptable highway works shall be in accordance with Leicestershire County Council Development Layout Standards and Construction Specifications.
2. All adoptable sewers to be laid in accordance with the 5th Edition of the W.A.A. "Sewers for Adoption."
3. Invert levels of outfall sewers are to be checked before commencing drainage works.
4. Private drainage to be constructed in accordance with BS 8301 1985 "Building Drainage" and Section H of the Building Regulations 1985, and any other specification required by the contract.
5. All private drainage to be 100# unless shown otherwise. Pipes to be laid and bedded in accordance with the manufacturer's instructions. All pipes on private laterals beneath public highway to be 150#.
6. Manhole cover levels are indicative and should be adjusted to suit finished levels. Covers should be fixed parallel to adjacent kerblines.
7. Pipes from adoptable road gullies to be 150 dia.

Status ☐ Preliminary ☐ For Consent ☐ For Approval ☐ For Information ☐ Tender ☐ Construction ☐ For Record Purposes

Revision	Ref	Details	Rev by	Date
	A	Roof types	rdp	11.11.19
	B	Additional SUDS added	rdp	19.11.19
	C	Road kerbs re-joint	rdp	10.04.19

Client: PERSIMMON HOMES

Project: MAIN STREET STANTON UNDER BARDON

preece consultants
ARCHITECTURAL & ENGINEERING DESIGN

Title: ADOPTION PLAN

Drawn/CAD	Engineer	Scale	Date
rdp	rdp	1:500	NOVEMBER 2019

Drg. No: 1605-101 Revision: C