Base Plan For Brick Work

NOT TO SCALE

IMPORTANT BASE DETAIL

IF IN ANY DOUBT PLEASE TELEPHONE 01233 740 804

▬▬	=	**SINGLE COURSE OF 3 HOLED ENGINEERING BRICKS**
E	=	**OUTSIDE EDGE OF BRICK**
CL	=	**CENTRE LINE OF BRICK...WHERE APPLICABLE**
▶ ◀ ▶ ◀	=	**CHECK DIAGONALS ARE EQUAL**

START BRICKS 4" INWARDS FROM EDGE OF CONCRETE

BRICKS MUST BE FLAT AND LEVEL



PLEASE ADD LIQUID WATERPROOF ADDITIVE TO MORTAR WHEN LAYING BRICKCOURSE

IF MORE THAN A SINGLE COURSE OF BRICKS ARE USED IT IS THE CUSTOMERS RESPONSIBILITY TO SECURE THE BUILDING TO THE BASE.
BASES MUST BE COMPLETED TWO WEEKS PRIOR TO DELIVERY. IF YOU ARE UNABLE TO MEET YOUR DELIVERY DATE
PLEASE INFORM US AS SOON AS POSSIBLE AND WE WILL OFFER AN ALTERNATIVE DATE WITHIN 12 WEEKS.
OUR VEHICLES CANNOT BE DRIVEN ACROSS WET & MUDDY FIELDS. IF WE ARE UNABLE TO GET WITH 10 PACES FROM THE BASE WE ASK TO ARRANGE FOR A TRACTOR, TRAILER AND STRONG EXTRA LABOUR TO ASSIST OUR ERECTING TEAM.
THE COMPANY CANNOT ACCEPT ANY RESPONSIBILITY OF DAMAGE CAUSED BY THE FOLLOWING: LIVESTOCK, FLOODING, LIGHTENING AND SEVERE WEATHER CONDITIONS ie WIND DRIVEN RAIN ect. AS A RESULT OF THIS PLEASE REMEMBER TO INSURE YOUR BUILDINGS.