

Reproduced from Ordnance Survey Digital Data by permission of Ordnance Survey® on behalf of the Controller of Her Majesty's Stationery Office. © Crown Copyright. All rights reserved. Reference number 100017603.

Notes - General Arrangement

1. The information shown on this drawing is intended to provide a general overview of the highway Improvement works. Please refer to the detailed design drawings for specific project details.
2. Do not scale from this drawing. All dimensions must be checked/ verified on site.
3. Any discrepancies noted on site are to be reported to the engineer immediately.
4. All works to be undertaken in accordance with Leicestershire County Councils design standards, specifications and standard details.
5. No works shall commence within the existing public highway until the legal agreement has been signed.
6. Highway drainage assets adjacent proposed works to be jetted and cleared of detritus.
7. All works to be undertaken shall be in accordance with the Leicestershire Highways Design Guide, LCC Standard drawings / specifications and to the satisfactory of the LCC Highways Inspector.

Key

- Highway boundary
- PCC dished channel.
- Footway / footpath / un-segregated facility
- Verges / embankments
- Tactile - Blister - controlled crossing
- TS — Traffic signal pole
- Non-illuminated traffic sign
- TP — Telegraph Pole
- FG — Proposed trapped footway gully

Schedule of Changes	
Last Rev.:	P01
Ref.	Description
1	PCC edging kerbs around grass verges removed.
2	Position of relocated telegraph poles included and key updated.
3	OS mapping trimmed to extents of topo survey for clarity.
4	Note 6 & 7 added.
5	Footway gully added at termination of PCC dished channel.
6	Highway boundary added.

PRELIMINARY ISSUE

Rev	Description	Date	Drn	Chk	App
P02	SEE SCHEDULE OF CHANGES	22.07.2026	JR	IF	IF
P01	PRELIMINARY FIRST ISSUE	07.11.2025	NN	AT	IF

Document Control

Issuing Office

Tetra Tech Leicester

4th Floor, No1 Great Central Square, Vaughan Way, Leicester, United Kingdom, LE1 4JS

Tel: +44 (0)11 6234 8000

www.tetratecheurope.com

Client

JELSON HOMES

Project Name

LAND SOUTH OF SAPCOTE ROAD, BURBAGE

Sheet Title

BURBAGE ROAD FOOTWAY IMPROVEMENT
GENERAL ARRANGEMENT
SHEET 1

TTE Project Number	Drawn By	Date	Checked By	Date	Approved By	Date	Scale @ A1	Suitability
784-B064979	NN	Nov '25	AT	Nov '25	IF	Nov '25	1:250	S4

Client Project Number	Originator	Function	Spatial	Form	Role	Number	Revision
B064979	- TTE	- HGN	- BR	- DR	- CH	-010001	P02

© Copyright Tetra Tech

TTE_MT_v1