

JMS (Midlands) Ltd		Page 1
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network	
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN	
XP Solutions	Network 2018.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	20.000	Add Flow / Climate Change (%)	0
Ratio R	0.400	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.114	4-8	0.048

Total Area Contributing (ha) = 0.162

Total Pipe Volume (m³) = 4.408

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	12.735	0.160	79.6	0.010	5.00	0.0	0.600	o	100	Pipe/Conduit	
1.001	16.375	0.205	79.9	0.004	0.00	0.0	0.600	o	100	Pipe/Conduit	
1.002	6.075	0.075	81.0	0.002	0.00	0.0	0.600	o	100	Pipe/Conduit	
1.003	5.855	0.040	146.4	0.006	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.004	10.170	0.080	127.1	0.002	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.25	119.100	0.010	0.0	0.0	0.0	0.86	6.8	1.4
1.001	50.00	5.56	118.940	0.014	0.0	0.0	0.0	0.86	6.8	1.9
1.002	50.00	5.68	118.735	0.016	0.0	0.0	0.0	0.86	6.7	2.2
1.003	50.00	5.80	118.610	0.022	0.0	0.0	0.0	0.83	14.6	3.0
1.004	50.00	5.99	118.570	0.024	0.0	0.0	0.0	0.89	15.7	3.2

JMS (Midlands) Ltd		Page 2
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
2.000	16.195	0.260	62.3	0.020	5.00	0.0	0.600	o	150	Pipe/Conduit	
1.005	17.555	0.430	40.8	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
3.000	15.565	0.105	148.2	0.008	5.00	0.0	0.600	o	150	Pipe/Conduit	
3.001	8.530	0.060	142.2	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
4.000	7.690	0.100	76.9	0.004	5.00	0.0	0.600	o	100	Pipe/Conduit	
4.001	22.575	0.270	83.6	0.003	0.00	0.0	0.600	o	100	Pipe/Conduit	
4.002	3.130	0.040	78.3	0.006	0.00	0.0	0.600	o	100	Pipe/Conduit	
3.002	19.625	0.130	151.0	0.007	0.00	0.0	0.600	o	150	Pipe/Conduit	
5.000	21.305	0.270	78.9	0.006	5.00	0.0	0.600	o	100	Pipe/Conduit	
5.001	4.570	0.030	152.3	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
5.002	11.680	0.080	146.0	0.015	0.00	0.0	0.600	o	150	Pipe/Conduit	
5.003	15.105	0.210	71.9	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
3.003	12.840	0.085	151.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
6.000	8.035	0.525	15.3	0.008	5.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
2.000	50.00	5.21	118.750	0.020	0.0	0.0	0.0	1.28	22.6	2.7
1.005	50.00	6.17	118.490	0.044	0.0	0.0	0.0	1.58	27.9	6.0
3.000	50.00	5.32	118.805	0.008	0.0	0.0	0.0	0.82	14.5	1.1
3.001	50.00	5.48	118.700	0.012	0.0	0.0	0.0	0.84	14.9	1.6
4.000	50.00	5.15	119.100	0.004	0.0	0.0	0.0	0.88	6.9	0.5
4.001	50.00	5.59	119.000	0.007	0.0	0.0	0.0	0.84	6.6	0.9
4.002	50.00	5.65	118.730	0.013	0.0	0.0	0.0	0.87	6.8	1.8
3.002	50.00	6.05	118.640	0.032	0.0	0.0	0.0	0.82	14.4	4.3
5.000	50.00	5.41	119.150	0.006	0.0	0.0	0.0	0.87	6.8	0.8
5.001	50.00	5.50	118.830	0.006	0.0	0.0	0.0	0.81	14.3	0.8
5.002	50.00	5.74	118.800	0.021	0.0	0.0	0.0	0.83	14.7	2.8
5.003	50.00	5.95	118.720	0.021	0.0	0.0	0.0	1.19	21.0	2.8
3.003	50.00	6.32	118.510	0.053	0.0	0.0	0.0	0.82	14.4	7.2
6.000	50.00	5.07	119.000	0.008	0.0	0.0	0.0	1.98	15.6	1.1

JMS (Midlands) Ltd		Page 3
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.004	22.595	0.295	76.6	0.008	0.00	0.0	0.600	o	150	Pipe/Conduit	
7.000	1.545	0.020	77.3	0.015	5.00	0.0	0.600	o	150	Pipe/Conduit	
7.001	4.895	0.470	10.4	0.010	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.006	6.500	0.045	144.4	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
8.000	2.785	0.020	139.3	0.020	5.00	0.0	0.600	o	150	Pipe/Conduit	
8.001	21.435	0.145	147.8	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
8.002	4.580	0.380	12.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.007	1.730	0.015	115.3	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.004	50.00	6.64	118.425	0.069	0.0	0.0	0.0	1.15	20.3	9.3
7.000	50.00	5.02	118.550	0.015	0.0	0.0	0.0	1.14	20.2	2.0
7.001	50.00	5.05	118.530	0.025	0.0	0.0	0.0	3.14	55.5	3.4
1.006	50.00	6.77	118.060	0.138	0.0	0.0	0.0	0.83	14.7«	18.7
8.000	50.00	5.05	118.560	0.020	0.0	0.0	0.0	0.85	15.0	2.7
8.001	50.00	5.49	118.540	0.024	0.0	0.0	0.0	0.82	14.6	3.2
8.002	50.00	5.51	118.395	0.024	0.0	0.0	0.0	2.92	51.6	3.2
1.007	50.00	6.80	118.015	0.162	0.0	0.0	0.0	1.22	48.4	21.9

JMS (Midlands) Ltd		Page 4
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Manhole Schedules for Storm

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	Pipe Out PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	Pipes In PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Backdrop (mm)
1	119.600	0.500	Open Manhole	1200	1.000	119.100	100				
2	119.550	0.610	Open Manhole	1200	1.001	118.940	100	1.000	118.940	100	
3	119.600	0.865	Open Manhole	1200	1.002	118.735	100	1.001	118.735	100	
4	119.700	1.090	Open Manhole	1200	1.003	118.610	150	1.002	118.660	100	
5	119.500	0.930	Open Manhole	1200	1.004	118.570	150	1.003	118.570	150	
6	119.650	0.900	Open Manhole	1200	2.000	118.750	150				
6	119.450	0.960	Open Manhole	1200	1.005	118.490	150	1.004	118.490	150	
								2.000	118.490	150	
8	119.700	0.895	Open Manhole	1200	3.000	118.805	150				
8	119.650	0.950	Open Manhole	1200	3.001	118.700	150	3.000	118.700	150	
12	119.700	0.600	Open Manhole	1200	4.000	119.100	100				
12	119.650	0.650	Open Manhole	1200	4.001	119.000	100	4.000	119.000	100	
12	119.650	0.920	Open Manhole	1200	4.002	118.730	100	4.001	118.730	100	
8	119.700	1.060	Open Manhole	1200	3.002	118.640	150	3.001	118.640	150	
								4.002	118.690	100	
14	119.650	0.500	Open Manhole	1200	5.000	119.150	100				
14	119.700	0.870	Open Manhole	1200	5.001	118.830	150	5.000	118.880	100	
16	119.800	1.000	Open Manhole	1200	5.002	118.800	150	5.001	118.800	150	
16	119.650	0.930	Open Manhole	1200	5.003	118.720	150	5.002	118.720	150	
8	119.500	0.990	Open Manhole	1200	3.003	118.510	150	3.002	118.510	150	
								5.003	118.510	150	
19	119.500	0.500	Open Manhole	1200	6.000	119.000	100				
8	119.400	0.975	Open Manhole	1200	3.004	118.425	150	3.003	118.425	150	
								6.000	118.475	100	
21	119.200	0.650	Open Manhole	1200	7.000	118.550	150				
21	119.200	0.670	Open Manhole	1200	7.001	118.530	150	7.000	118.530	150	
8	119.250	1.190	Open Manhole	1200	1.006	118.060	150	1.005	118.060	150	
								3.004	118.130	150	
								7.001	118.060	150	
24	119.300	0.740	Open Manhole	1200	8.000	118.560	150				
21	119.300	0.760	Open Manhole	1200	8.001	118.540	150	8.000	118.540	150	
26	119.150	0.755	Open Manhole	1200	8.002	118.395	150	8.001	118.395	150	
9	119.150	1.135	Open Manhole	1200	1.007	118.015	225	1.006	118.015	150	
								8.002	118.015	150	
	119.100	1.100	Open Manhole	0		OUTFALL		1.007	118.000	225	

JMS (Midlands) Ltd	Page 5
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN
XP Solutions	Network 2018.1



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd	Diam	MH	C.Level	I.Level	D.Depth	MH	MH DIAM., L*W
	Sect	(mm)	Name	(m)	(m)	(m)	Connection	(mm)
1.000	o	100	1	119.600	119.100	0.400	Open Manhole	1200
1.001	o	100	2	119.550	118.940	0.510	Open Manhole	1200
1.002	o	100	3	119.600	118.735	0.765	Open Manhole	1200
1.003	o	150	4	119.700	118.610	0.940	Open Manhole	1200
1.004	o	150	5	119.500	118.570	0.780	Open Manhole	1200
2.000	o	150	6	119.650	118.750	0.750	Open Manhole	1200
1.005	o	150	6	119.450	118.490	0.810	Open Manhole	1200
3.000	o	150	8	119.700	118.805	0.745	Open Manhole	1200
3.001	o	150	8	119.650	118.700	0.800	Open Manhole	1200
4.000	o	100	12	119.700	119.100	0.500	Open Manhole	1200
4.001	o	100	12	119.650	119.000	0.550	Open Manhole	1200
4.002	o	100	12	119.650	118.730	0.820	Open Manhole	1200
3.002	o	150	8	119.700	118.640	0.910	Open Manhole	1200
5.000	o	100	14	119.650	119.150	0.400	Open Manhole	1200
5.001	o	150	14	119.700	118.830	0.720	Open Manhole	1200

Downstream Manhole

PN	Length	Slope	MH	C.Level	I.Level	D.Depth	MH	MH DIAM., L*W
	(m)	(1:X)	Name	(m)	(m)	(m)	Connection	(mm)
1.000	12.735	79.6	2	119.550	118.940	0.510	Open Manhole	1200
1.001	16.375	79.9	3	119.600	118.735	0.765	Open Manhole	1200
1.002	6.075	81.0	4	119.700	118.660	0.940	Open Manhole	1200
1.003	5.855	146.4	5	119.500	118.570	0.780	Open Manhole	1200
1.004	10.170	127.1	6	119.450	118.490	0.810	Open Manhole	1200
2.000	16.195	62.3	6	119.450	118.490	0.810	Open Manhole	1200
1.005	17.555	40.8	8	119.250	118.060	1.040	Open Manhole	1200
3.000	15.565	148.2	8	119.650	118.700	0.800	Open Manhole	1200
3.001	8.530	142.2	8	119.700	118.640	0.910	Open Manhole	1200
4.000	7.690	76.9	12	119.650	119.000	0.550	Open Manhole	1200
4.001	22.575	83.6	12	119.650	118.730	0.820	Open Manhole	1200
4.002	3.130	78.3	8	119.700	118.690	0.910	Open Manhole	1200
3.002	19.625	151.0	8	119.500	118.510	0.840	Open Manhole	1200
5.000	21.305	78.9	14	119.700	118.880	0.720	Open Manhole	1200
5.001	4.570	152.3	16	119.800	118.800	0.850	Open Manhole	1200

JMS (Midlands) Ltd	Page 6
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN
XP Solutions	Network 2018.1



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
5.002	o	150	16	119.800	118.800	0.850	Open Manhole	1200
5.003	o	150	16	119.650	118.720	0.780	Open Manhole	1200
3.003	o	150	8	119.500	118.510	0.840	Open Manhole	1200
6.000	o	100	19	119.500	119.000	0.400	Open Manhole	1200
3.004	o	150	8	119.400	118.425	0.825	Open Manhole	1200
7.000	o	150	21	119.200	118.550	0.500	Open Manhole	1200
7.001	o	150	21	119.200	118.530	0.520	Open Manhole	1200
1.006	o	150	8	119.250	118.060	1.040	Open Manhole	1200
8.000	o	150	24	119.300	118.560	0.590	Open Manhole	1200
8.001	o	150	21	119.300	118.540	0.610	Open Manhole	1200
8.002	o	150	26	119.150	118.395	0.605	Open Manhole	1200
1.007	o	225	9	119.150	118.015	0.910	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
5.002	11.680	146.0	16	119.650	118.720	0.780	Open Manhole	1200
5.003	15.105	71.9	8	119.500	118.510	0.840	Open Manhole	1200
3.003	12.840	151.1	8	119.400	118.425	0.825	Open Manhole	1200
6.000	8.035	15.3	8	119.400	118.475	0.825	Open Manhole	1200
3.004	22.595	76.6	8	119.250	118.130	0.970	Open Manhole	1200
7.000	1.545	77.3	21	119.200	118.530	0.520	Open Manhole	1200
7.001	4.895	10.4	8	119.250	118.060	1.040	Open Manhole	1200
1.006	6.500	144.4	9	119.150	118.015	0.985	Open Manhole	1200
8.000	2.785	139.3	21	119.300	118.540	0.610	Open Manhole	1200
8.001	21.435	147.8	26	119.150	118.395	0.605	Open Manhole	1200
8.002	4.580	12.1	9	119.150	118.015	0.985	Open Manhole	1200
1.007	1.730	115.3		119.100	118.000	0.875	Open Manhole	0

JMS (Midlands) Ltd		Page 7
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall C. Level Name (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.007	119.100	118.000	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha	Storage 2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	6
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	2	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.000	Storm Duration (mins)	30
Ratio R	0.400		

©1982-2018 Innovyze

JMS (Midlands) Ltd		Page 8
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Online Controls for Storm

Orifice Manhole: 6, DS/PN: 1.005, Volume (m³): 1.5

Diameter (m) 0.028 Discharge Coefficient 0.600 Invert Level (m) 118.490

Orifice Manhole: 8, DS/PN: 3.003, Volume (m³): 1.7

Diameter (m) 0.017 Discharge Coefficient 0.600 Invert Level (m) 118.510

Hydro-Brake® Optimum Manhole: 9, DS/PN: 1.007, Volume (m³): 1.4

Unit Reference	MD-SHE-0095-4000-1000-4000
Design Head (m)	1.000
Design Flow (l/s)	4.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	95
Invert Level (m)	118.015
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.000	4.0
Flush-Flo™	0.294	4.0
Kick-Flo®	0.629	3.2
Mean Flow over Head Range	-	3.5

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.0	1.200	4.3	3.000	6.7	7.000	10.0
0.200	3.9	1.400	4.7	3.500	7.2	7.500	10.3
0.300	4.0	1.600	5.0	4.000	7.6	8.000	10.6
0.400	3.9	1.800	5.3	4.500	8.1	8.500	10.9
0.500	3.8	2.000	5.5	5.000	8.5	9.000	11.2
0.600	3.4	2.200	5.8	5.500	8.9	9.500	11.5
0.800	3.6	2.400	6.0	6.000	9.3		
1.000	4.0	2.600	6.2	6.500	9.6		

JMS (Midlands) Ltd	Page 9
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN
XP Solutions	Network 2018.1



Storage Structures for Storm

Porous Car Park Manhole: 4, DS/PN: 1.003

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	5.0
Membrane Percolation (mm/hr)	1000	Length (m)	8.6
Max Percolation (l/s)	11.9	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	119.120	Cap Volume Depth (m)	0.400

Porous Car Park Manhole: 6, DS/PN: 2.000

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	5.0
Membrane Percolation (mm/hr)	1000	Length (m)	20.8
Max Percolation (l/s)	28.9	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	119.020	Cap Volume Depth (m)	0.400

Porous Car Park Manhole: 8, DS/PN: 3.002

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	5.0
Membrane Percolation (mm/hr)	1000	Length (m)	15.4
Max Percolation (l/s)	21.4	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	119.045	Cap Volume Depth (m)	0.500

Porous Car Park Manhole: 16, DS/PN: 5.002

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	5.0
Membrane Percolation (mm/hr)	1000	Length (m)	22.0
Max Percolation (l/s)	30.6	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	119.020	Cap Volume Depth (m)	0.500

Swale Manhole: 21, DS/PN: 7.000

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

Infiltration Coefficient Base (m/hr)	0.00000	Length (m)	18.0
Infiltration Coefficient Side (m/hr)	0.00000	Side Slope (1:X)	3.0
Safety Factor	2.0	Slope (1:X)	100.0
Porosity	1.00	Cap Volume Depth (m)	0.000
Invert Level (m)	118.550	Cap Infiltration Depth (m)	0.000
Base Width (m)	0.3	Include Swale Volume	Yes

JMS (Midlands) Ltd		Page 10
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

Swale Manhole: 24, DS/PN: 8.000

Warning:- Volume should always be included unless the upstream pipe is being used for storage and/or as a carrier

Infiltration Coefficient Base (m/hr)	0.00000	Length (m)	10.0
Infiltration Coefficient Side (m/hr)	0.00000	Side Slope (1:X)	3.0
Safety Factor	2.0	Slope (1:X)	100.0
Porosity	1.00	Cap Volume Depth (m)	0.000
Invert Level (m)	118.560	Cap Infiltration Depth (m)	0.000
Base Width (m)	0.3	Include Swale Volume	Yes

JMS (Midlands) Ltd									Page 11
Victoria Count					CO23/0201/03				
Tennant St Nuneaton					Ashby Road, Stapleton				
Warwickshire CV11 4LZ					Detailed Drainage Network				
Date 30/11/2023 17:08					Designed by PG				
File MICRODRAINAGE 27.11.23.MDX					Checked by BN				
XP Solutions					Network 2018.1				
<u>1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>									
<u>Simulation Criteria</u>									
Areal Reduction Factor	1.000				Additional Flow - % of Total Flow	0.000			
Hot Start (mins)	0				MADD Factor * 10m³/ha Storage	2.000			
Hot Start Level (mm)	0				Inlet Coefficient	0.800			
Manhole Headloss Coeff (Global)	0.500				Flow per Person per Day (l/per/day)	0.000			
Foul Sewage per hectare (l/s)	0.000								
Number of Input Hydrographs	0				Number of Storage Structures	6			
Number of Online Controls	3				Number of Time/Area Diagrams	0			
Number of Offline Controls	0				Number of Real Time Controls	0			
<u>Synthetic Rainfall Details</u>									
Rainfall Model					FSR	Ratio R	0.400		
Region England and Wales Cv (Summer)							0.750		
M5-60 (mm)					20.000 Cv (Winter)		0.840		
Margin for Flood Risk Warning (mm)								300.0	
Analysis Timestep	2.5				Second Increment (Extended)				
DTS Status								OFF	
DVD Status								ON	
Inertia Status								ON	
Profile(s)								Summer and Winter	
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440								
Return Period(s) (years)								1, 30, 100	
Climate Change (%)								0, 0, 40	
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	1	+0%	30/30 Winter				119.132
1.001	2	15 Winter	1	+0%	30/15 Summer				118.977
1.002	3	60 Winter	1	+0%	1/30 Winter				118.890
1.003	4	60 Winter	1	+0%	1/15 Summer				118.888
1.004	5	60 Winter	1	+0%	1/15 Summer				118.887
2.000	6	60 Winter	1	+0%	30/15 Summer				118.886
1.005	6	60 Winter	1	+0%	1/15 Summer				118.884
3.000	8	240 Winter	1	+0%	1/60 Winter				119.007
3.001	8	240 Winter	1	+0%	1/30 Summer				119.007
4.000	12	15 Winter	1	+0%	30/60 Winter				119.120
4.001	12	15 Winter	1	+0%	30/15 Summer				119.025
4.002	12	240 Winter	1	+0%	1/15 Winter				119.007
3.002	8	240 Winter	1	+0%	1/15 Summer				119.007
5.000	14	15 Winter	1	+0%	100/30 Summer				119.174
5.001	14	240 Winter	1	+0%	1/120 Winter				119.007
5.002	16	240 Winter	1	+0%	1/60 Winter				119.007
5.003	16	240 Winter	1	+0%	1/30 Summer				119.006
3.003	8	240 Winter	1	+0%	1/15 Summer				119.006
6.000	19	15 Winter	1	+0%					119.019

JMS (Midlands) Ltd		Page 12
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network	
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN	
XP Solutions	Network 2018.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm


PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	1	-0.068	0.000	0.21		1.4	OK	
1.001	2	-0.063	0.000	0.29		1.9	OK	
1.002	3	0.055	0.000	0.19		1.1	SURCHARGED	
1.003	4	0.128	0.000	0.08		0.9	SURCHARGED	
1.004	5	0.167	0.000	0.05		0.7	SURCHARGED	
2.000	6	-0.014	0.000	0.07		1.5	OK	
1.005	6	0.244	0.000	0.04		1.0	SURCHARGED	
3.000	8	0.052	0.000	0.02		0.2	SURCHARGED	
3.001	8	0.157	0.000	0.02		0.2	SURCHARGED	
4.000	12	-0.080	0.000	0.09		0.5	OK	
4.001	12	-0.075	0.000	0.14		0.9	OK	
4.002	12	0.177	0.000	0.05		0.3	SURCHARGED	
3.002	8	0.217	0.000	0.03		0.4	SURCHARGED	
5.000	14	-0.076	0.000	0.13		0.8	OK	
5.001	14	0.027	0.000	0.02		0.2	SURCHARGED	
5.002	16	0.057	0.000	0.04		0.6	SURCHARGED	
5.003	16	0.136	0.000	0.02		0.4	SURCHARGED	
3.003	8	0.346	0.000	0.03		0.4	SURCHARGED	
6.000	19	-0.081	0.000	0.08		1.1	OK	

JMS (Midlands) Ltd		Page 13
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Level
							Act.	(m)
3.004	8 30	Winter	1	+0%	30/15 Summer			118.501
7.000	21 15	Winter	1	+0%	30/15 Summer			118.594
7.001	21 15	Winter	1	+0%	30/15 Summer			118.557
1.006	8 30	Winter	1	+0%	1/15 Summer			118.496
8.000	24 15	Winter	1	+0%	30/15 Summer			118.611
8.001	21 15	Winter	1	+0%	30/15 Summer			118.589
8.002	26 30	Winter	1	+0%	30/15 Summer			118.491
1.007	9 30	Winter	1	+0%	1/15 Summer			118.489

US/MH		Surcharged Flooded		Pipe		Level	
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status
							Exceeded
3.004	8	-0.074	0.000	0.10		1.9	OK
7.000	21	-0.106	0.000	0.19		2.0	OK
7.001	21	-0.123	0.000	0.07		3.2	OK
1.006	8	0.286	0.000	0.26		3.2	SURCHARGED
8.000	24	-0.099	0.000	0.25		2.7	OK
8.001	21	-0.101	0.000	0.23		3.2	OK
8.002	26	-0.054	0.000	0.07		2.5	OK
1.007	9	0.249	0.000	0.13		4.0	SURCHARGED

JMS (Midlands) Ltd		Page 14	
Victoria Count		CO23/0201/03	
Tennant St Nuneaton		Ashby Road, Stapleton	
Warwickshire CV11 4LZ		Detailed Drainage Network	
Date 30/11/2023 17:08		Designed by PG	
File MICRODRAINAGE 27.11.23.MDX		Checked by BN	
XP Solutions		Network 2018.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	6
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	20.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	60 Winter	30	+0%	30/30 Winter				119.217
1.001	2	60 Winter	30	+0%	30/15 Summer				119.212
1.002	3	60 Winter	30	+0%	1/30 Winter				119.207
1.003	4	60 Winter	30	+0%	1/15 Summer				119.205
1.004	5	60 Winter	30	+0%	1/15 Summer				119.203
2.000	6	60 Winter	30	+0%	30/15 Summer				119.203
1.005	6	60 Winter	30	+0%	1/15 Summer				119.201
3.000	8	240 Winter	30	+0%	1/60 Winter				119.239
3.001	8	240 Winter	30	+0%	1/30 Summer				119.239
4.000	12	240 Winter	30	+0%	30/60 Winter				119.240
4.001	12	240 Winter	30	+0%	30/15 Summer				119.240
4.002	12	240 Winter	30	+0%	1/15 Winter				119.239
3.002	8	240 Winter	30	+0%	1/15 Summer				119.239
5.000	14	240 Winter	30	+0%	100/30 Summer				119.240
5.001	14	240 Winter	30	+0%	1/120 Winter				119.239
5.002	16	240 Winter	30	+0%	1/60 Winter				119.239
5.003	16	240 Winter	30	+0%	1/30 Summer				119.238
3.003	8	240 Winter	30	+0%	1/15 Summer				119.237
6.000	19	15 Winter	30	+0%					119.030

©1982-2018 Innovyze

JMS (Midlands) Ltd		Page 15
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network	
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN	
XP Solutions	Network 2018.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	1	0.017	0.000	0.27		1.7	SURCHARGED	
1.001	2	0.172	0.000	0.32		2.0	SURCHARGED	
1.002	3	0.372	0.000	0.29		1.7	SURCHARGED	
1.003	4	0.445	0.000	0.16		2.0	SURCHARGED	
1.004	5	0.483	0.000	0.14		1.9	FLOOD RISK	
2.000	6	0.303	0.000	0.09		2.0	SURCHARGED	
1.005	6	0.561	0.000	0.05		1.2	FLOOD RISK	
3.000	8	0.284	0.000	0.03		0.4	SURCHARGED	
3.001	8	0.389	0.000	0.05		0.6	SURCHARGED	
4.000	12	0.040	0.000	0.04		0.2	SURCHARGED	
4.001	12	0.140	0.000	0.06		0.4	SURCHARGED	
4.002	12	0.409	0.000	0.10		0.6	SURCHARGED	
3.002	8	0.449	0.000	0.05		0.6	SURCHARGED	
5.000	14	-0.010	0.000	0.06		0.4	OK	
5.001	14	0.259	0.000	0.03		0.3	SURCHARGED	
5.002	16	0.289	0.000	0.05		0.6	SURCHARGED	
5.003	16	0.368	0.000	0.02		0.4	SURCHARGED	
3.003	8	0.577	0.000	0.04		0.5	FLOOD RISK	
6.000	19	-0.070	0.000	0.19		2.7	OK	

JMS (Midlands) Ltd		Page 16
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network	
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN	
XP Solutions	Network 2018.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

									Water
	US/MH			Return	Climate	First (X)	First (Y)	First (Z)	Overflow
PN	Name	Storm	Period		Change	Surcharge	Flood	Overflow	Act.
									Level
									(m)
3.004	8	60 Winter	30		+0%	30/15 Summer			118.800
7.000	21	60 Winter	30		+0%	30/15 Summer			118.797
7.001	21	60 Winter	30		+0%	30/15 Summer			118.797
1.006	8	60 Winter	30		+0%	1/15 Summer			118.795
8.000	24	60 Winter	30		+0%	30/15 Summer			118.795
8.001	21	60 Winter	30		+0%	30/15 Summer			118.794
8.002	26	60 Winter	30		+0%	30/15 Summer			118.790
1.007	9	60 Winter	30		+0%	1/15 Summer			118.788

US/MH		Surcharged Flooded		Pipe		Level	
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status
3.004	8	0.225	0.000	0.14		2.7	SURCHARGED
7.000	21	0.097	0.000	0.21		2.2	SURCHARGED
7.001	21	0.117	0.000	0.08		3.6	SURCHARGED
1.006	8	0.585	0.000	0.31		3.9	SURCHARGED
8.000	24	0.085	0.000	0.28		3.0	SURCHARGED
8.001	21	0.104	0.000	0.25		3.5	SURCHARGED
8.002	26	0.245	0.000	0.07		2.6	SURCHARGED
1.007	9	0.548	0.000	0.13		4.0	SURCHARGED

JMS (Midlands) Ltd		Page 18
Victoria Count Tennant St Nuneaton Warwickshire CV11 4LZ	CO23/0201/03 Ashby Road, Stapleton Detailed Drainage Network	
Date 30/11/2023 17:08 File MICRODRAINAGE 27.11.23.MDX	Designed by PG Checked by BN	
XP Solutions	Network 2018.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	1	0.267	0.000	0.56		3.6	FLOOD RISK	
1.001	2	0.384	0.000	0.71		4.6	FLOOD RISK	
1.002	3	0.570	0.000	0.42		2.5	FLOOD RISK	
1.003	4	0.642	0.000	0.15		1.8	FLOOD RISK	
1.004	5	0.681	0.000	0.13		1.9	FLOOD RISK	
2.000	6	0.501	0.000	0.07		1.5	FLOOD RISK	
1.005	6	0.759	0.000	0.05		1.2	FLOOD RISK	
3.000	8	0.517	0.000	0.05		0.6	FLOOD RISK	
3.001	8	0.621	0.000	0.07		0.9	FLOOD RISK	
4.000	12	0.272	0.000	0.04		0.3	FLOOD RISK	
4.001	12	0.372	0.000	0.07		0.4	FLOOD RISK	
4.002	12	0.641	0.000	0.16		0.9	FLOOD RISK	
3.002	8	0.681	0.000	0.07		0.9	FLOOD RISK	
5.000	14	0.222	0.000	0.07		0.4	FLOOD RISK	
5.001	14	0.491	0.000	0.03		0.4	FLOOD RISK	
5.002	16	0.521	0.000	0.03		0.4	SURCHARGED	
5.003	16	0.600	0.000	0.02		0.3	FLOOD RISK	
3.003	8	0.809	0.000	0.04		0.6	FLOOD RISK	
6.000	19	-0.059	0.000	0.35		5.0	OK	

JMS (Midlands) Ltd		Page 19
Victoria Count	CO23/0201/03	
Tennant St Nuneaton	Ashby Road, Stapleton	
Warwickshire CV11 4LZ	Detailed Drainage Network	
Date 30/11/2023 17:08	Designed by PG	
File MICRODRAINAGE 27.11.23.MDX	Checked by BN	
XP Solutions	Network 2018.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

US/MH		Return Climate		First (X)		First (Y)		First (Z)		Overflow	Water Level
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.			(m)
3.004	8	60 Winter	100	+40%	30/15 Summer						118.997
7.000	21	60 Winter	100	+40%	30/15 Summer						118.994
7.001	21	60 Winter	100	+40%	30/15 Summer						118.993
1.006	8	60 Winter	100	+40%	1/15 Summer						118.991
8.000	24	60 Winter	100	+40%	30/15 Summer						118.992
8.001	21	60 Winter	100	+40%	30/15 Summer						118.991
8.002	26	60 Winter	100	+40%	30/15 Summer						118.986
1.007	9	60 Winter	100	+40%	1/15 Summer						118.984

US/MH		Surcharged		Flooded		Pipe		Level	
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status	Exceeded	
3.004	8	0.422	0.000	0.26		5.0	SURCHARGED		
7.000	21	0.294	0.000	0.21		2.3	FLOOD RISK		
7.001	21	0.313	0.000	0.09		3.8	FLOOD RISK		
1.006	8	0.781	0.000	0.34		4.3	FLOOD RISK		
8.000	24	0.282	0.000	0.31		3.3	SURCHARGED		
8.001	21	0.301	0.000	0.26		3.6	SURCHARGED		
8.002	26	0.441	0.000	0.06		2.3	FLOOD RISK		
1.007	9	0.744	0.000	0.13		4.0	FLOOD RISK		