



LEGEND

- EXISTING VEGETATION
To be removed
- EXISTING HEDGES
*With Root Protection Area
To be retained*
- PROPOSED TREES
*Select Standard/Heavy Standard
See Schedule*
- SPECIMEN PLANTING
See Schedule
- ORNAMENTAL HEDGE
*See Schedule
TOTAL LENGTH: 608m*
- NATIVE HEDGE
*See Schedule
TOTAL LENGTH: 391m*
- PROPOSED PLANTING
See Schedule
- TURF
TOTAL AREA: 2130m²
- AMENITY GRASS AREAS
*Emergent EG22 sown at 25g/m²
Kestrel mown short to 40mm
TOTAL AREA: 4185m²*
- WILDFLOWER MEADOW
*Emergent EM3 sown at 4 g/m²
TOTAL AREA: 1925m²
(Planting presented to be retained and managed
where retention is required see above)*
- NATIVE BUFFER MIX
*See Schedule
TOTAL AREA: 130m²*
- MARGINAL MIX
*See Schedule
TOTAL AREA: 921m²*
- GRAVEL
*40mm of Stone over Membrane
TOTAL AREA: 30m²*

DRAWING NOTES

All tree and shrub locations and species must be taken into consideration by the project Structural Engineer to ensure that foundation design accords with the specifications set out in Chapter 4 of the NHBC Standards.

The Landscape Contractor must ensure that plant material is planted in the locations shown and with NO SUBSTITUTIONS made without consulting the Group Landscape Design Department. It is the Landscape Contractor's responsibility to ensure that all underground services have been located and identified in advance of tree pit excavation so that no services are damaged or compromised by tree planting. Any changes to tree positions, species or specifications must be approved by the Group Landscape Design Department. Underground service strips are to be kept free of all plant material. Contractors must comply with all Health and Safety regulations and be aware of project/site specific information including referring to the information set out in the CDM drawings.

SHEET LAYOUT LOCATION PLAN

NOT TO SCALE

CDM LEGEND

Symbol	Brief description of risk.
	Caution overhead / underground services.
	Sewer easement.
	Trees have protection order in place, guarding required.

NOTES:
Principal contractor to ensure all health and safety procedures are being correctly followed in relation to all temporary works.

PLOT NUMBER SHEET REF.

024: 1-27, 30-35, 109-111, 114, 118-127
025: 29-31, 36-59, 60-79
026: 27-32, 43-48, 97-117, 88-92, 60-75
027: 60-63, 70-78, 80-96

FOR SPECIFICATION, PLANTING DETAILS & SCHEDULE SEE DRAWING EM100-LS-029

Revision	Date	
A	Updated to show LEAP	16.04.25
B	Updated PCS on northern boundary	24.04.25
C	Revised PCS on southern boundary	16.05.25
D	Updated landscaping to latest site layout	23.05.25
E	Revised PCS on northern boundary	26.05.25
F	Revised Red Line Boundary	17.07.25
G	Updated to latest layout	28.10.25

Job:	SITE LANDSCAPING - FITCHETT		
Title:	Site Landscaping		
Scale:	1:200 @A0	Drawn:	RB
Date:	March 2025	Checked:	PmJ

THIS DRAWING AND THE BUILDING WORKS DEPICTED ARE THE COPYRIGHT OF FITCHETT BY BLOOR HOMES. NO PART OF THIS DRAWING OR THE BUILDING WORKS DEPICTED ARE TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FITCHETT BY BLOOR HOMES.

Fitchett
by Bloor Homes

3 S BLOOR (SERVICES) LIMITED
ASHBY ROAD, MEASHAM, SWADLINCOTE,
DERBYSHIRE, DE12 7JP.
TELEPHONE 01530 272100 FACSIMILE 01530 272000

Drawing No. EM100-LS-027g

HINCKLEY - PH7