

Area 1
Existing Permitted waste site.
All yard concreted with drainage through Conder CNS80s/11 Class 1 full retention seperator with silt trap discharging to adjacent water course.
WC connected to Package treatment plant discharging to watercourse.

Area 2
Existing drains removed and replaced with 2 number precast trapped road gullies to BS5911 with Grade A Class 1 grates feeding via 160 sealed Hepworth PlastiDrain to Conder CNS80s/11 Clas 1 Full retention seperator with silt trap discharging to water course.
Any potentially contaminated soils removed from site to suitably Permitted site.
Site edges to south and east formed using 200 x 6000 x 1000 mm precast concrete panels with one panel laid below finished concrete pavement. Panels moved back from edge of existing boundary walls and watercourse an additional 1 metre.
All vertical and horizontal joints sealed with Hydrotite.
Concrete pavement made good with 300mm C40 concrete with A143 steel mesh and dowelled joints falling to gullies. Joints cut, primed and sealed with Fosroc Colpor 200PF.

Area 3
Clear site and disconnect all drains, including any foul drains from house.
Remove and contaminated materials to Permitted Site.
Make good ground level with 300 mm clean hardcore.
Lay 300 mm C40 concrete with A143 steel mesh and dowelled joints to fall to gullies.
Gullies precast trapped road gullies to BS5911 feeding via 160 mm sealed Hepworth PlastiDrain to Conder CN30s/11 full retention seperator with silt trap discharging to watercourse.
Additional roof waters connect to discharge pipe downstream of seperator.

N

KEY

Site demarcation

Drain line

Flow Gully

Seperator

E Taylor Skip Hire & Recycling Ltd

TITLE
Site Layout
Leicester Road
Hinckley

SIZE		DWG NO	REV
A1		ETR/HIN/09/2	
SCALE 1/500		April 2009	SHEET 1