This drawing is to be checked against all other relevant drawings including those by specialist. Copyright of Henry Mein Partnership DO NOT SCALE

Revision	Date	By	Chkd	No
rooflight to the retail and sola vents removed	28.08.12	nh	nh	A
car parking reduced under the tree canopy and bin collection point for residential relocated	17.10.12	nh	nh	B
acoustic fence highlighted	31.10.12	nh	nh	C
alterations to the plant compound, reduction in landscaping and block pavers amended to coloured tarmac to the residential, bark chippings to back of site	05.02.13	nh	nh	D

LEGEND

- Tarmac
- Concrete paving slabs
- block pavers
- coloured tarmac to match block paving
- Geo textile sheeting under bark chippings
- Grasscrete surfacing
- Landscaped area
- Existing trees
- Indicative Proposed Trees / Planting
- Indicative Proposed extent of acoustic fence

DWELLINGS

No. 1, 2 & 3 (2 Bedroom)

Ground Floor Area: 36.85m² / 396.66 sq ft

First Floor Area: 36.85m² / 396.66 sq ft

Total Floor Area: 73.70m² / 793.32 sq ft

No. 4, 5 & 6 (3 Bedroom)

Ground Floor Area: 41.69m² / 448.76 sq ft

First Floor Area: 41.69m² / 448.76 sq ft

Total Floor Area: 83.38m² / 897.52 sq ft

PARKING

Retail - 22 Spaces (Inc. 3 disabled).

Dwellings - 12 spaces (2no. per dwelling)

ACOUSTIC FENCING

reflective sound screen proposed which will be 2m high, 18mm thick with a surface density of at least 10 Kg/m2.

Conforms and tested to BS EN 1793 and BS EN 1794-1 and BS EN 1791-2

N

0 2 4 6 8 10m 12 14 16 18 20m

Linear Scale (metres)

Tender

Midlands Co-operative Society

Proposed New Store
Main Street
Markfield

Site Plan

1:200 @ A1 June 2012 **6671T06 D**

Drawn By: JEB Checked By: nh

Henry Mein Partnership
Architects

12 Clarendon Street Nottingham NG1 5HQ t: 0115 9476065 f: 0115 9240136 e: info@henrymein.co.uk w: www.henrymein.co.uk

ISO 9001 REGISTERED FIRM

PROPOSED SITE PLAN