





Final locations of trees to be agreed on site.

- Existing levels to be preserved around existing trees and vegetation to be retained or thinned out.
- Existing trees to be retained as identified on landscape plans, these are to be protected during construction inline with BS 5837:2012 Trees in relation to construction.
- Any necessary tree works to be undertaken by a approved tree surgeon to comply with BS3998:2010 'Recommendations for tree works'.
- For all arboricultural issues refer to survey and reports undertaken by others.
- Final location of tree species will be subject to location of fencing, foundations and services. Locations to be agreed on site.
- In the event that any trees, shrubs, planting included in the scheme, or any replacement trees, shrubs or planting being removed, destroyed, dying or dead within 5 years of planting, they shall be replaced within 12 months in the same place by large nursery stock of the same species.
- The final size of tree pits to be dug will be subject to soil conditions and size of rootball. Tree pit sizes are to be agreed with the landscape architect prior to excavations. All tree pits to be inspected by the Client representative prior to planting.

[illegible]

Previous Superseded Drawing number:
P22009-00-001-DZ-0410

Client: