



Hinckley Day Care

Car Park Enabling Works – Planning Number 23/01203/FUL

March 2024

Waterman Infrastructure & Environment Limited

5th Floor, One Cornwall Street, Birmingham, B3 2DX
www.watermangroup.com

Client Name: Darwin Group
Document Reference: WIE19849-100-3-1-3-TN Enabling
Project Number: WIE19849

Quality Assurance – Approval Status

This document has been prepared and checked in accordance with
Waterman Group’s IMS (BS EN ISO 9001: 2015, BS EN ISO 14001: 2015 and BS EN ISO 45001:2018)

Issue	Date	Prepared by	Checked by	Approved by
First	18/03/2024	R.Lal	S.Songprasit	P.Edge
				

Comments

Comments

Disclaimer

This report has been prepared by Waterman Infrastructure & Environment Limited, with all reasonable skill, care and diligence within the terms of the Contract with the client, incorporation of our General Terms and Condition of Business and taking account of the resources devoted to us by agreement with the client.

We disclaim any responsibility to the client and others in respect of any matters outside the scope of the above.

This report is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the report at its own risk.

Contents

1. Introduction	1
Background	1
Site Description	1
Development Proposals	2
2. Drainage	3
Site Surface Water Drainage System	3
Greenfield Runoff Rates	3
Brownfield Runoff Rates	3
Proposed Surface Water Drainage Strategy	4
3 Conclusions and Recommendations	6

Figures

Figure 1: Site Location Plan	1
------------------------------------	---

Tables

Table 1: Greenfield Runoff Rates	3
Table 2: Brownfield Runoff Rates for 1 in 1 year	3
Table 3: Brownfield Runoff Rates for 1 in 30 year	4
Table 4: Brownfield Runoff Rates for 1 in 100 year	4

Appendices

- A. Site Location Plan
- B. Drainage Strategy Calculations
- C. Drainage Maintenance Plan

Contents

Hinckley Day Care

Project Number: WIE19849

Document Reference: WIE19849-100-3-1-3-TN Enabling

1. Introduction


Background

- 1.1. Waterman Infrastructure & Environment Limited ("Waterman") have been commissioned by Waterman Structures, on behalf of Darwin Group ('the Client') to prepare a Technical Note in response to the planning application for the enabling/car park works package at Hinckley and District Hospital, on Mount Road, Hinckley LE10 1AG (hereafter referred to as 'the Site').
- 1.2. The purpose of this report is to provide details of the Site drainage calculations to discharge the surface water from the Hinckley Daycare site in respect of the requirements of planning application. 23/01203/FUL.

Site Description

- 1.3. The Site is located at Hinckley and District Hospital, Hinckley, approximately 20km from Leicester City Centre. The overall Site is brownfield with an approximate red line boundary of 0.214ha and a blue line boundary of 0.186ha. Therefore the total Site boundary is 0.400ha.
- 1.4. The west of the Site is bound by access roads (Argents Mead) and a leisure centre. There are residential dwellings to the east and Mouth Road to the south of the Site. To the north, there are more access roads, footways, Greenland and behind that a car park.
- 1.5. The Site is located at the grid reference SP 42927 93749 with coordinates X:442927, Y: 293749 and the nearest postcode being LE10 1AG.
- 1.6. The general site location is shown in **Figure 1** below and the red and blue line boundaries shown on Drawing 19849-WIE-ZZ-XX-DR-D-92-003 in **Appendix A**.

Figure 1: Site Location Plan



Development Proposals

- 1.7. The development proposals involve the construction of a car park and external facilities and a two-storey Community Diagnostics Centre (CDC) and Endoscopy building in the adjacent site (blue line boundary).

2. Drainage

Site Surface Water Drainage System

- 2.1. The surface water drainage for the application site is part of a larger new system which incorporates the adjacent new Community Diagnostics Centre (CDC) and Endoscopy building. The proposed area for the application Site (red line boundary) is 0.214ha. The existing access road (Argents Mead) to the west of the Site has existing adequate drainage in place and does not form part of the proposed drainage design. The road area of 0.069ha is therefore excluded from the drainage calculations, leaving the catchment drainage area of the whole site to be 0.335ha.

Greenfield Runoff Rates

- 2.2. The greenfield runoff rates have been calculated based off the whole site area of 0.335ha using the ICP SUDS method in MicroDrainage which uses the IH124 method and scales the runoffs down from a 50-ha Site. The results are shown in Error! Reference source not found. below and **Appendix B**.

Table 1: Greenfield Runoff Rates

Flood Event	Open Field
QBAR _{Rural}	1.8 l/s
QBAR _{Urban}	1.8 l/s
Q1 Year	1.5 l/s
Q30 Years	3.5 l/s
Q100 Years	4.6 l/s

Brownfield Runoff Rates

- 2.3. As the entire Site has been previously developed, a brownfield runoff rate is calculated based on the hardstanding area of 0.298 ha. Runoff from the existing Site has been calculated using the Rational Method based on an estimation of impermeable areas. The existing Site runoff calculation is shown in Error! Reference source not found. to **Table 4: Brownfield Runoff Rates for 1 in 100 year**
- 2.4. 4.

Table 2: Brownfield Runoff Rates for 1 in 1 year

Storm Duration (mins)	Average Rainfall Intensity (mm/hr)	Brownfield Runoff Rate (l/s)
	1 in 1 year	Modified Rational Method $Q = 2.78 C i A$
15	30.7	24.8
30	20.0	16.1
60	12.7	10.2
120	7.9	6.3
240	4.8	3.9
360	3.6	2.9
600	2.5	2.0
1440	1.3	1.1

Table 3: Brownfield Runoff Rates for 1 in 30 year

Storm Duration (mins)	Average Rainfall Intensity (mm/hr)	Brownfield Runoff Rate (l/s)
	1 in 30 years	Modified Rational Method $Q = 2.78 C i A$
15	75.2	60.8
30	49.0	39.6
60	30.5	24.6
120	18.4	14.9
240	10.9	8.8
360	8.0	6.4
600	5.4	4.3
1440	2.7	2.2

Table 4: Brownfield Runoff Rates for 1 in 100 year

Storm Duration (mins)	Average Rainfall Intensity (mm/hr)	Brownfield Runoff Rate (l/s)
	1 in 100 years	Modified Rational Method $Q = 2.78 C i A$
15	97.6	78.8
30	64.1	51.8
60	40.1	32.4
120	24.2	19.6
240	14.2	11.5
360	10.3	8.3
600	6.9	5.6
1440	3.4	2.8

- 2.4 The brownfield runoff rates for the 1 in 1, 1 in 30 and 1 in 100 year for 60 minutes storm duration are 10.2l/s, 24.6l/s and 32.4l/s respectively.

Proposed Surface Water Drainage Strategy

- 2.5 The management of surface water is considered an essential element in reducing future flood risk to both the Site and its surroundings. In accordance with the NPPF, design proposals should seek to ensure that surface water run-off is managed as close to its source as possible.
- 2.6 As the greenfield run-off rates are very low and will likely cause a blockage in the drainage system, the drainage for the Site has been designed based on 5 l/s. The average attenuation storage was calculated using InfoDrainage Software with a maximum allowable discharge rate of 5 l/s.
- 2.7 The InfoDrainage calculations are presented in **Appendix B** with the highlighted figures relevant to the car park enabling works planning application.
- 2.8 The proposed overall attenuation storage volume of approximately 140m³ is sized for a maximum allowable surface water discharge rate of 5l/s for the 1 in 100-year critical storm return period with a 40% allowance for climate change. The proposed storage volume is to be attenuated through the below-ground cellular tank and permeable paving within the application site.
- 2.9 The proposed surface water drainage is to connect to the existing foul water manhole to the west of

the Site which is to be reinstated to a combined drainage system. The proposed connection is subject to third party's approval.

- 2.10 Location and size of the proposed attenuation storage systems are subject to coordination with the landscaping proposal, site levels and other proposed works.
- 2.11 Further investigation should take place to confirm the outfall of the existing drainage network and infiltration rates.
- 2.12 It is noted that the proposed drainage system does not include the access road to the west of the Site (Argents Mead) as it has existing adequate drainage in place. The existing arrangements indicate the road is drained via road gullies.
- 2.13 The proposed Drainage Strategy for the application site is presented is presented in **Appendix C** with the blue-line boundary as the supplication site boundary.

3 Conclusions and Recommendations

- 3.1 This report has been carried out to provide details of the Site drainage calculations in respect of planning application 23/01203/FUL.
- 3.2 Based on the assessment in this report, our conclusions are as follows:
- The proposed application Site boundary extends to an area of approximately 0.214 ha.
 - The risk of flooding from surface water, sewers, groundwater and artificial sources is low.
 - The existing access road (Argents Mead) to the west of the Site has existing adequate drainage in place and does not form part of the proposed drainage design. The road area of 0.069ha is therefore excluded from the drainage calculations, leaving the site catchment drainage area of 0.335ha.
 - As the greenfield run-off rates are very low, to reduce the risk of blockage in the drainage system, the proposed surface water drainage for the Site has been designed based on 5 l/s.
 - The average attenuation storage for the Site is 140m³ which will be accommodated with attenuation tanks and permeable paving. The attenuation storage volumes are calculated based on a maximum allowable surface water discharge rate of 5 l/s for the 1 in 100 year critical storm return period with 40% allowance for climate change.
 - The proposed surface water drainage is to connect to the existing foul water manhole to the west of the Site which is to be reinstated to a combined drainage system. The proposed connection is subject to third party's approval.
 - Future maintenance for any private drainage systems would be under the responsibility of the Site owner or an appointment management company.

APPENDICES


A. Site Location Plan

Appendices

Hinckley Day Care

Project Number: WIE19849

Document Reference: WIE19849-100-3-1-3-TN Enabling



PROPOSED ATTENUATION TANK:

- STORAGE VOLUME: 140m³ (APPROX.). SEE NOTE 11
- DEPTH OF TANK: 1.02m
- COVER LEVEL OF GROUND: 122.00 (ASSUMED) WITH MINIMUM 800mm COVER)
- INVERT LEVEL OF BASE OF TANK: 118.840
- PRODUCT: HYDRO INTERNATIONAL'S STORMBLOC EXTRA OR SIMILAR APPROVED

PROPOSED MANHOLE WITH FLOW CONTROL DEVICE (HYDROBRAKE)
DISCHARGE RATE 5.0l/s (SEE NOTE 11)

SW10 (WITH HYDRO-BRAKE)
CL: 120.350 (ASSUMED)
IL: 118.777
SIZE: 1,500mmØ

SW11
CL: 120.000 (ASSUMED)
IL: 118.665
SIZE: 1,350mm

SW05
CL: 120.200 (ASSUMED)
IL: 119.085
SIZE: 1,350mm

SW04
CL: 120.200 (ASSUMED)
IL: 119.242
SIZE: 1,350mm

SW12
CL: 120.000 (ASSUMED)
IL: 118.448
SIZE: 1,350mm

PROPOSED SURFACE WATER AND FOUL WATER DRAINAGE CONNECTION TO EXISTING FOUL WATER MANHOLE. THIS MANHOLE AND THE ASSOCIATED OUTGOING PIPE TO BE REINSTATED TO A COMBINED DRAINAGE SYSTEM. SEE NOTE 13.

EX MH
CL: 120.070
IL: 118.390
SIZE: 1,350mm

SW09
CL: 120.400 (ASSUMED)
IL: 118.981
SIZE: 1,350mm

SW03
CL: 120.200 (ASSUMED)
IL: 119.353
SIZE: 1,200mm

SW02
CL: 120.450 (ASSUMED)
IL: 119.423
SIZE: 1,200mm

PROPOSED OIL SEPARATOR

SW08
CL: 122.000 (ASSUMED)
IL: 119.142
SIZE: 1,200mm

SW07
CL: 122.000 (ASSUMED)
IL: 119.288
SIZE: 1,200mm

SW06
CL: 122.000 (ASSUMED)
IL: 119.550
SIZE: 1,200mm

SW01
CL: 120.450 (ASSUMED)
IL: 119.550
SIZE: 1,200mm

This drawing should not be scaled. Dimensions to be verified on site.
Any discrepancies should be referred to the Engineer prior to work being put in hand.
This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited
Pickfords Wharf, Clink Street, London SE1 1UG 020 7928 7888 03333 444 501

GENERAL NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
3. THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND REGULATIONS.
5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES.
6. THE PROPOSED ARCHITECTS LAYOUT IS BASED ON THE DESIGN BUREAU'S DRAWING "1782-DBC-ZZ-00-DR-A-0100" REV P06 DATED 12.07.2023.
7. THE TOPOGRAPHICAL SURVEY INFORMATION IS BASED ON SURVEY SOLUTIONS DRAWING "24422v-01" DATED 24/05/19.
8. THE EXISTING UTILITY SURVEY INFORMATION IS BASED ON C L B SURVEY LTD'S DRAWING "JAZ3-4892-1" DATED JANUARY 2023.
9. THE EXISTING PUBLIC SEWER INFORMATION IS BASED ON SEVERN TRENT'S SEWER RECORD PLAN.
10. CATCHMENT AREA IS CALCULATED BASED ON ASSUMED IMPERMEABILITY COEFFICIENTS OF 0.20 AND 0.95 FOR PERMEABLE AND IMPERMEABLE AREAS RESPECTIVELY. THE APPROXIMATE OVERALL EFFECTIVE IMPERMEABLE AREA FOR THE SITE IS 0.319ha.
11. THE PROPOSED OVERALL ATTENUATION STORAGE VOLUME OF 140m³ IS SIZED BASED ON A MAXIMUM ALLOWABLE SURFACE WATER DISCHARGE RATE OF 5 L/S FOR THE 1 IN 100 YEAR CRITICAL STORM RETURN PERIOD WITH 40% ALLOWANCE FOR CLIMATE CHANGE. ALLOWANCE FOR CLIMATE CHANGE.
12. THE LOCATION AND SIZE OF THE PROPOSED ATTENUATION STORAGE SYSTEMS & PROPOSED LINEAR DRAINAGE CHANNELS ARE SUBJECT TO COORDINATION WITH THE LANDSCAPING PROPOSAL AND OTHER PROPOSED WORKS.
13. THE PROPOSED SURFACE WATER DRAINAGE STRATEGY IS SUBJECT TO FURTHER SITE INVESTIGATIVE WORKS AND THIRD PARTIES APPROVAL.
14. THE PROPOSED SURFACE WATER DRAINAGE STRATEGY IS BASED ON ASSUMED FINISHED FLOOR LEVELS AND EXTERNAL LEVELS.
15. THE PROPOSED FINISHED FLOOR LEVELS AND EXTERNAL LEVELS ARE BASED ON INFORMATION RECEIVED FROM NHS PROPERTY SERVICES.

KEY

- REDLINE BOUNDARY
- BLUELINE BOUNDARY
- EXISTING FOUL WATER DRAINAGE (SEE NOTE 8)
- EXISTING SURFACE WATER DRAINAGE (SEE NOTE 8)
- EXISTING PRIVATE COMBINED WATER DRAINAGE (SEE NOTE 8)
- EXISTING PUBLIC COMBINED WATER SEWER (SEE NOTE 8)
- PROPOSED COMBINED SEWER
- PROPOSED SURFACE WATER DRAINAGE
- PROPOSED OIL SEPARATOR
- PROPOSED ATTENUATION TANK
- PROPOSED PERMEABLE PAVING

Rev	Date	Description	By	Chk
A01	14.03.24	FIRST ISSUE	SM	PE

Project
HINCKLEY CDC AND ENDOSCOPY


PROPOSED SURFACE WATER DRAINAGE STRATEGY CAR PARK ENABLING WORKS

Client
NHS PROPERTY SERVICES



5th Floor, One Cornwall Street, Birmingham, B3 2DX
T: 0121 212 7700
mail@watermangroup.com www.watermangroup.com

Work Stage	STAGE 2 Concept design	RIBA
Subsidiary	PRELIMINARY	
Designed By	RB	Director
Drawn By	RL	Date
Project	Originator Functional Spatial Form Discipline Number	Revision
19849-WIE-ZZ-XX-DR-D-92-003		A02



B. Drainage Strategy Calculations

Appendices

Hinckley Day Care

Project Number: WIE19849

Document Reference: WIE19849-100-3-1-3-TN Enabling

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 30/05/2023 11:14 File	Designed by BMRL1 Checked by	
Innovyze		Source Control 2020.1.3
<u>ICP SUDS Mean Annual Flood</u> Input Return Period (years) 10 Soil 0.450 Area (ha) 0.335 Urban 0.000 SAAR (mm) 700 Region Number Region 4 Results 1/s QBAR Rural 1.8 QBAR Urban 1.8 Q10 years 2.7 Q1 year 1.5 Q30 years 3.5 Q100 years 4.6		
©1982-2020 Innovyze		

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			


Inlets

Junction	Inlet Name	Incoming Item(s)	Bypass Destination	Capacity Type
SW01	Inlet	Catchment Area	(None)	No Restriction
SW02	Inlet	1.000	(None)	No Restriction
SW04	Inlet	1.002	(None)	No Restriction
	Inlet (1)	Catchment Area (4)	(None)	No Restriction
SW06	Inlet	Catchment Area (2)	(None)	No Restriction
SW07	Inlet	2.000	(None)	No Restriction
	Inlet (1)	Catchment Area (3)	(None)	No Restriction
SW08	Inlet	2.001	(None)	No Restriction
	Inlet (1)	Catchment Area (5)	(None)	No Restriction
SW09	Inlet (2)	2.002 1.004	(None)	No Restriction
SW05	Inlet	1.003 Catchment Area (6) Catchment Area (7)	(None)	No Restriction
SW10 WITH HB	Inlet (3)	1.006	(None)	No Restriction
SW11	Inlet	1.007	(None)	No Restriction
EX MH	Inlet	1.009	(None)	No Restriction
SW12	Inlet	1.008	(None)	No Restriction
SW03	Inlet	1.001 Catchment Area (1)	(None)	No Restriction

Outlets

Junction	Outlet Name	Outgoing Connection	Outlet Type
SW01	Outlet	1.000	Free Discharge
SW02	Outlet	1.001	Free Discharge
SW04	Outlet	1.003	Free Discharge
SW06	Outlet	2.000	Free Discharge
SW07	Outlet	2.001	Free Discharge
SW08	Outlet	2.002	Free Discharge
SW09	Outlet	1.005	Free Discharge
SW05	Outlet	1.004	Free Discharge
	Outlet	1.007	Hydro-Brake®

Invert Level (m)	118.777
Design Depth (m)	1.297
Design Flow (L/s)	5.0
Objective	Minimise Upstream Storage Requirements
Application	Surface Water Only
Sump Available	☐
Unit Reference	CHE-0096-5000-1297-5000



SW11	Outlet	1.008	Free Discharge
SW12	Outlet	1.009	Free Discharge
SW03	Outlet	1.002	Free Discharge

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Stormwater Controls Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



TANK

Type : Cellular Storage

Inlets

Inlet

Inlet Type	Point Inflow
Incoming Item(s)	1.005
Bypass Destination	(None)
Capacity Type	No Restriction

Outlets

Outlet

Outgoing Connection	1.006
Outlet Type	Free Discharge

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Connections Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Name	Length (m)	Connection Type	Slope (1:X)	Manning's n	Colebrook-White Roughness (mm)	Diameter / Base Width (mm)	Upstream Cover Level (m)	Upstream Invert Level (m)
2.000	23.510	Pipe	89.734		0.6	225	122.000	119.550
2.001	13.139	Pipe	89.996		0.6	300	122.000	119.288
2.002	14.348	Pipe	89.119		0.6	300	122.000	119.142
1.007	17.327	Pipe	154.708		0.6	375	120.350	118.777
1.000	19.612	Pipe	154.422		0.6	225	120.450	119.550
1.003	24.208	Pipe	154.192		0.6	375	120.200	119.242
1.004	16.025	Pipe	154.084		0.6	375	120.200	119.085
1.006	9.814	Pipe	155.778		0.6	375	122.000	118.840
1.005	6.310	Pipe	44.755		0.6	375	120.400	118.981
1.008	33.505	Pipe	154.402		0.6	375	120.000	118.665
1.009	5.038	Pipe	86.859		0.6	375	120.000	118.448
1.001	10.757	Pipe	153.669		0.6	225	120.450	119.423
1.002	17.156	Pipe	154.559		0.6	300	120.200	119.353

Name	Downstream Cover Level (m)	Downstream Invert Level (m)	Lock	Flow Restriction (L/s)	Velocity (m/s)
2.000	122.000	119.288	All		
2.001	122.000	119.142	All		
2.002	120.400	118.981	All		
1.007	120.000	118.665	All	5.0	
1.000	120.450	119.423	All		
1.003	120.200	119.085	All		
1.004	120.400	118.981	All		
1.006	120.350	118.777	All		
1.005	121.500	118.840	All		
1.008	120.000	118.448	All		
1.009	120.070	118.390	All		
1.001	120.200	119.353	All		
1.002	120.200	119.242	All		

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Manhole Schedule Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Name	Cover Level (m) Invert Level (m)	Manhole Size (m)	Connection Details				Type
Coordinates (m)	Depth (m)		Incoming Connections	Connection Type	Connection Invert (m)	Connection Size (mm)	Junction Type
			Outgoing Connections				Cover
SW01	120.450 119.550	Diameter / Length: 1.200					Manhole - Access Required
E:442927.129 N:293684.786	0.900						
			{a} 1.000	Pipe	119.550	Diam/Width:225	Not Applicable
SW02	120.450 119.423	Diameter / Length: 1.200	{1} 1.000	Pipe	119.423	Diam/Width:225	Manhole - Access Required
E:442908.029 N:293680.338	1.027						
			{a} 1.001	Pipe	119.423	Diam/Width:225	Not Applicable
SW04	120.200 119.242	Diameter / Length: 1.350	{1} 1.002	Pipe	119.242	Diam/Width:300	Manhole - Access Required
E:442897.791 N:293704.496	0.958						
			{a} 1.003	Pipe	119.242	Diam/Width:375	Not Applicable
SW06	122.000 119.550	Diameter / Length: 1.200					Manhole - Access Required
E:442932.994 N:293699.767	2.450						
			{a} 2.000	Pipe	119.550	Diam/Width:225	Not Applicable
SW07	122.000 119.288	Diameter / Length: 1.200	{1} 2.000	Pipe	119.288	Diam/Width:225	Manhole - Access Required
E:442929.944 N:293723.079	2.712						
			{a} 2.001	Pipe	119.288	Diam/Width:300	Not Applicable

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Manhole Schedule Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Name	Cover Level (m) Invert Level (m)	Manhole Size (m)	Connection Details				Type
Coordinates (m)	Depth (m)		Incoming Connections	Connection Type	Connection Invert (m)	Connection Size (mm)	Junction Type
			Outgoing Connections				Cover
SW08	122.000 119.142	Diameter / Length: 1.200	{1} 2.001	Pipe	119.142	Diam/Width:300	Manhole - Access Required
E:442928.440 N:293736.132	2.858						
			{a} 2.002	Pipe	119.142	Diam/Width:300	Not Applicable
SW09	120.400 118.981	Diameter / Length: 1.350	{1} 2.002	Pipe	118.981	Diam/Width:300	Manhole - Access Required
E:442914.144 N:293734.918	1.419		{2} 1.004	Pipe	118.981	Diam/Width:375	
			{a} 1.005	Pipe	118.981	Diam/Width:375	Not Applicable
SW05	120.200 119.085	Diameter / Length: 1.350	{1} 1.003	Pipe	119.085	Diam/Width:375	Manhole - Access Required
E:442899.395 N:293728.651	1.115						
			{a} 1.004	Pipe	119.085	Diam/Width:375	Not Applicable
SW10 WITH HB	120.350 118.777	Diameter / Length: 1.500	{1} 1.006	Pipe	118.777	Diam/Width:375	Manhole
E:442902.935 N:293736.447	1.573						
			{a} 1.007	Pipe	118.777	Diam/Width:375	Not Applicable
SW11	120.000 118.665	Diameter / Length: 1.350	{1} 1.007	Pipe	118.665	Diam/Width:375	Manhole - Access Required
E:442888.423 N:293726.978	1.335						
			{a} 1.008	Pipe	118.665	Diam/Width:375	Not Applicable

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023		
Report Details: Type: Manhole Schedule Storm Phase: Phase		Designed by: RB	Checked by: SS	
		Approved By: SS		
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX		

Name	Cover Level (m) Invert Level (m)	Manhole Size (m)	Connection Details				Type	
Coordinates (m)	Depth (m)		Incoming Connections	Connection Type	Connection Invert (m)	Connection Size (mm)	Junction Type	
			Outgoing Connections				Cover	
EX MH	120.070 118.390	Diameter / Length: 1.350	{1} 1.009	Pipe	118.390	Diam/Width:375	Manhole - Access Required - Sealed	
E:442892.264 N:293688.834	1.680							Not Applicable
SW12	120.000 118.448	Diameter / Length: 1.350	{1} 1.008	Pipe	118.448	Diam/Width:375	Manhole - Access Required	
E:442893.102 N:293693.801	1.552							
			{a} 1.009	Pipe	118.448	Diam/Width:375		Not Applicable
SW03	120.200 119.353	Diameter / Length: 1.200	{1} 1.001	Pipe	119.353	Diam/Width:225	Manhole - Access Required	
E:442899.986 N:293687.481	0.847							
			{a} 1.002	Pipe	119.353	Diam/Width:300		Not Applicable

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Inflow Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Inflow Label	Connected To	Flow (L/s)	Runoff Method	Area (ha)	Percentage Impervious (%)	Urban Creep (%)	Adjusted Percentage Impervious (%)	Area Analysed (ha)
Catchment Area	SW01		Time of Concentration	0.029	95	0	95	0.027
Catchment Area (1)	SW03		Time of Concentration	0.045	95	0	95	0.043
Catchment Area (2)	SW06		Time of Concentration	0.075	95	0	95	0.071
Catchment Area (3)	SW07		Time of Concentration	0.046	95	0	95	0.043
Catchment Area (4)	SW04		Time of Concentration	0.019	95	0	95	0.018
Catchment Area (5)	SW08		Time of Concentration	0.062	95	0	95	0.059
Catchment Area (6)	SW05		Time of Concentration	0.045	95	0	95	0.042
Catchment Area (7)	SW05		Time of Concentration	0.015	95	0	95	0.015
TOTAL		0.0		0.336				0.319

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Network Design Report Storm Phase: Phase Flow Path: Path 1.000		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Name	Time Of Travel (mins)	Rainfall Intensity (mm/hr)	Total Area (ha)	Total Impermeable Area (ha)	Proportional Depth (mm)	Proportional Velocity (m/s)	Full Bore Velocity (m/s)	Capacity (L/s)
1.000	5.31	158.537	0.029	0.027	81	0.904	1.050	41.7368
1.001	5.48	156.667	0.029	0.027	81	0.905	1.052	41.8402
1.002	5.71	154.265	0.074	0.070	118	1.133	1.262	89.2213
1.003	5.99	151.451	0.093	0.088	120	1.183	1.457	160.8895
1.004	6.17	149.660	0.153	0.145	156	1.347	1.457	160.9464
Branch: 2.000								
2.000	5.28	158.846	0.075	0.071	120	1.419	1.381	54.9056
2.001	5.42	157.384	0.121	0.115	135	1.586	1.658	117.1999
2.002	5.56	155.833	0.183	0.174	172	1.753	1.666	117.7798
1.005	6.21	149.288	0.336	0.319	172	2.616	2.715	299.8391
1.006	6.32	148.218	0.336	0.319	256	1.605	1.449	160.0611
1.007	6.52	146.381	0.336	0.319	255	1.609	1.454	160.6189
1.008	6.90	142.992	0.336	0.319	255	1.611	1.456	160.7789
1.009	6.95	142.623	0.336	0.319	210	2.029	1.945	214.8287

Name	Flow (L/s)
1.000	11.7156
1.001	11.7156
1.002	29.1810
1.003	36.0886
1.004	58.7751
Branch: 2.000	
2.000	30.7380
2.001	48.9389
2.002	73.3266
1.005	128.8756
1.006	128.8756
1.007	128.8756
1.008	128.8756
1.009	128.8756

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design	Date: 01/06/2023	
Report Details: Type: Network Design Criteria Storm Phase: Phase	Designed by: RB Checked by: SS Approved By: SS	
Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX		

Flow Options

Peak Flow Calculation	(UK) Modified Rational Method
Min. Time of Entry (mins)	5
Max. Travel Time (mins)	30

Rain 1

Type: FSR

Return Period (years)	100.0
Region	England And Wales
M5-60 (mm)	19.8
Ratio R	0.400

Pipe Options

Lock Slope Options	None
Design Level	Level Inverts
Min. Cover Depth (m)	1.200
Min. Slope (1:X)	500.00
Max. Slope (1:X)	40.00
Min. Velocity (m/s)	1.0
Max. Velocity (m/s)	3.0
Use Flow Restriction	☐
Reduce Channel Depths	☐

Manhole Options

Apply Offset	☐
An error has occurred while processing TextBox 'txtSynchroniseManholeInvertLevelsHeader': The expression contains object 'SynchroniseManholeInvertLevelsTitle' that is not defined in the current context.	
	☐

Manhole Size Library

Default

Diameter / Width

Connection (mm)	Diameter / Length (m)	Width (m)
0	1.200	0.000
375	1.350	0.000
500	1.500	0.000
750	1.800	0.000

Additional Sizing

Connection (mm)	900
Diameter / Length (m)	0.900
Width (m)	0.000

Depth

Depth (m)	Diameter / Length (m)	Width (m)
0.000	1.050	0.000
1.500	1.200	0.000

Access

Depth (m)	Ladder Protrusion (mm)
0.000	130
3.000	230

Benching Requirements

Landing Width (mm)	500
Benching Width (mm)	225

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Outfall Details Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Outfalls

Outfall	Outfall Type	Fixed Surcharged Level (m)	Level Curve
EX MH	Free Discharge		

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Title: Rainfall Analysis Criteria		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			

Runoff Type	Dynamic
Output Interval (mins)	1
Time Step	Shortest
Urban Creep	Apply Global Value
Urban Creep Global Value (%)	0
Junction Flood Risk Margin (mm)	150
Perform No Discharge Analysis	☐

Rainfall

Rain 1	Type: FSR
--------	-----------

Region	England And Wales
M5-60 (mm)	19.8
Ratio R	0.400
Summer	☒
Winter	☒

Return Period

Return Period (years)	Increase Rainfall (%)
2.0	0.000
5.0	0.000
10.0	0.000
30.0	0.000
100.0	40.000

Storm Durations

Duration (mins)	Run Time (mins)
15	30
30	60
60	120
120	240
180	360
240	480
360	720
480	960
600	1200
720	1440
960	1920
1440	2880
2160	4320

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
SW01	Rain 1: 2 years: +0 %: 15 mins: Winter	120.45 0	119.55 0	119.603	0.053	4.9	0.060	0.000	4.8	2.273	OK
SW02	Rain 1: 2 years: +0 %: 15 mins: Winter	120.45 0	119.42 3	119.474	0.051	4.8	0.058	0.000	4.8	2.264	OK
SW04	Rain 1: 2 years: +0 %: 15 mins: Winter	120.20 0	119.24 2	119.320	0.078	15.4	0.111	0.000	15.4	7.307	OK
SW06	Rain 1: 2 years: +0 %: 15 mins: Winter	122.00 0	119.55 0	119.625	0.075	12.9	0.085	0.000	12.7	5.949	OK
SW07	Rain 1: 2 years: +0 %: 15 mins: Winter	122.00 0	119.28 8	119.379	0.091	20.5	0.103	0.000	20.2	9.554	OK
SW08	Rain 1: 2 years: +0 %: 15 mins: Winter	122.00 0	119.14 2	119.256	0.114	30.9	0.128	0.000	30.5	14.462	OK
SW09	Rain 1: 2 years: +0 %: 15 mins: Winter	120.40 0	118.98 1	119.106	0.125	55.6	0.180	0.000	55.8	26.482	OK
SW05	Rain 1: 2 years: +0 %: 15 mins: Winter	120.20 0	119.08 5	119.194	0.109	25.2	0.156	0.000	25.3	12.039	OK
SW10 WITH HB	Rain 1: 2 years: +0 %: 120 mins: Winter	120.35 0	118.77 7	119.074	0.297	4.8	0.525	0.000	4.6	45.411	OK
SW11	Rain 1: 2 years: +0 %: 180 mins: Winter	120.00 0	118.66 5	118.709	0.044	4.6	0.064	0.000	4.6	56.844	OK
EX MH	Rain 1: 2 years: +0 %: 180 mins: Winter	120.07 0	118.39 0	118.428	0.038	4.6	0.000	0.000	4.6	56.808	OK
SW12	Rain 1: 2 years: +0 %: 180 mins: Winter	120.00 0	118.44 8	118.488	0.040	4.6	0.057	0.000	4.6	56.808	OK
SW03	Rain 1: 2 years: +0 %: 15 mins: Winter	120.20 0	119.35 3	119.431	0.078	12.4	0.088	0.000	12.2	5.810	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 5 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
SW01	Rain 1: 5 years: +0 %: 15 mins: Winter	120.450	119.550	119.611	0.061	6.3	0.069	0.000	6.2	2.927	OK
SW02	Rain 1: 5 years: +0 %: 15 mins: Winter	120.450	119.423	119.481	0.058	6.2	0.066	0.000	6.2	2.918	OK
SW04	Rain 1: 5 years: +0 %: 15 mins: Winter	120.200	119.242	119.331	0.089	19.9	0.127	0.000	19.9	9.409	OK
SW06	Rain 1: 5 years: +0 %: 15 mins: Winter	122.000	119.550	119.637	0.087	16.6	0.098	0.000	16.4	7.664	OK
SW07	Rain 1: 5 years: +0 %: 15 mins: Winter	122.000	119.288	119.395	0.107	26.5	0.121	0.000	26.1	12.308	OK
SW08	Rain 1: 5 years: +0 %: 15 mins: Winter	122.000	119.142	119.275	0.133	39.8	0.150	0.000	39.3	18.636	OK
SW09	Rain 1: 5 years: +0 %: 120 mins: Winter	120.400	118.981	119.175	0.194	22.8	0.277	0.000	22.9	65.615	OK
SW05	Rain 1: 5 years: +0 %: 15 mins: Winter	120.200	119.085	119.211	0.126	32.6	0.180	0.000	32.7	15.524	OK
SW10 WITH HB	Rain 1: 5 years: +0 %: 120 mins: Winter	120.350	118.777	119.175	0.398	5.0	0.703	0.000	4.6	40.898	Surcharged
SW11	Rain 1: 5 years: +0 %: 480 mins: Winter	120.000	118.665	118.709	0.044	4.6	0.064	0.000	4.6	92.848	OK
EX MH	Rain 1: 5 years: +0 %: 480 mins: Winter	120.070	118.390	118.428	0.038	4.6	0.000	0.000	4.6	92.845	OK
SW12	Rain 1: 5 years: +0 %: 480 mins: Winter	120.000	118.448	118.488	0.040	4.6	0.057	0.000	4.6	92.845	OK
SW03	Rain 1: 5 years: +0 %: 15 mins: Winter	120.200	119.353	119.443	0.090	15.9	0.101	0.000	15.7	7.481	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
SW01	Rain 1: 10 years: +0 %: 15 mins: Winter	120.45 0	119.55 0	119.616	0.066	7.4	0.074	0.000	7.3	3.400	OK
SW02	Rain 1: 10 years: +0 %: 15 mins: Winter	120.45 0	119.42 3	119.487	0.064	7.3	0.072	0.000	7.2	3.390	OK
SW04	Rain 1: 10 years: +0 %: 15 mins: Winter	120.20 0	119.24 2	119.338	0.096	23.1	0.137	0.000	23.1	10.934	OK
SW06	Rain 1: 10 years: +0 %: 15 mins: Winter	122.00 0	119.55 0	119.645	0.095	19.3	0.107	0.000	19.1	8.901	OK
SW07	Rain 1: 10 years: +0 %: 15 mins: Winter	122.00 0	119.28 8	119.405	0.117	30.8	0.133	0.000	30.3	14.300	OK
SW08	Rain 1: 10 years: +0 %: 15 mins: Winter	122.00 0	119.14 2	119.288	0.146	46.2	0.165	0.000	45.7	21.656	OK
SW09	Rain 1: 10 years: +0 %: 120 mins: Winter	120.40 0	118.98 1	119.242	0.261	26.8	0.373	0.000	26.6	75.976	OK
SW05	Rain 1: 10 years: +0 %: 120 mins: Winter	120.20 0	119.08 5	119.242	0.157	12.2	0.224	0.000	12.3	34.857	OK
SW10 WITH HB	Rain 1: 10 years: +0 %: 120 mins: Winter	120.35 0	118.77 7	119.242	0.465	5.2	0.821	0.000	4.6	36.722	Surcharged
SW11	Rain 1: 10 years: +0 %: 720 mins: Summer	120.00 0	118.66 5	118.709	0.044	4.6	0.064	0.000	4.6	105.846	OK
EX MH	Rain 1: 10 years: +0 %: 720 mins: Summer	120.07 0	118.39 0	118.428	0.038	4.6	0.000	0.000	4.6	105.844	OK
SW12	Rain 1: 10 years: +0 %: 720 mins: Summer	120.00 0	118.44 8	118.488	0.040	4.6	0.057	0.000	4.6	105.844	OK
SW03	Rain 1: 10 years: +0 %: 15 mins: Winter	120.20 0	119.35 3	119.450	0.097	18.5	0.110	0.000	18.2	8.692	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Depth

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
SW01	Rain 1: 30 years: +0 %: 15 mins: Winter	120.45 0	119.55 0	119.625	0.075	9.3	0.084	0.000	9.2	4.312	OK
SW02	Rain 1: 30 years: +0 %: 15 mins: Winter	120.45 0	119.42 3	119.498	0.075	9.2	0.084	0.000	9.1	4.301	OK
SW04	Rain 1: 30 years: +0 %: 180 mins: Winter	120.20 0	119.24 2	119.370	0.128	7.0	0.183	0.000	7.0	30.170	OK
SW06	Rain 1: 30 years: +0 %: 15 mins: Winter	122.00 0	119.55 0	119.660	0.110	24.4	0.124	0.000	24.2	11.288	OK
SW07	Rain 1: 30 years: +0 %: 15 mins: Winter	122.00 0	119.28 8	119.425	0.137	39.0	0.154	0.000	38.5	18.133	OK
SW08	Rain 1: 30 years: +0 %: 180 mins: Winter	122.00 0	119.14 2	119.370	0.228	13.9	0.258	0.000	13.9	59.416	OK
SW09	Rain 1: 30 years: +0 %: 180 mins: Winter	120.40 0	118.98 1	119.370	0.389	25.4	0.557	0.000	24.6	107.345	Surcharged
SW05	Rain 1: 30 years: +0 %: 180 mins: Winter	120.20 0	119.08 5	119.370	0.285	11.6	0.408	0.000	11.6	49.161	OK
SW10 WITH HB	Rain 1: 30 years: +0 %: 180 mins: Winter	120.35 0	118.77 7	119.370	0.593	5.1	1.048	0.000	4.6	60.629	Surcharged
SW11	Rain 1: 30 years: +0 %: 960 mins: Winter	120.00 0	118.66 5	118.709	0.044	4.6	0.064	0.000	4.6	158.785	OK
EX MH	Rain 1: 30 years: +0 %: 960 mins: Winter	120.07 0	118.39 0	118.428	0.038	4.6	0.000	0.000	4.6	158.783	OK
SW12	Rain 1: 30 years: +0 %: 960 mins: Winter	120.00 0	118.44 8	118.488	0.040	4.6	0.057	0.000	4.6	158.783	OK
SW03	Rain 1: 30 years: +0 %: 15 mins: Winter	120.20 0	119.35 3	119.464	0.111	23.5	0.126	0.000	23.1	11.026	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Junctions Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 100 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Depth

Junction	Storm Event	Cover Level (m)	Invert Level (m)	Max. Level (m)	Max. Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Status
SW01	Rain 1: 100 years: +40 %: 240 mins: Winter	120.45 0	119.55 0	120.175	0.625	3.2	0.707	0.000	3.2	18.415	Surcharged
SW02	Rain 1: 100 years: +40 %: 240 mins: Winter	120.45 0	119.42 3	120.175	0.752	3.2	0.850	0.000	3.2	18.398	Surcharged
SW04	Rain 1: 100 years: +40 %: 240 mins: Winter	120.20 0	119.24 2	120.175	0.933	10.2	1.335	0.000	9.4	56.712	Flood Risk
SW06	Rain 1: 100 years: +40 %: 240 mins: Winter	122.00 0	119.55 0	120.175	0.625	8.4	0.707	0.000	8.4	47.889	Surcharged
SW07	Rain 1: 100 years: +40 %: 240 mins: Winter	122.00 0	119.28 8	120.175	0.887	13.5	1.003	0.000	12.9	75.940	Surcharged
SW08	Rain 1: 100 years: +40 %: 240 mins: Winter	122.00 0	119.14 2	120.175	1.033	19.6	1.168	0.000	18.7	114.003	Surcharged
SW09	Rain 1: 100 years: +40 %: 240 mins: Winter	120.40 0	118.98 1	120.175	1.194	32.3	1.708	0.000	31.8	203.100	Surcharged
SW05	Rain 1: 100 years: +40 %: 240 mins: Winter	120.20 0	119.08 5	120.175	1.090	15.5	1.559	0.000	13.8	91.984	Flood Risk
SW10 WITH HB	Rain 1: 100 years: +40 %: 240 mins: Winter	120.35 0	118.77 7	120.175	1.398	5.3	2.469	0.000	5.1	109.389	Surcharged
SW11	Rain 1: 100 years: +40 %: 240 mins: Winter	120.00 0	118.66 5	118.712	0.047	5.1	0.067	0.000	5.1	109.120	OK
EX MH	Rain 1: 100 years: +40 %: 240 mins: Winter	120.07 0	118.39 0	118.430	0.040	5.1	0.000	0.000	5.1	108.963	OK
SW12	Rain 1: 100 years: +40 %: 240 mins: Winter	120.00 0	118.44 8	118.490	0.042	5.1	0.060	0.000	5.1	108.963	OK
SW03	Rain 1: 100 years: +40 %: 240 mins: Winter	120.20 0	119.35 3	120.175	0.822	8.2	0.930	0.000	8.1	46.409	Flood Risk

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
TANK	Rain 1: 2 years: +0 %: 120 mins: Winter	119.074	119.074	0.234	0.234	18.5	32.031	0.000	0.000	4.8	45.730	77.391	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 5 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
TANK	Rain 1: 5 years: +0 %: 120 mins: Winter	119.175	119.175	0.335	0.335	22.9	45.787	0.000	0.000	5.0	41.668	67.682	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
TANK	Rain 1: 10 years: +0 %: 120 mins: Winter	119.242	119.242	0.402	0.402	26.6	54.939	0.000	0.000	5.2	37.842	61.222	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023		
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Designed by: RB	Checked by: SS	
		Approved By: SS		
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX		



Rain 1: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
TANK	Rain 1: 30 years: +0 %: 180 mins: Winter	119.370	119.370	0.530	0.530	24.6	72.500	0.000	0.000	5.1	61.887	48.827	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Stormwater Controls Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 100 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Avg. Depth

Stormwater Control	Storm Event	Max. US Level (m)	Max. DS Level (m)	Max. US Depth (m)	Max. DS Depth (m)	Max. Inflow (L/s)	Max. Resident Volume (m³)	Max. Flooded Volume (m³)	Total Lost Volume (m³)	Max. Outflow (L/s)	Total Discharge Volume (m³)	Percentage Available (%)	Status
TANK	Rain 1: 100 years: +40 %: 240 mins: Winter	120.175	120.175	1.335	1.335	31.8	139.884	0.000	0.000	5.3	111.572	1.265	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Connections Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
2.000	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW06	SW07	122.000	119.625	0.083	5.949	1.0	0.23	12.7	OK
2.001	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW07	SW08	122.000	119.379	0.103	9.554	1.0	0.17	20.2	OK
2.002	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW08	SW09	122.000	119.256	0.119	14.462	1.2	0.26	30.5	OK
1.007	Rain 1: 2 years: +0 %: 180 mins: Winter	Pipe	SW10 WITH HB	SW11	120.350	119.066	0.044	56.891	0.6	0.03	4.6	OK
1.000	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW01	SW02	120.450	119.603	0.052	2.273	0.7	0.12	4.8	OK
1.003	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW04	SW05	120.200	119.320	0.093	7.307	0.7	0.1	15.4	OK
1.004	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW05	SW09	120.200	119.194	0.117	12.039	0.9	0.16	25.3	OK
1.006	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	TANK	SW10 WITH HB	122.000	119.008	0.199	5.615	0.4	0.03	5.5	OK
1.005	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW09	TANK	120.400	119.106	0.121	26.482	2.7	0.19	55.8	OK
1.008	Rain 1: 2 years: +0 %: 180 mins: Winter	Pipe	SW11	SW12	120.000	118.709	0.042	56.844	0.7	0.03	4.6	OK
1.009	Rain 1: 2 years: +0 %: 180 mins: Winter	Pipe	SW12	EX MH	120.000	118.488	0.039	56.808	0.8	0.02	4.6	OK
1.001	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW02	SW03	120.450	119.474	0.064	2.264	0.5	0.11	4.8	OK
1.002	Rain 1: 2 years: +0 %: 15 mins: Winter	Pipe	SW03	SW04	120.200	119.431	0.078	5.810	0.8	0.14	12.2	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Connections Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 5 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
2.000	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW06	SW07	122.000	119.637	0.097	7.664	1.0	0.3	16.4	OK
2.001	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW07	SW08	122.000	119.395	0.120	12.308	1.0	0.22	26.1	OK
2.002	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW08	SW09	122.000	119.275	0.139	18.636	1.2	0.33	39.3	OK
1.007	Rain 1: 5 years: +0 %: 480 mins: Winter	Pipe	SW10 WITH HB	SW11	120.350	119.061	0.044	92.852	0.6	0.03	4.6	OK
1.000	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW01	SW02	120.450	119.611	0.059	2.927	0.7	0.15	6.2	OK
1.003	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW04	SW05	120.200	119.331	0.107	9.409	0.8	0.12	19.9	OK
1.004	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW05	SW09	120.200	119.211	0.136	15.524	0.9	0.2	32.7	OK
1.006	Rain 1: 5 years: +0 %: 15 mins: Summer	Pipe	TANK	SW10 WITH HB	122.000	119.033	0.224	6.116	0.4	0.04	6.7	OK
1.005	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW09	TANK	120.400	119.127	0.152	33.888	2.8	0.24	71.6	OK
1.008	Rain 1: 5 years: +0 %: 480 mins: Winter	Pipe	SW11	SW12	120.000	118.709	0.042	92.848	0.7	0.03	4.6	OK
1.009	Rain 1: 5 years: +0 %: 480 mins: Winter	Pipe	SW12	EX MH	120.000	118.488	0.039	92.845	0.8	0.02	4.6	OK
1.001	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW02	SW03	120.450	119.481	0.074	2.918	0.5	0.15	6.2	OK
1.002	Rain 1: 5 years: +0 %: 15 mins: Winter	Pipe	SW03	SW04	120.200	119.443	0.089	7.481	0.9	0.18	15.7	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Connections Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 10 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
2.000	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW06	SW07	122.000	119.645	0.106	8.901	1.0	0.35	19.1	OK
2.001	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW07	SW08	122.000	119.405	0.132	14.300	1.0	0.26	30.3	OK
2.002	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW08	SW09	122.000	119.288	0.153	21.656	1.3	0.39	45.7	OK
1.007	Rain 1: 10 years: +0 %: 600 mins: Winter	Pipe	SW10 WITH HB	SW11	120.350	119.094	0.044	113.553	0.6	0.03	4.6	OK
1.000	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW01	SW02	120.450	119.616	0.064	3.400	0.8	0.17	7.3	OK
1.003	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW04	SW05	120.200	119.338	0.117	10.934	0.8	0.14	23.1	OK
1.004	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW05	SW09	120.200	119.223	0.150	18.046	0.9	0.24	37.9	OK
1.006	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	TANK	SW10 WITH HB	122.000	119.095	0.286	6.214	0.5	0.04	6.0	OK
1.005	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW09	TANK	120.400	119.142	0.184	39.163	2.8	0.28	83.0	OK
1.008	Rain 1: 10 years: +0 %: 720 mins: Summer	Pipe	SW11	SW12	120.000	118.709	0.042	105.846	0.7	0.03	4.6	OK
1.009	Rain 1: 10 years: +0 %: 720 mins: Summer	Pipe	SW12	EX MH	120.000	118.488	0.039	105.844	0.8	0.02	4.6	OK
1.001	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW02	SW03	120.450	119.487	0.080	3.390	0.6	0.17	7.2	OK
1.002	Rain 1: 10 years: +0 %: 15 mins: Winter	Pipe	SW03	SW04	120.200	119.450	0.096	8.692	0.9	0.2	18.2	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023		
Report Details: Type: Connections Summary Storm Phase: Phase		Designed by: RB	Checked by: SS	
		Approved By: SS		
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX		



Rain 1: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
2.000	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW06	SW07	122.000	119.660	0.123	11.288	1.1	0.44	24.2	OK
2.001	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW07	SW08	122.000	119.425	0.154	18.133	1.1	0.33	38.5	OK
2.002	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW08	SW09	122.000	119.313	0.181	27.422	1.3	0.49	58.0	OK
1.007	Rain 1: 30 years: +0 %: 960 mins: Summer	Pipe	SW10 WITH HB	SW11	120.350	119.167	0.044	141.712	0.6	0.03	4.6	Surcharged
1.000	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW01	SW02	120.450	119.625	0.074	4.312	0.8	0.22	9.2	OK
1.003	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW04	SW05	120.200	119.351	0.135	13.891	0.8	0.18	29.3	OK
1.004	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW05	SW09	120.200	119.245	0.175	22.493	1.0	0.3	48.1	OK
1.006	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	TANK	SW10 WITH HB	122.000	119.167	0.359	5.201	0.5	0.04	7.0	OK
1.005	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW09	TANK	120.400	119.173	0.257	48.794	2.9	0.35	104.6	OK
1.008	Rain 1: 30 years: +0 %: 960 mins: Winter	Pipe	SW11	SW12	120.000	118.709	0.042	158.785	0.7	0.03	4.6	OK
1.009	Rain 1: 30 years: +0 %: 960 mins: Winter	Pipe	SW12	EX MH	120.000	118.488	0.039	158.783	0.8	0.02	4.6	OK
1.001	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW02	SW03	120.450	119.498	0.093	4.301	0.6	0.22	9.1	OK
1.002	Rain 1: 30 years: +0 %: 15 mins: Winter	Pipe	SW03	SW04	120.200	119.464	0.110	11.026	1.0	0.26	23.1	OK

Project: WIE19849 Hinckley Daycare Phase 1 Proposed Surface Water Drainage Design		Date: 01/06/2023			
Report Details: Type: Connections Summary Storm Phase: Phase		Designed by: RB	Checked by: SS		Approved By: SS
		Company Address: Waterman Infrastructure & Environment Ltd 5th Floor One Cornwall Street Birmingham, B3 2DX			



Rain 1: 100 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Flow

Connection	Storm Event	Connection Type	From	To	Upstream Cover Level (m)	Max. US Water Level (m)	Max. Flow Depth (m)	Discharge Volume (m³)	Max. Velocity (m/s)	Flow / Capacity	Max. Flow (L/s)	Status
2.000	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW06	SW07	122.000	119.717	0.194	20.514	1.2	0.8	44.0	OK
2.001	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW07	SW08	122.000	119.519	0.279	32.419	1.1	0.59	69.5	OK
2.002	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW08	SW09	122.000	119.469	0.300	48.125	1.5	0.88	103.7	Surcharged
1.007	Rain 1: 100 years: +40 %: 240 mins: Winter	Pipe	SW10 WITH HB	SW11	120.350	120.175	0.047	109.330	0.6	0.03	5.1	Surcharged
1.000	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW01	SW02	120.450	119.656	0.110	7.832	0.9	0.4	16.7	OK
1.003	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW04	SW05	120.200	119.415	0.251	23.962	0.9	0.33	53.3	OK
1.004	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW05	SW09	120.200	119.414	0.375	37.875	1.0	0.53	84.8	OK
1.006	Rain 1: 100 years: +40 %: 15 mins: Summer	Pipe	TANK	SW10 WITH HB	122.000	119.358	0.375	6.171	0.5	0.06	9.0	Surcharged
1.005	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW09	TANK	120.400	119.415	0.375	83.548	3.1	0.61	184.3	Surcharged
1.008	Rain 1: 100 years: +40 %: 240 mins: Winter	Pipe	SW11	SW12	120.000	118.712	0.044	109.120	0.7	0.03	5.1	OK
1.009	Rain 1: 100 years: +40 %: 240 mins: Winter	Pipe	SW12	EX MH	120.000	118.490	0.041	108.963	0.8	0.02	5.1	OK
1.001	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW02	SW03	120.450	119.538	0.137	7.821	0.7	0.4	16.6	OK
1.002	Rain 1: 100 years: +40 %: 15 mins: Winter	Pipe	SW03	SW04	120.200	119.513	0.158	19.887	1.1	0.47	42.1	OK


C. Drainage Layout Plan

Appendices

Hinckley Day Care

Project Number: WIE19849

Document Reference: WIE19849-100-3-1-3-TN Enabling



PROPOSED ATTENUATION TANK:

- STORAGE VOLUME: 140m³ (APPROX.). SEE NOTE 11
- DEPTH OF TANK: 1.02m
- COVER LEVEL OF GROUND: 122.00 (ASSUMED) WITH MINIMUM 800mm COVER)
- INVERT LEVEL OF BASE OF TANK: 118.840
- PRODUCT: HYDRO INTERNATIONAL'S STORMBLOC EXTRA OR SIMILAR APPROVED

PROPOSED MANHOLE WITH FLOW CONTROL DEVICE (HYDROBRAKE)
DISCHARGE RATE 5.0l/s (SEE NOTE 11)

SW10 (WITH HYDRO-BRAKE)
CL: 120.350 (ASSUMED)
IL: 118.777
SIZE: 1,500mmØ

SW11
CL: 120.000 (ASSUMED)
IL: 118.665
SIZE: 1,350mm

SW05
CL: 120.200 (ASSUMED)
IL: 119.085
SIZE: 1,350mm

SW04
CL: 120.200 (ASSUMED)
IL: 119.242
SIZE: 1,350mm

SW12
CL: 120.000 (ASSUMED)
IL: 118.448
SIZE: 1,350mm

PROPOSED SURFACE WATER AND FOUL WATER DRAINAGE CONNECTION TO EXISTING FOUL WATER MANHOLE. THIS MANHOLE AND THE ASSOCIATED OUTGOING PIPE TO BE REINSTATED TO A COMBINED DRAINAGE SYSTEM. SEE NOTE 13.

EX MH
CL: 120.070
IL: 118.390
SIZE: 1,350mm

SW09
CL: 120.400 (ASSUMED)
IL: 118.981
SIZE: 1,350mm

SW03
CL: 120.200 (ASSUMED)
IL: 119.353
SIZE: 1,200mm

SW02
CL: 120.450 (ASSUMED)
IL: 119.423
SIZE: 1,200mm

PROPOSED OIL SEPARATOR

SW08
CL: 122.000 (ASSUMED)
IL: 119.142
SIZE: 1,200mm

SW07
CL: 122.000 (ASSUMED)
IL: 119.288
SIZE: 1,200mm

SW06
CL: 122.000 (ASSUMED)
IL: 119.550
SIZE: 1,200mm

SW01
CL: 120.450 (ASSUMED)
IL: 119.550
SIZE: 1,200mm

This drawing should not be scaled. Dimensions to be verified on site.
Any discrepancies should be referred to the Engineer prior to work being put in hand.
This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited
Pickfords Wharf, Clink Street, London SE1 1UG 020 7928 7888 03333 444 501

GENERAL NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
2. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
3. THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
4. ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND REGULATIONS.
5. ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES.
6. THE PROPOSED ARCHITECTS LAYOUT IS BASED ON THE DESIGN BUREAU'S DRAWING "1782-DBC-ZZ-00-DR-A-0100" REV P06 DATED 12.07.2023.
7. THE TOPOGRAPHICAL SURVEY INFORMATION IS BASED ON SURVEY SOLUTIONS DRAWING "24422v-01" DATED 24/05/19.
8. THE EXISTING UTILITY SURVEY INFORMATION IS BASED ON C L B SURVEY LTD'S DRAWING "JAZ3-4892-1" DATED JANUARY 2023.
9. THE EXISTING PUBLIC SEWER INFORMATION IS BASED ON SEVERN TRENT'S SEWER RECORD PLAN.
10. CATCHMENT AREA IS CALCULATED BASED ON ASSUMED IMPERMEABILITY COEFFICIENTS OF 0.20 AND 0.95 FOR PERMEABLE AND IMPERMEABLE AREAS RESPECTIVELY. THE APPROXIMATE OVERALL EFFECTIVE IMPERMEABLE AREA FOR THE SITE IS 0.319ha.
11. THE PROPOSED OVERALL ATTENUATION STORAGE VOLUME OF 140m³ IS SIZED BASED ON A MAXIMUM ALLOWABLE SURFACE WATER DISCHARGE RATE OF 5 L/S FOR THE 1 IN 100 YEAR CRITICAL STORM RETURN PERIOD WITH 40% ALLOWANCE FOR CLIMATE CHANGE ALLOWANCE FOR CLIMATE CHANGE.
12. THE LOCATION AND SIZE OF THE PROPOSED ATTENUATION STORAGE SYSTEMS & PROPOSED LINEAR DRAINAGE CHANNELS ARE SUBJECT TO COORDINATION WITH THE LANDSCAPING PROPOSAL AND OTHER PROPOSED WORKS.
13. THE PROPOSED SURFACE WATER DRAINAGE STRATEGY IS SUBJECT TO FURTHER SITE INVESTIGATIVE WORKS AND THIRD PARTIES APPROVAL.
14. THE PROPOSED SURFACE WATER DRAINAGE STRATEGY IS BASED ON ASSUMED FINISHED FLOOR LEVELS AND EXTERNAL LEVELS.
15. THE PROPOSED FINISHED FLOOR LEVELS AND EXTERNAL LEVELS ARE BASED ON INFORMATION RECEIVED FROM NHS PROPERTY SERVICES.

KEY

- REDLINE BOUNDARY
- BLUELINE BOUNDARY
- EXISTING FOUL WATER DRAINAGE (SEE NOTE 8)
- EXISTING SURFACE WATER DRAINAGE (SEE NOTE 8)
- EXISTING PRIVATE COMBINED WATER DRAINAGE (SEE NOTE 8)
- EXISTING PUBLIC COMBINED WATER SEWER (SEE NOTE 8)
- PROPOSED COMBINED SEWER
- PROPOSED SURFACE WATER DRAINAGE
- PROPOSED OIL SEPARATOR
- PROPOSED ATTENUATION TANK
- PROPOSED PERMEABLE PAVING

Rev	Date	Description	By	Chk
A01	14.03.24	FIRST ISSUE	SM	PE

Project
HINCKLEY CDC AND ENDOSCOPY


PROPOSED SURFACE WATER DRAINAGE STRATEGY CAR PARK ENABLING WORKS

Client
NHS PROPERTY SERVICES



5th Floor, One Cornwall Street, Birmingham, B3 2DX
T: 0121 212 7700
mail@watermangroup.com www.watermangroup.com

Work Stage	STAGE 2	RIBA
Subsidiary	PRELIMINARY	
Designed By	RB	Director
Drawn By	RL	Date
Project	Originator	Functional
19849-WIE-ZZ-XX-DR-D-92-003	Revision	A02



We are Waterman, where every project matters

We deliver progressive, sustainability-driven environmental and engineering consultancy services across every sector. We think differently, and we're harnessing our collective expertise to deliver greener, healthier and well-connected communities, networks and built environments.

Based in strategic locations throughout the UK and Ireland, our team of specialists is at the forefront of tackling the climate emergency and forging a path to a Net Zero built environment.

UK & Ireland Office Locations

