



Planting Schedule: To be used throughout the site

Tree Planting:

1	Birch	8 - 10 cm girth
2	Holly	8 - 10 cm girth
3	Holly	6 - 8 cm girth
4	Hazel	6 - 8 cm girth
5	Mountain Ash	6 - 8 cm girth
6	Spotted Yew	6 - 8 cm girth
7	Red Robin	6 - 8 cm girth

Shrub Planting: To be mixed across the site

Bp	Barberry	2 - 4 cm girth
Cj	Camelia	2 - 4 cm girth
Ce	Cotoneaster	2 - 4 cm girth
Lj	Lavender	2 - 4 cm girth
Mh	Malva	2 - 4 cm girth

Hedge Planting: Hedges to be mixed with the following

Hw	Hawthorn	300mm high \ 450mm apart
Bw	Blackthorn	300mm high \ 450mm apart
Hv	Holly	300mm high \ 450mm apart

Note:

All trees and shrubs are to be planted within the first planting season after the completion of the development and in accordance with the species own specific requirements. All are to be staked with a stake one third the height of the trunk and laced with a single tie only.

For a period of 1 year from the completion of planting the contractor shall be responsible for the maintenance of the plants and shall be responsible for the die or becoming diseased. To be carried out in the first available planting season.