DC PLAN



T1. ASH. FRAXINUS EXCELSIOR. HEIGHT 15M. SPREAD 11 M DIA. 550 MM. CATEGORY (BS 5837:05) B1. AGE CLASS. MATURE. RPA. 6.6 M. (20.8 M²). MULTI-STEM @ 1M, OBTUSE FORKS WITH SOME WEAKNESS IN UNIONS BUT APPEARS SOUND AT PRESENT, SOME DEAD WOOD BUT CROWN GENERALLY GOOD. ONE BRANCH GROWING INTO SITE MAY CAUSE PROBLEMS (OBLIQUE GROWTH) HAS WEIGHT INCREASE ON UNION. BRANCH LOW INTO SITE, BUT LIFT OVER GARDENS OWING TO SHADE.
RECOMMEND. CROWN LIFT TO 5 M. TO BALANCE TREE & CROWN REDUCE OBLIQUE LIMB BY 40% TO REDUCE WEIGHT.

T2. APPLE. MALUS SPP. H. 7M S. 4M DIA 400 MM. CAT. R. AGE M. RPA N/A. TREE WITH SEVERE DECAY TO BOLE & BRANCH UNIONS.
REC. REMOVE & REPLACE WITHIN SCHEME.

T3. HAZEL. CORYLUS AVELLANA. H 6M S. 3M COPPICED HAZEL WITH NUMEROUS STEMS. CIR. 30 MAX DIA 25 MM. RPA SAY 1 M.
REC. RETAIN. COPPICE BY 30%.

T4. ASH. FRAXINUS EXCELSIOR H. 6M S. 2M DIA 100 MM. CAT. C1. AGE. YOUNG. RPA 1.2M. A DRAWN BUT REASONABLE TREE WITH GOOD CANOPY.
REC. RETAIN.

T5. ASH. FRAXINUS EXCELSIOR. H 6M. S 3M. (MIXED WITH STEMS OF HAZEL). DIA 105MM CAT C1. AGE Y. RPA. 1.26M.
REC. REMOVE - ALLOW ADJ ASH TO DEVELOPE.

T6. SPOIL OF 5 SAPLING ASH @ V. CLOSE CENTRES & CLOSE TO BOUNDARY.
REC. REMOVE - REPLACE WITHIN NEW LANDSCAPE SCHEME.

T7. ELDER. SAMBUCUS NIGRA. - SHRUB. TO 4M. - CLOSE TO BOUNDARY.
REC. REMOVE

T8. ASH FRAXINUS EXCELSIOR H. 4.5M. S. 2M. DIA 100 MM. CAT C1. AGE Y. RPA 1.2M. REASONABLE SAPLING.
REC. RETAIN

BRADLEY ENVIRONMENTAL CONSULTANTS
DAVID BRADLEY CMLI
25 CROMWELL STREET
SHEFFIELD S6 3RN
TELE 0114 2346418.

CLIENT MIDLANDS CO-OPERTIVE SOCIETY.

CONTRACT MAIN STREET. MARKFIELD, LEICS.

TITLE TREE SURVEY & COMMENTS

SCALE	DATE	DRAWN BY
1:200	MAR 11.	DHB.
DRAWING No.		REVISION
MCS/HMP/DHB/TS/01.		