D.C. PLAN

* CHECK SERVICES ON SITE PRIOR TO EXCAVATIONS & PLANTING.

MIX 1. LOW GROUND COVER TO FRONT GARDENS + SPOT PLANTS.

G.C
- 10 CISTUS SILVER PINK
- 15 EUONYMUS EMERALD 'GAIETY'
- 15 COTONEASTER DAMMERI
- 6 CELISTA LUTEA
- 15 HEBE RED EDGE
- 15 HEBE RAKAIENSIS.
- 10 HEBE SUNNIE BLUE
- 10 POTENTILLA RED ACE.
- 15 SPIRAEA GOLDFLAME
- 15 SANTOLINA CHAMAECYPARISSUS
- 15 BERGENIA MORNING RED.

SPOT
- 3 PHORMIUM BRONZE BABY
- 3 PHORMIUM YELLOW WAVE
- 6 PIERIS FOREST FLAME
- 9 PHYSOCARPUS DARLO
- 6 CHOISYA SUNDANCE.

PLANT @ (GROUND COVER) 500 MM CTS IN GROUPS OF 3-5.
SPOT PLANTS AS REQUIRED 3 PER GARDEN.

MAIN STREET.

9. ESCALONIA CRIMSON SPIRE @ 750 CTS.
10 SENECIO SUNSHINE @ 500 CTS.
10 CORNUS WESTONBIRT @ 700 CTS.
10. CHOISYA SUNSHINE @ 700 CTS.
15 MIX 1.
35 MIX 1.
5. PARTHENOCISSUS HENRYANA TO WALL
CRASS
20 MIX 1.
ESCALONIA COLD BRUSH @ 600 CTS
PYRUS CHANTICLEER 14-16 CM.
25 MIX 1
15. MIX 1
30 MIX 1
15 MIX 1
15 MIX 1
MIX 1.
FRAXINUS ORNUS 12-14 CM.
15. CORNUS SPAETHII @ 700 CTS.
SORBUS ARIA LUTESCENS 14-16 CM.
PYRUS CHANTICLEER 14-16 CM.
NATIVE SHRUBS/SCREEN MIX 2.
15. HEBE MRS WINDER @ 500 CTS.
20 SENECIO SUNSHINE @ 500 CTS.
18 MAHONIA WAGNERI PINNACLE @ 700 CTS.
QUERCUS ROBUR 14-16 CMS.
30. HEBE WIRI CHARM @ 500 CTS.
45. BERBERIS MELROID PILLAR @ 500 CTS.
15. CORNUS ELEGANTISSIMA @ 700 CTS.
15. HEBE MRS WINDER @ 500 CTS.
30 PYRACANTHA ROGERSIANA @ 750 CTS.
25. VIBURNUM TINUS @ 900 CTS.
2. ACER CAMPESTRE STREETWISE @ 12-14CM
30. PRUNUS LUSITANICA @ 750 CTS.
15. CORNUS SPAETHII @ 700 CTS.
CRASS
CRASS - CRETE
EX TREE T1
35. MAHONIA WAGNERI PINNACLE @ 700 CTS.
EX TREE T8
EX TREES T3 & T4.

GRASS AREAS.
TOPSOIL 150 MM DEPTH
CULTIVATE TO 100 MM - STONES 75CM, FIRM & RAKE TO A FINE TILTH. INC PRE-SEED FERT @ 50 gms M² IN FINAL RAKING.
SUPPLY & SOW BRITISH SEED HOUSES AGS SEED MIX * OR SIMILAR APPROVED @ 35 gms M² & LIGHTLY RAKE IN.
* SPRAY WITH GLYPHOSATE HERBICIDE (TO MANU INSTRUC) OR HAND WEED IF REQUIRED PRIOR TO CULTIVATION. TO PROVIDE WEED FREE AREAS.

NATIVE SHRUB/SCREEN PLANTS MIX 2
- 20 CORYLUS AVELLANA
- 30 PRUNUS SPINOSA
- 30 ILEX AQUIFOLIUM 2L POT
- 30 ROSA CANINA
- 15 ACER SYLVESTRIS
- 15 HIPPOPHAE RHAMNOIDES
- 30 VIBURNUM OPULUS.
- 20 AUCUBA JAPONICA CROTONIFOLIA 2L POT
- 30 PRUNUS LUSITANICA. 2L POT.

PLANT @ 800 MM CTS IN GROUPS OF 5-10.
PLANTS 600-900 MM WHIPS/TRANSPLANTS UNLESS STATED.
220 PLANTS TOTAL.

TREES. PT PLANT IN 1000 MM DIA X 700 MM DEEP PITS FORK OVER BASE & INC 60 LTRS PEAT FREE TREE COMPOST (TPC) PER STATION. SINGLE STAKE & TIE.

PLANTED AREAS. 300 MM TOPSOIL, CLEAR AREAS OF DEBRIS, LARGE STONES ETC & SPRAY WITH (AS REQ) GLYPHOSATE HERBICIDE (TO MANU INSTRUCTIONS). CULTIVATE TO 200 MM DEPTH TO PRODUCE A FRIABLE SOIL STRUCTURE INC. TPC INTO CULTIVATIONS * OR SIMILAR APPROVED.
PT PLANT SHRUBS IN COMPLIANCE WITH C.P.S.E. HANDLING & ESTABLISHMENT OF LANDSCAPE PLANTS PART III PARA 6.2 TO 6.6 INC. INCORP 3 LTRS TPC PER STATION.
ON COMPLETION OF PLANTING, LIGHTLY FORK OVER BED(S) & SUPPLY & SPREAD 50 MM DEPTH LANDSCAPE GRADE BARK MULCH.
* WATERING WILL DEPEND UPON LOCAL RESTRICTIONS & CLIMATE CONDITIONS.
ALL AREAS TO BE MAINTAINED WEED FREE *
* NOTE NATIVE SHRUB/SCREEN AREAS ONCE PLANTS ESTABLISHED, NATIVE GROUND FLORA ALLOWED TO DEVELOPE.
PLANTS SUBJECT TO 12 MONTHS DEFECTS LIABILITY PERIOD. THEREAFTER MAINTAINED BY CLIENT / & OR RESIDENTS.
* ALL SHRUBS 2 L POT GROWN, UNLESS STATED OTHERWISE.

BRADLEY ENV. CONSULTANTS
DAVID BRADLEY CMLI
25 CROMWELL STREET.
SHEFFIELD. S6 3RN.
TELE 0114 2346418.

CLIENT. MIDLANDS CO-OPERATIVE SOCIETY.
CONTRACT. MAIN STREET. MARKFIELD. LEICS.
TITLE. LANDSCAPE PROPOSALS
SCALE 1:200 DATE NOVE 11
DRG. NO. S/MAP/DRG/LP/02.