

General Notes

For General Notes and Details, refer to GRM Foundation Plan & Details Drawing ref. P10441_01.

TARGET FOUNDATION SCHEDULE (Best case estimates only. No allowance for contingencies)

- 1 - Depth of Excavation and bearing levels shown are indicative only. Actual depths to formation level are to be determined on site, and to be inspected by and agreed with GRM
- 2 - FFL's shown should be consistent with external works drawings, and any anomalies are to be queried with GRM. FFL's are also subject to revisions on site.
- 3 - For detailed hazard information refer to GRM Foundation Schedule.

Rev	Plot	House Type	Finished Floor Level	Average EGL	Anticipated Foundation Strata	Additional Information on General Hazards	Reason for Foundation Depth				Anticipated Bearing Level of Vibro Replacement Column				Minimum Length of Vibro Replacement Column below FFL				Anticipated Bearing Level of Concrete Foundation				Average Depth of Foundation Below EGL	Depth of Foundation Below FFL				Cut- or Fill +	Type of Foundation	Floor Slab Type	Claymaster Required	Gas Membrane Required	Radon Membrane Required	Retaining Wall or Plot Specific Construction Detail Required	Min. Void Required Under B&B Floor	Plot
							1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4		1	2	3	4									
A	26G	SG02	112.450	112.490	Clay	Variable and Poor Strength Strata	WPL	WPL	WPL	WPL	108.500	108.530	108.480	108.450	3.950	3.920	3.970	4.000	111.250	111.250	111.250	111.250	1.240	1.200	1.200	1.200	1.200	-0.04	Vibro-Replacement	B&B	No	No	No	No	0.250	26G
A	26	SIB	112.600	112.333	Clay	Variable and Poor Strength Strata	WPL	WPL	Min Depth	Min Depth	108.390	108.440	108.280	108.220	4.210	4.160	4.320	4.380	111.400	111.400	111.380	111.320	0.958	1.200	1.200	1.220	1.280	0.12	Vibro-Replacement	B&B	No	No	No	No	0.250	26
A	27	BRK	112.700	112.408	Clay	-	Pipe	Pipe	Min Depth	Pipe	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	111.240	111.450	111.580	111.428	0.983	1.460	1.250	1.120	1.272	0.14	Traditional	B&B	No	No	No	No	0.250	27
A	28	BRK	112.700	112.408	Clay	-	Pipe	Min Depth	Min Depth	Pipe	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	111.428	111.580	111.580	111.033	1.002	1.272	1.120	1.120	1.667	0.14	Traditional	B&B	No	No	No	No	0.250	28
A	29	HTR	112.750	112.385	Clay	-	Min Depth	Min Depth	Min Depth	Min Depth	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	111.390	111.410	111.580	111.560	0.900	1.360	1.340	1.170	1.190	0.21	Traditional	B&B	No	No	No	No	0.250	29
-	30	HEA	113.200	112.715	Clay	Trees																					0.33	Pile and Ground Beam	B&B	Yes	No	No	No	0.250	30	
-	31	HUT	113.200	112.795	Clay	Trees																					0.25	Pile and Ground Beam	B&B	Yes	No	No	No	0.250	31	
-	32	HUT	113.200	112.893	Clay	Trees																					0.16	Pile and Ground Beam	B&B	Yes	No	No	No	0.250	32	
-	33	BAR	113.200	113.040	Clay	Trees																					0.01	Pile and Ground Beam	B&B	Yes	No	No	No	0.250	33	

