Pond area = 961.4m²
Roads = 4,762.1m²
Drives = 7,500.5m²
Plots = 7,070.6m²

Total hardstanding area = **20,294.6m²**

Suds calc pond (area x 5) = 4,807m^2
Suds calc permeable drive (area x 5) = 15,756.5m^2
Total Suds infiltration= **20,514.5m²**

Permeable paving

Tarmac drive

Adoptable road

Buildings

Pond

SA09 = 1.26 x 10^{-5} m/s

SA08 = 2.28 x 10^{-5} m/s

SA07 = 1.25 x 10^{-5} m/s

SA07 = 1.25 x 10^{-5} m/s

Aston Flamville Road, Burbage

0m 10m 20m 30m 40m 50m

Revision.			
A	Updated to suit latest layout.	17.08.26	DM

ASTON FLAMVILLE ROAD
BURBAGE

SUDS Interception

DATE: **22.07.26**
SCALE: **1:500 @ A1**
DRAWN: **DM**
CHECKED: **DS**

BLOOR HOMES

Drawing No. EM039-EN-003A