



**FPCR Environment and Design Ltd
For Boyer Group**

December 2023

New Farm Site, Stanton Under Bardon – Implementation Timetable

The table below outlines the timing of implementation for the landscape works as shown on the drawings (Refs.11432-FPCR-XX-XX-DR-L-0001, 0002, 0003) and should be read in conjunction with these.

Landscape Element	Timescale
Hedgerow removal	End September – end February (avoiding bird-nesting season and periods of heavy/ prolonged frost/ rain)
Tree translocation	November – February (avoiding periods of heavy/ prolonged frost/ rain)
Woodland and hedgerow planting	November – February (avoiding periods of heavy/ prolonged frost/ rain)
Meadow grassland	March – May/ August – September
Wet grassland	March – May/ August – September
Reed bed	June – September
Surfacing, fencing	Anytime during suitable weather conditions, according to manufacturer's recommendations

All hard and soft landscaping will be completed in the relevant planting season prior to occupation / use of the buildings/development