The copyright to this drawing belongs to Ian Stemp Landscape Associates and shall not be reproduced without their written consent.
Do not scale from this drawing.

N

14No.Mahonia japonica
12No.Bergenia cordifolia
9No.Lonicera 'Baggesens Gold'
6No.Lonicera 'Baggesens Gold'
8No.Lonicera 'Maygreen'
6No.Prunus 'Otto Luyken'
12No.Geranium 'Wargrave Pink'
16No.Photinia 'Red Robin'
9No.Spiraea 'Goldflame'
16No.Mahonia japonica
9No.Hebe 'Marjorie'
16No.Choisya ternata
7No.Spiraea 'Anthony Waterer'
15No.Hosta sieboldiana 'Elegans'
7No.Hypericum x moserianum
15No.Prunus 'Otto Luyken'
16No.Berberis thunbergii
11No.Rosa 'Bonica'
12No.Hebe 'Pagei'
7No.Lavandula angustifolia
14No.Geranium 'Wargrave Pink'
5No.Fuschia 'Mrs Popple'
5No.Geranium 'Wargrave Pink'
9No.Hebe 'Pagei'
9No.Mahonia japonica
7No.Prunus 'Otto Luyken'
9No.Escallonia 'Apple Blossom'
14No.Hemerocallis 'Corky'
16No.Lonicera 'Maygreen'
42No.Escallonia 'Donard Star'
8No.Lonicera 'Maygreen'
74No.Viburnum tinus 'Eve Price'
24No.Bergenia cordifolia
9No.Hypericum x moserianum
12No.Viburnum davidii
24No.Viburnum tinus 'Eve Price'
14No.Hypericum x moserianum
12No.Hypericum x moserianum
42No.Viburnum tinus 'Eve Price'
16No.Aucuba 'Crotonifolia
24No.Choisya ternata
14No.Photinia 'Red Robin'
12No.Rosa 'Bonica'
Native Hedgerow 1
12No.Symphoricarpos 'Hancock'
45No.Escallonia 'Edinensis'
16No.Bergenia cordifolia
6No.Elaeagnus 'Limelight'
8No.Hypericum x moserianum
18No.Bergenia cordifolia
30No.Viburnum tinus 'Eve Price'
3No.Prunus 'Otto Luyken'
T1 T2 T3 T4 T5
F1 F4 F6 RW1
1 1a 2 2a 3 3a 4 5 6 7 8 9 10 11 12 33 34 35
A M R ST

KEY

Proposed Tree Planting
Tree pits shall be 900x900x900 with loose soil to base, care shall be taken to prevent smearing of tree pit sides. The pit shall be backfilled with a ⅔ mix of good quality topsoil and an non peat based compost. 140gms of Enmag granular slow-release fertiliser shall be incorporated to the fill mixture.Trees shall be double staked and fixed to horizontal crossbar using rubber strapping, with rubber block positioned between the tree and cross bar. Stakes shall be 60mm diameter treated softwood, driven firmly into ground either side, and not through the rootball, with tree central between the stakes. The above ground height of the stake should be a minimum of a third of the stem high. All trees to receive perforated watering pipes surrounding root ball.

Proposed Areas of Shrub Planting
Shrub areas to have minimum 450mm depth of good quality imported cultivated topsoil, free from bricks, large stones and other rubbish. MycorForce Transplanter shall be spread around the roots of each plant during planting at a rate specified by the supplier, Tel:English Woodlands Burrow Nursery 01435 862992.
All shrub areas shall have 50mm depth Melcourt Ornamental Bark Mulch, (or similar approved).

Grass seeding
To be Pro Landscape Low Maintenance Landscape with Wild Flora mix.
Sowing rate 35g/m2. Areas for grass seeding to be have 100mm good quality topsoil free from any object over 20mm in size.

Native Hedgerow. To be planted at 5 plants per linear metre in double staggered rows. All plants to have spiral rabbit guards secured with cane. Line of hedgerow to have 50mm amenity grade bark mulch.

Proposed Ornamental Hedgerow
Areas for planting to be treated with translocated herbicide to clear weeds before planting. All specimens to be pit planted backfilled with 70grams of Enmag slow release fertiliser.

PLANT SCHEDULE

Species		Girth	Height	Root Cont.	Hedge Ltrs	Habit	Breaks	Nos.
Trees								
T1	Acer campestre	14-16cm		C				3
T2	Fraxinus excelsior	14-16cm		C				2
T3	Quercus robur	14-16cm		C				6
T4	Rhus typhina	14-16cm		C				2
T5	Sorbus aria 'Majestica'	14-16cm		C				4
Ornamental Hedgerow. To be planted at 3 plants per linear metre.								
	Escallonia 'Edinensis'			C	15			170
	Viburnum tinus 'Eve Price							
Shrubs								
	Aucuba 'Crotonifolia			c	3			16
	Berberis thunbergii			c	3			16
	Choisya ternata			c	3			40
	Elaeagnus 'Limelight'			c	3			6
	Escallonia 'Apple Blossom'			c	3			9
	Escallonia 'Donard Star'			c	3			42
	Fuschia 'Mrs Popple'			c	3			5
	Hebe 'Marjorie'			c	3			9
	Hebe 'Pagei'			c	3			21
	Hypericum x moserianum			c	3			50
	Lavandula angustifolia			c	3			7
	Lonicera 'Baggesens Gold'			c	3			15
	Lonicera 'Maygreen'			c	3			32
	Mahonia japonica			c	3			39
	Photinina 'Red Robin'			c	3			30
	Prunus 'Otto Luyken'			c	3			31
	Rosa 'Bonica'			c	3			23
	Spiraea 'Anthony Waterer'			c	3			7
	Spiraea 'Goldflame'			c	3			9
	Symphoricarpos 'Hancock'			c	3			12
	Viburnum davidii			c	3			12
Herbaceous								
	Bergenia cordifolia			c	2			70
	Geranium 'Wargrave Pink'			c	2			31
	Hemerocallis 'Corky'			c	2			14
	Hosta sieboldiana 'Elegans'			c	2			15
Native Hedgerow.								
	Acer campestre			br	60-90			10
	Corylus avellna			br	60-90			15
	Crataegus monogyna			br	60-90			70
	Ilex aquifolium			c	2L			20
	Prunus spinosa			br	60-90			20

Project
Ferndale Drive, Ratby
for
Cawrey Homes

Drawing
Soft Landscape Proposals
Plots 1 - 5.

Date	Drawn
30.07.08	cjn
Dwg. No. 08.762.001	Scale 1:150 @ A1
Revision	Checked cjn

Revisions | Dwn. | Date

IAN STEMP LANDSCAPE ASSOCIATES
LANDSCAPE ARCHITECTURE . LANDSCAPE PLANNING . URBAN LANDSCAPE DESIGN
STUDIO ONE, THE MEWS, 206 AVENUE ROAD EXTENSION, CLARENDON PARK, LEICESTER, LE2 3EL
Tel: 0116 270 1387 Fax: 0116 244 8840
email: ilfs@stempltd.funet.co.uk