

	EXISTING TREES/HEDGES <i>To be retained</i>
	PROPOSED TREES <i>Heavy/Selected/Standard</i> <i>See Schedule</i>
	ORNAMENTAL HEDGE <i>See Schedule</i>
	NATIVE HEDGE MIX <i>See Schedule</i>
	PROPOSED PLANTING <i>Shrubs/Herbaceous/Grasses</i> <i>See Schedule</i>
	TURF <i>with area (m²)</i>
	AMENITY GRASS AREAS <i>Flowering Grass Mixture</i> <i>Enrichment E/L 1 sown at 4g/m²</i> <i>Kept mown short to 40mm</i>
	WILDFLOWER MEADOW <i>Special General Purpose Meadow Mix</i> <i>Enrichment EM3 sown at 4 g/m²</i> <i>(Existing grassland to be retained and managed</i> <i>reseedling is required once as above)</i>
	GRAVEL <i>40mm of Golden Gravel</i> <i>Laid over Geotextile</i>
	GRAVEL PATH REGIONAL SPECIFICATION

1. **CLIMBING TRUNKS x3**
As Supplied by Ashwell Timber Ltd
3-4m in Length
Or Similar Approved
2. **PARALLEL BARS**
As Supplied by Playdale
Ref: P.A.S
Or similar approved
3. **CLIMBING BOULDERS x8**
Californian Glacial Boulders
Mixture of Sizes, Well-rounded
Partly Embedded in the Soil
4. **LEAP FROG**
As Supplied by Proludic
Ref: JPS161
Or similar approved
5. **DOUBLE TURBO CHALLENGE**
As Supplied by Kompan
Ref: FR0212
Or similar approved
6. **JUMP RAMP**
As Supplied by Proludic
Ref: JPS23
Or similar approved
7. **BALANCE WEAVE**
As Supplied by Miracle Design & Play
Ref: TBR7140
Or similar approved
8. **HURDLES**
As Supplied by Miracle Design & Play
Ref: TBR7142
Or similar approved



All tree and shrub locations and species must be taken into consideration by the Project Designer. The Project Designer shall ensure the Foundation design accords with the specifications set out in Chapter 4 of the NHC Standards.

The Landscape Contractor must ensure that the planting of all plants and shrubs at the location shown and with NO SUBSTITUTIONS made without consulting the Group Landscape Design Department. It is the Landscape Contractor's responsibility to ensure that all underground services have been located and identified in advance of tree pit excavation and that the planting of all plants and shrubs by tree planting. Any change to tree positions, species or specifications must be approved by the Group Landscape Design Department. Underground service strips are to be kept free of all plant material.

Contractors must comply with all Health and Safety regulations and be aware of any specific requirements of the Client, referring to the information set out in the CDM drawings.

Symbol.	Brief description of risk.
	Caution overhead / underground services.
	Sewer easement.
	Trees have protection order in place, guarding required.

NOTES:

Principal contractor to ensure all health and safety procedures are being correctly followed in relation

SHEET 017 (78-137,139-146,149-167,171-173)
SHEET 018 (40-77,138,147-148,168-170,
174-180)
SHEET 019 (1-39)

Revision	Date
a Updated to latest layout and boundary	24.01.20
b Updated following comments	07.02.20
c Updated following comments	02.05.20
d Updated following comments	09.05.20
e Updated boundary, changed trim trail and ecological features added.	23.05.20
f Play equipment added to SE of site	26.05.20
g Changes to house types, ecological features added.	06.06.20

Scale. 1:250 @A0	Drawn. LP
Date. Jan 2023	Checked. PmJ

THIS DRAWING AND THE BUILDING WORKS DEPICTED ARE THE COPYRIGHT OF J.S.BLOOR (SERVICES) LIMITED AND MAY NOT BE REPRODUCED OR AMENDED EXCEPT BY WRITTEN PERMISSION. NO LIABILITY WILL BE ACCEPTED FOR AMENDMENTS MADE BY OTHER PERSONS

BLOOR HOMES
J S BLOOR (SERVICES) LIMITED
ASHBY ROAD, MEASHAM, SWADLINCOTE,
DERBYSHIRE DE12 7JP
TELEPHONE 01530 270100 FACSIMILE 01530 272006

Drawing No. EM100-LS-018c

HINCKLEY WEST PH4