Vat no. 833 5083 36

6th January 2010

Mr Charlie Yates
Carlton Select Homes Ltd
Glebe Farm
Shackerstone Walk
Carlton
CV13 0BY

Dear Mr Yates

**Building Plot, Rectory Lane, Nailstone, Leicestershire.**

Please find enclosed my recommendations for works to trees located at the above site.

**Silver Birch (*Betula pendula).*** As the south side of this trees crown will be very close to the proposed building line, recommended work consists of reducing the south and southwest side by approx 30%. This will allow room for scaffolding and the movement of machinery without causing damage to the trees crown and leave a more balanced appearance. The remaining crown will then be thinned by 20% to allow more light through to the proposed building. All pruning will be back to appropriate growth points leaving a balanced and natural shape.

**Scots Pine *(Pinus sylvestris).*** Recommended work will consist of removing any deadwood within the trees crown and correctly pruning any broken stubs.

All brash and timber will be removed leaving site tidy.

All work carried out to BS3998:1989 (Recommendations for tree works).

Cost = £350.00

VAT (17.5%) = £61.25

TOTAL COST = £411.25

Please find enclosed a copy of our insurance. If you have any queries please don't hesitate to contact me

Neil Harbour (RFS Cert Arb)