Build over sewers policy

CCTV contractors July 2008

job number B5224 | issue date 04/07/08 | produced by MARK | ☐ design ☐ artwork | ☐ checked and passed ☐ further amends required sign here and return to wm | ☐ c ☐ wm | QM SYSTEM ISO 9001 REGISTERED FIRM | 02

6.0 Locating the position and condition of the public sewer

When applying for permission to build over or near a sewer you may need a pre and post construction survey carrying out. In certain circumstances these may not be required. Please refer to sections 3, 4 and 5 for details.

If a survey is required then you will need to employ the services of a specialist CCTV contractor. Please ensure that the contractor is capable of undertaking the work to the standards described below. If information is missing we will have to reject your application. This will obviously delay your work.

The survey report should be carried out by a competent contractor who will produce a report complying with the WRc Model Contract Document for Non Man Entry Sewer Inspection Third Edition and UK Water Industry Manual of Sewer Condition Classification Third Edition. The contractor will have to seek our permission to work on our sewers and will be required to provide evidence of their health and safety competence in the form of a written method statement.

The survey should include:

- A block plan showing the point of entry of the CCTV into the public sewer, the length of sewer surveyed, any drain connections and the location of the sewer as confirmed by direct line tracing in relation to the existing building and boundary fences. The plan should be to scale and dimensioned.

- An inspection report to WRC standards including; sewer details such as type (foul or surface water), pipe size, pipe material, pipe depth, condition classification, drain connections, defects and recommendations, photographs of significant defects.

The choice of contractor is yours. A list of contractors is included for your information. These contractors have been vetted for health and safety competence and are authorised to work on the public sewer network.

(1) 365 Environmental Services Ltd (Formerly DBI)

Letters to: Head Office
365 Environmental Services Ltd
Hanger G1, G Site
Kemble Airfield
Cirencester
Gloucestershire GL7 6FD

Further offices based locally

Telephone: 08454 600365 (Local Rate)
Fax: 01285 740638
Website: www.365es.co.uk
Areas Covered: Coventry, Gloucestershire, Herefordshire, Warwickshire, Worcestershire, Staffordshire, Shropshire, Powys, Oxfordshire, West Midlands

(2) Bethell Construction Ltd

Letters to: Bethell Construction Ltd
Dane House
Europa Park
Stoneclough Park
Kearsley
Greater Manchester M26 1GE

Telephone: 01204 439100
Fax: 01204 439101
Website: www.bethell.co.uk
Areas Covered: Northern Counties including Nottinghamshire, Derbyshire & Stoke-on-Trent

(3) Draintech Services

Letters to: Draintech Services
Atlantic House
Dumballs Road
Cardiff CF10 5FE

Telephone: 029 2023 0390
Fax: 029 2037 1691
Website: www.draintech.co.uk
Areas Covered: Gloucestershire, Worcestershire, Shropshire, Mid Wales & West Birmingham

(4) Ferro Monk Systems Ltd

Letters to: Ferro Monk Systems Ltd
Peckfield, Great North Road
South Milford
Leeds LS25 5LH

Telephone: 01384 822160
Fax: 01384 823160
Website: www.ferromonk.co.uk
Areas Covered: All Counties covered

(5) Future Amtec Ltd

Letters to: Future Amtec Ltd
Whitting Valley Road
Old Whittington
Chesterfield S41 9EY

Telephone: 01246 260603
Fax: 01246 260599
Website: www.futureamtec.com
Areas Covered: All Counties covered

(6) Onsite Central Ltd

Letters to: Onsite Central Ltd
Building Over Department
89 Blackpole West
Blackpole
Worcester WR3 8TJ

Telephone: 0845 4082153
Fax: 01905 751559
Email: buildovers@onsite.co.uk
Website: www.onsite.co.uk
Areas Covered: All Counties covered

(7) Underground Surveys Ltd

Letters to: Underground Surveys Ltd
Unit CG 17 & 18
Warrington Business Park
Long Lane
Warrington WA2 8TX

Telephone: 01925 444664
Fax: 01925 444663
Website: www.undergroundsurveys.co.uk
Areas Covered: All Counties covered

job number B5224 | issue date 04/07/08 | produced by MARK | ☐ design ☐ artwork | ☐ checked and passed ☐ further amends required sign here and return to wm | ☐ c ☐ wm | 02