COPY 28th July

Leicestershire County Council

Higham on the Hill Primary School
Main Street
Higham on the Hill
Nuneaton
Warwickshire
CV13 6AJ

Date: 24th July, 2009
My ref: E/RP/NF/7346/9
Your ref:
Contact:
Phone: Ext. 56920
Email: nfell@leics.gov.uk

Dear Ms. Walsh

TREE SURVEY – HIGHAM ON THE HILL PRIMARY SCHOOL

I refer to your request for a tree survey to be undertaken in relation to the proposed construction of gazebo at the school. I have now carried out a survey of trees in the immediate vicinity and attached are 2 copies. The survey has been carried out from ground level and includes all trees which potentially could be affected by the proposed construction.
I have classified the trees in the retention categories detailed in British Standard 5837:2005 'Trees in Relation to Construction - Recommendations' . These are as follows: -

Category A - Trees of high quality (marked light green on the attached plan)

Category B - Trees of moderate quality (marked blue on the attached plan)

Category C - Trees of low quality (marked grey on the attached plan)

Category R - Trees for removal (no trees are included in this category)

I have also indicated on the plan the necessary root protection area required to successfully protect the trees and avoid damage. This area will need to be identified on site, excluded from the work area and where appropriate, protected with scaffold framed fencing specified in B. S. 5837:2005. This should be positioned as indicated on the attached plan.

Details of individual trees are given on the schedule attached.

cont.....

Property Services, Resources Department
Leicestershire County Council, County Hall, Glenfield, Leicestershire LE3 8RE
Telephone: 0116 232 3232 Fax: 0116 265 6722 Email: property@leics.gov.uk

Steve Siddons, BSc (Hons), Head of Property and Asset Management
Brian Roberts, CPFA, Director of Resources

www.leics.gov.uk

INVESTOR IN PEOPLE

If the construction works were to result in the loss of any existing trees, new tree planting involving advanced container grown specimens should be accommodated in the design and undertaken as part of post construction landscaping. The new trees should be of an appropriate species and should be positioned to ensure long term compatibility with the new gazebo.

If you require any further advice, please contact me on 0116 3056920.

N. Fell

Nick Fell
Team Leader - Forestry

SITE Higham on the Hill Primary School

No.	Species	Height	Branch Spread	S. Dia.	Height Clear.	Ageclass	Remaining Contribution	Condition	Category	Root Protection Area Radius
		metres	metres	mm			Years			
1	Prunus 'Kanzan' (Japanese Cherry)	8	N 3 S 4 E 5 W 3	400	3m	Mature	20	Fair	B	4.8 metres
2	Acer pseudoplatanus (Sycamore)	12	N 7 S 6 E 7 W 6	700	4m	Mature	30	Good - forks at 3 metres	A	8.4 metres
3	Ilex aquifolium (Holly)	8	N 3 S 3 E 3 W 3	Multi Stemmed 400	2m	Mature	10	Poor	C	6 metres
4	Acer pseudoplatanus (Sycamore)	9	N 4 S 4 E 4 W 4	Multi Stemmed 600	2m	Young Mature	40	Good	B	6 metres
5	Quercus robur (English Oak)	9	N 4 S 5 E 4 W 5	500	2m	Mature	80	Good	A	6 metres
6	Aesculus hippocastanum (Horse Chestnut)	8	N 3 S 4 E 4 W 4	200	2m	Semi Mature	60	Good	A	2.4 metres
7	Fagus sylvatica (Beech)	8	N 4 S 4 E 5 W 3	250	1.5m	Semi Mature	60	Good	A	3 metres

SITE Higham on the Hill Primary School

No.	Species	Height	Branch Spread	S. Dia.	Height Clear.	Ageclass	Remaining Contribution	Condition	Category	Root Protection Area Radius
		metres	metres	mm			Years			
1	Prunus 'Kanzan' (Japanese Cherry)	8	N 3 S 4 E 5 W 3	400	3m	Mature	20	Fair	B	4.8 metres
2	Acer pseudoplatanus (Sycamore)	12	N 7 S 6 E 7 W 6	700	4m	Mature	30	Good - forks at 3 metres	A	8.4 metres
3	Ilex aquifolium (Holly)	8	N 3 S 3 E 3 W 3	Multi Stemmed 400	2m	Mature	10	Poor	C	6 metres
4	Acer pseudoplatanus (Sycamore)	9	N 4 S 4 E 4 W 4	Multi Stemmed 600	2m	Young Mature	40	Good	B	6 metres
5	Quercus robur (English Oak)	9	N 4 S 5 E 4 W 5	500	2m	Mature	80	Good	A	6 metres
6	Aesculus hippocastanum (Horse Chestnut)	8	N 3 S 4 E 4 W 4	200	2m	Semi Mature	60	Good	A	2.4 metres
7	Fagus sylvatica (Beech)	8	N 4 S 4 E 5 W 3	250	1.5m	Semi Mature	60	Good	A	3 metres

SITE Higham on the Hill Primary School

No.	Species	Height	Branch Spread	S. Dia.	Height Clear.	Ageclass	Remaining Contribution	Condition	Category	Root Protection Area Radius
		metres	metres	mm			Years			
8	Populus tremula (Aspen)	10	N 4 S 4 E 4 W 4	200	2m	Semi Mature	50	Good	A	2.4 metres
9	Acer platanoides (Norway Maple)	9	N 4 S 4 E 4 W 4	250	1.5m	Semi Mature	60	Good	A	3 metres
10			N S E W							
11			N S E W							
12			N S E W							
13			N S E W							
14			N S E W							

Catergory A Trees of high quality

Catergory B Trees of moderate quality

Catergory C Trees of low quality

Position of protective fencing

Root protection area

N

W E

S

PH

ox Inn

83

MAIN STREET

117.4m

1

2

3

4

5

6

7

8

9

Reproduced from an Ordnance Survey map with the permission of the Controller of HMSO
® Crown Copyright. Leicestershire County Council
Licence number 100019271

Tree Survey - Higham on the Hill C of E Primary School

Main Street, Higham on the Hill : UPRN 290

Approx Scale 1:250 @ A3 Landscape
(Layer 10 and 11)

Compiled by J. Sproston
23 July 2009

Leicestershire County Council

Property Services
Corporate Resources Department
County Hall, Glenfield.
Leicester. LE3 8RE
Tel:0116 232 3232

Template: F:\GIS\PRINTING\TEMPLATE\2006A3land.wor