Landscape materials

- Tarmac
- Block paving - Brindle
- Patio slabs to client's specification
- Grass
- Existing wall retained and repaired
- New brick wall to match existing
- Car charging point
- Bin storage
- bins — Bin collection points
- 1800mm high solid timber bow top gate
- 1800mm high woven timber fencing with timber posts and timber gravel boards
- 1100mm high timber picket fencing
- Native hedgerow planting to be a mix of hawthorn, beech, yew and honeysuckle
- Existing tree / hedgerow to be removed

Shrubs

Type	Density	Height	Pot size
Viburnum davidii	2/m²	30-40cm	10L

Native mix hedgerows

Crataegus monogyna (Hawthorn) 50% @ 0.3m centres	60-90cm	2L
Fagus sylvatica (Beech) 20% @ 0.3m centres	60-90cm	2L
Taxus baccata (Yew) 20% @ 0.3m centres	60-90cm	2L
Lonicera nitida "Baggesden's Gold" (Honeysuckle) 10% @ 0.5m ctrs	20-30cm	2L

LANDSCAPE MANAGEMENT PLAN

ESTABLISHMENT MAINTENANCE
Plants and planting areas shall be maintained for a period of 5 years after planting to include the following operations.

Failures of planting:
- replace shrubs that have failed to thrive after completion with equivalent shrubs
- replacements to match size of adjacent or nearby plants of same species or match original specification, whichever is the greater
- make good during the next suitable planting season

Cleanliness:
- remove soil and arisings from hard surfaces and grassed areas
- leave the works in a clean and tidy condition at completion and after maintenance operations

Planting maintenance generally:
- keep planting beds clear of weeds by maintaining full thickness of mulch
- fork over planting beds as necessary to keep soil loose with gentle cambers and no hollows. Take care not to reduce depth or effect of mulch.
- ensure that shrubs are not damaged by use of mowers, nylon filament rotary cutters and similar power tools
- gently firm loosened soil around shrubs, straighten leaning shrubs

Planting maintenance - Pruning:
- prune shrubs as required to promote healthy growth and natural shape
- remove dead, dying, diseased wood and suckers
- low hedges - trim annually to maintain maximum hedge height as stated on drawing

Final mulching:
- at the end of the establishment maintenace period remulch all planting areas to a minimum depth of 75mm
- ensure that soil is thorougly moistened prior to remulching, applying moisture where necessary

LONG TERM MANAGEMENT OBJECTIVES
The objective of long-term management is to ensure the sucess and sustainability of all soft landscaping thereby achieving the aims and objectives of the landscaping scheme designed to:
- integrate the proposed development with it's setting and provide visual amenity
- enhance site biodiversity through the use of wildlife friendly shrub species.

IMPLEMENTATION
All soft landscaping to be completed prior to sale of the plot associated with it.

Bat mitigation

- Ibstock bat brick 'c'
- Schwegler wall mounted bat box 1FE
- Schwegler tree mounted bat box 2FN
- Bat roost
- Bat loft over

A Bat Mitigation (Development) Licence from Natural England will be required before any works to Buildings 1 and 2 can be carried out.

Levels

x 108.000 — Proposed levels

107.78 — Existing levels

0 2 4 6 8 10 20m

Rev.	Date	Description	By	Ckd
B	03.07.24	Materials removed and shown on drawing no. 19. Landscaping amended as per planner's comments.	ZLM	
C	09.08.24	Bin collectin points amended for clarity	ZLM	
D	09.08.24	Key amended	ZLM	

Client: **Forsthe Estates NJ Ltd**

Project Title: Proposed development
Moore's Arms
Norton Juxta Twycross

Drawing Title: **Landscape**

Scale	Date	Sheet
1:200	June 2022	A2
Author: ZLM	Checked by: -	

THE COPYRIGHT OF THIS DRAWING IS VESTED IN HAYWARD ARCHITECTS LTD.
REPRODUCTION IN ANY FORM, EITHER IN WHOLE OR IN PART IS FORBIDDEN WITHOUT THE PRIOR WRITTEN PERMISSION OF THE COPYRIGHT HOLDER. DO NOT SCALE FROM DRAWING AND ONLY FIGURED DIMENSIONS ARE TO BE USED

hayward ARCHITECTS LTD
19 Station Road
Hinckley
Leicestershire
LE10 1AW
Tel: 01455 635 665
Fax: 01455 618 971
www.hayward-architects.co.uk

Job No.	Drawing No.
19/116	18d

Status: PLANNING