

Handrail to steps.

New handrail to steps to be 'Dryad' 50mm dia nylon coated steel in red (04-E-53 to BS 4800 colurs) All handrail details to conform to BS 8300:2001 and to a height of 1.00 metres above finished ground level).

Typical Planter Wall / Steps Wall Elevation

General Note: All new walls to have Anti-Skateboard rails (i.e 'Skate-Stop' stainless steel studs built into top of walls at 600 mm centres along entire length)

All brickwork constructions to be built with Ibstock Audley Red Mixture facing bricks with blue engineering brick capping.

LANDSCAPING

Trees within new brick planters to be 1No. Sorbus aucuparia 'Joseph Rock' and 1No. Sorbus hupehensis.

Suitable root barrier protection to be installed in each new raised brick planter.

Dense shrub planting around base of new trees to be a mix of berberis 'Park Jewel' and Fatsia japonica, of 3L pot size planted at 250 mm centres.

Fencing Detail

ALTO 'Yeoman' Bollard removable type, unit to be 1.0m.above finished ground level

DEVELOPMENT SERVICES
05 MAR 2009
RECEIVED

Rev.	Date	Details	Drawn	Checked
D	27.02.09	Misc details added by Jelson Ltd	SRP	SRP
C	02.02.09	Misc details added by Jelson Ltd	SRP	SRP
B	04.02.08	New bollards and tree removed	JSI	MR

Issued for: Comments

Project/Client: Battling Brook, Clifton Way, Hinckley

Project No: 71493

Dwg No: 200 Rev:

Scale: 1:100 @ A1

Drawing: Proposed Works

North:

Drawn By: LRJ Date: 25-9-06

Checked By: Date:

SMC CHARTER ARCHITECTS

INVESTOR IN PEOPLE Certificate No. FS 30051

2 St Stephen's Court St Stephen's Road Bournemouth BH2 6LA
T: 01202 554625 F: 01202 294007
E: bournemouth@smccharterarchitects.com
excellence in design and service □ www.smccharterarchitects.com

Contractors must work only to figured dimensions which are to be checked on site.