

No	US MH	Length	IL US	IL DS	Fall	Grad.	Diameter	Construction
F1.000	F1	16.310	112.703	112.500	0.203	80.3	100	P
F2.000	EX FMH1	4.013	113.270	113.121	0.149	26.9	100	P
F2.001	F2	8.990	113.121	112.790	0.331	27.2	100	P
	Ex FMH3	9.015	112.790					

No.	CL	IL	Depth	Diameter	Construction	Cover
F1	114.000	112.703	1.297	450	PPIC	B125
EX FMH1	113.643	113.270	0.373			
F2	113.740	113.121	0.619	450	PPIC	D400
Ex FMH3	114.324	112.790	1.534			

Locations of SVPs are assumed. Refer to Architects specification for details



		
Diamond Wood & Shaw Limited The Old School • Babby Road • Enderby • Leicester • LE19 4AR Tel: 0115 254 5555 • Email: info@dswd.co.uk		
Project Title MANOR HOUSE FARM		
CARLTON		
Drawn DW	Engineer DW	Checked BP
Scale at 1:100 @ A1		Date AUG 2024
Drawing Title DRAINAGE LAYOUT		
Project No. 23-20021	Drawing No. 0-500	Revision P1
IIM Code		

NOT FOR CONSTRUCTION