PDP Associates
Great Asby
Appleby in Westmorland
Cumbria
CA16 6HD
017683 54130
info@pdpcumbria.co.uk

Client
Redrow Homes

Project
Burbage

Drawing title
Landscape Masterplan
Sheet 2 of 2

Scale
1:1000 @ A1

Drawn by
PDP

Date
May 2023

Drawing No.
# c-2109-02 Revision A

Revision A: Updated to align with replanned site layout. PDP. 09.11.23

- Extra heavy standard tree planting in grassed or planted areas with provision made for protection of highway. Tree pits as per BS 8545:2014. To include single 1.6m timber stake, 600mm above ground, spacer and biodegradable tie.
- Extra heavy standard tree planting in grassed or planted areas. Tree pits as per BS 8545:2014. To include single 1.6m timber stake, 600mm above ground, spacer and biodegradable tie.
- Heavy standard tree planting in grassed or planted areas. Tree pits as per BS 8545:2014. To include single 1.6m timber stake, 600mm above ground, spacer and biodegradable tie.
- Ornamental shrub planting, including 50mm depth no-fines bark mulch. Individual species to be planted in groups of no more than 7 plants.
- Ornamental hedge planting, including 50mm depth no-fine bark mulch.
- Native hedge planting. Plants to be pit planted at 0.33m spacing in a double staggered row (6 plants per linear metre). Shelters to all plants. Species to be planted in random, single species groups of no more than 5 plants.
- Areas to be turfed.
- Areas of amenity grass seed mix or existing grassland, made good.
- Areas of species-rich wetland grass seeding, such as Emorsgate Mix EG8, or similar and approved.
- Areas of existing grassland, enhanced through over-sowing or plug-plants with species-rich meadow grass seeding, such as Emorsgate Mix EM2, or similar and approved.
- New native planting at 1m (shrub species) and 2m (tree species) centres, including tubular guards and stakes.
- Orchard planting using local heritage species and underplanted with a grid of wildflower seed mix, such as Emorsgate Mix EM1F.
- Mown grass paths leading to LAP.

Top of Bank: 107.00
Max water level 106.70
Bed: 106.00
Outlet 105.70