

Waterman Group		Page 1																										
Pickfords Wharf Clink Street London, SE1 9DG																												
Date 05/07/2022 12:02 File	Designed by CSKRS Checked by																											
Innovyze		Source Control 2020.1.3																										
<u>Greenfield Runoff Volume</u> FSR Data <table> <tr> <td>Return Period (years)</td> <td>100</td> </tr> <tr> <td>Storm Duration (mins)</td> <td>360</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.000</td> </tr> <tr> <td>Ratio R</td> <td>0.400</td> </tr> <tr> <td>Areal Reduction Factor</td> <td>1.00</td> </tr> <tr> <td>Area (ha)</td> <td>1.570</td> </tr> <tr> <td>SAAR (mm)</td> <td>700</td> </tr> <tr> <td>CWI</td> <td>105.000</td> </tr> <tr> <td>Urban</td> <td>0.000</td> </tr> <tr> <td>SPR</td> <td>47.000</td> </tr> </table> Results <table> <tr> <td>Percentage Runoff (%)</td> <td>45.98</td> </tr> <tr> <td>Greenfield Runoff Volume (m³)</td> <td>451.222</td> </tr> </table>			Return Period (years)	100	Storm Duration (mins)	360	Region	England and Wales	M5-60 (mm)	20.000	Ratio R	0.400	Areal Reduction Factor	1.00	Area (ha)	1.570	SAAR (mm)	700	CWI	105.000	Urban	0.000	SPR	47.000	Percentage Runoff (%)	45.98	Greenfield Runoff Volume (m³)	451.222
Return Period (years)	100																											
Storm Duration (mins)	360																											
Region	England and Wales																											
M5-60 (mm)	20.000																											
Ratio R	0.400																											
Areal Reduction Factor	1.00																											
Area (ha)	1.570																											
SAAR (mm)	700																											
CWI	105.000																											
Urban	0.000																											
SPR	47.000																											
Percentage Runoff (%)	45.98																											
Greenfield Runoff Volume (m³)	451.222																											
©1982-2020 Innovyze																												

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:37	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details


Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 435950 295750 SP 35950 95750
Data Type	Catchment
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow
1.000		1 15 Winter	2	+0%	100/15 Winter		
1.001		2 15 Winter	2	+0%	30/15 Summer		
2.000		3 15 Summer	2	+0%			
1.002		4 15 Winter	2	+0%	30/15 Summer		
3.000	Dummy Rainfall	L 15 Summer	2	+0%	100/15 Summer		
3.001		20 15 Winter	2	+0%	100/15 Summer		
1.003		5 15 Winter	2	+0%	100/15 Summer		
1.004		6 15 Winter	2	+0%	30/15 Summer		
1.005		7 15 Winter	2	+0%	100/15 Summer		
1.006		8 15 Winter	2	+0%	30/15 Winter		
4.000		9 15 Winter	2	+0%			
4.001		10 30 Winter	2	+0%	100/15 Summer		
5.000		11 15 Summer	2	+0%			
4.002		12 30 Winter	2	+0%	30/15 Summer		
6.000		13 15 Winter	2	+0%	100/15 Summer		
7.000		x 15 Summer	2	+0%	100/30 Winter		
4.003		14 30 Winter	2	+0%	2/15 Summer		
8.000		15 15 Summer	2	+0%			

©1982-2020 Innovyze



Waterman Group		Page 2
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:37 File PLOT 8+9_KAREN UPDATES.MDX	Designed by CSKRS Checked by	
Innovyze		Network 2020.1.3
2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm		
PN	US/MH Name	Overflow Act. Water Level (m) Surcharged Depth (m) Flooded Volume (m³) Flow / Overflow Cap. (l/s) Half Drain Time (mins)
1.000		1 94.053 -0.247 0.000 0.07
1.001		2 93.591 -0.217 0.000 0.12 4
2.000		3 94.000 -0.300 0.000 0.00
1.002		4 93.583 -0.020 0.000 0.09 5
3.000	Dummy Rainfall L	94.000 -0.100 0.000 0.00
3.001	20	93.677 -0.196 0.000 0.26 7
1.003	5	93.232 -0.243 0.000 0.27
1.004	6	92.870 -0.170 0.000 0.57
1.005	7	92.687 -0.213 0.000 0.38
1.006	8	92.222 -0.208 0.000 0.41
4.000	9	94.032 -0.268 0.000 0.03
4.001	10	93.685 -0.265 0.000 0.03 10
5.000	11	94.000 -0.225 0.000 0.00
4.002	12	93.555 -0.070 0.000 0.08 6
6.000	13	93.807 -0.168 0.000 0.14
7.000	x	93.900 -0.225 0.000 0.00
4.003	14	93.548 0.153 0.000 0.18 10
8.000	15	94.000 -0.225 0.000 0.00
PN	US/MH Name	Pipe Flow (l/s) Status Level Exceeded
1.000		1 7.6 OK
1.001		2 14.0 OK
2.000		3 0.0 OK
1.002		4 10.0 OK
3.000	Dummy Rainfall L	0.0 OK
3.001	20	33.1 OK
1.003	5	40.8 OK
1.004	6	61.5 OK
1.005	7	60.5 OK
1.006	8	59.6 OK
4.000	9	3.0 OK
4.001	10	4.1 OK
5.000	11	0.0 OK
4.002	12	8.4 OK
6.000	13	7.8 OK
7.000	x	0.0 OK
4.003	14	16.5 SURCHARGED
8.000	15	0.0 OK
©1982-2020 Innovyze		

Waterman Group

Page 3

Pickfords Wharf
Clink Street
London, SE1 9DG

Date 13/07/2022 18:37
File PLOT 8+9_KAREN UPDATES.MDX

Designed by CSKRS
Checked by

Innovyze

Network 2020.1.3

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
4.004	16	30 Winter	2	+0%	2/15 Summer				93.535
4.005	17	30 Winter	2	+0%	100/240 Winter				92.809
9.000	21	15 Winter	2	+0%	100/15 Summer				93.476
9.001	22	15 Winter	2	+0%	30/15 Summer				92.709
1.007	18	480 Winter	2	+0%	30/15 Summer				92.034
10.000	22	15 Winter	2	+0%	30/15 Summer				93.377
10.001	23	15 Winter	2	+0%	30/15 Summer				93.377
1.008	19	480 Winter	2	+0%	2/240 Winter				92.032

PN	US/MH Name	Depth (m)	Surcharged Volume (m³)	Flooded Flow / Cap.	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
4.004	16	0.280	0.000	0.24		13 15.2	SURCHARGED	
4.005	17	-0.376	0.000	0.06		15.2	OK	
9.000	21	-0.149	0.000	0.24		13.4	OK	
9.001	22	-0.117	0.000	0.46		7 23.5	OK	
1.007	18	-0.076	0.000	0.13		26.1	OK	
10.000	22	-0.148	0.000	0.01		0.3	OK	
10.001	23	-0.081	0.000	0.74		28.1	OK	
1.008	19	0.057	0.000	0.03		4.9	SURCHARGED	

©1982-2020 Innovyze

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:38	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 2.000

Hot Start Level (mm) 0

Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 10

Number of Online Controls 3

Number of Time/Area Diagrams 0

Number of Offline Controls 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH

FEH Rainfall Version 2013

Site Location GB 435950 295750 SP 35950 95750

Data Type Catchment

Cv (Summer) 0.750

Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

DVD Status OFF

Analysis Timestep Fine Inertia Status OFF

DTS Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440

Return Period(s) (years) 2, 30, 100

Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
1.000		1 15 Winter	30	+0%	100/15 Winter		
1.001		2 15 Winter	30	+0%	30/15 Summer		
2.000		3 15 Summer	30	+0%			
1.002		4 15 Winter	30	+0%	30/15 Summer		
3.000	Dummy Rainfall L	15 Summer	30	+0%	100/15 Summer		
3.001		20 15 Summer	30	+0%	100/15 Summer		
1.003		5 15 Winter	30	+0%	100/15 Summer		
1.004		6 15 Winter	30	+0%	30/15 Summer		
1.005		7 15 Winter	30	+0%	100/15 Summer		
1.006		8 480 Winter	30	+0%	30/15 Winter		
4.000		9 15 Winter	30	+0%			
4.001		10 30 Winter	30	+0%	100/15 Summer		
5.000		11 15 Summer	30	+0%			
4.002		12 30 Winter	30	+0%	30/15 Summer		
6.000		13 30 Winter	30	+0%	100/15 Summer		
7.000		x 15 Summer	30	+0%	100/30 Winter		
4.003		14 30 Winter	30	+0%	2/15 Summer		
8.000		15 15 Summer	30	+0%			

©1982-2020 Innovyze

Waterman Group

Pickfords Wharf
Clink Street
London, SE1 9DG

Date 13/07/2022 18:38
File PLOT 8+9_KAREN UPDATES.MDX

Innovyze

Page 2



Designed by CSKRS
Checked by

Network 2020.1.3

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
1.000		1	94.081	-0.219	0.000	0.16		
1.001		2	93.953	0.145	0.000	0.21		7
2.000		3	94.000	-0.300	0.000	0.00		
1.002		4	93.942	0.339	0.000	0.14		9
3.000	Dummy Rainfall L		94.000	-0.100	0.000	0.00		
3.001		20	93.764	-0.109	0.000	0.73		4
1.003		5	93.331	-0.144	0.000	0.67		
1.004		6	93.123	0.083	0.000	1.48		
1.005		7	92.854	-0.046	0.000	0.96		
1.006		8	92.580	0.150	0.000	0.15		
4.000		9	94.046	-0.254	0.000	0.06		
4.001		10	93.889	-0.061	0.000	0.06		15
5.000		11	94.000	-0.225	0.000	0.00		
4.002		12	93.888	0.263	0.000	0.11		24
6.000		13	93.909	-0.066	0.000	0.24		
7.000		x	93.900	-0.225	0.000	0.00		
4.003		14	93.885	0.490	0.000	0.33		21
8.000		15	94.000	-0.225	0.000	0.00		

PN	US/MH Name	Pipe Flow (l/s)	Status	Level Exceeded
1.000		1 16.8	OK	
1.001		2 23.6	SURCHARGED	
2.000		3 0.0	OK	
1.002		4 16.0	SURCHARGED	
3.000	Dummy Rainfall L	0.0	OK	
3.001		20 93.8	OK	
1.003		5 103.5	OK	
1.004		6 158.8	SURCHARGED	
1.005		7 152.1	OK	
1.006		8 22.3	SURCHARGED	
4.000		9 6.7	OK	
4.001		10 7.7	OK	
5.000		11 0.0	OK	
4.002		12 11.1	SURCHARGED	
6.000		13 13.4	OK	
7.000		x 0.0	OK	
4.003		14 29.5	SURCHARGED	
8.000		15 0.0	OK	

©1982-2020 Innovyze

Waterman Group

Pickfords Wharf
Clink Street
London, SE1 9DG

Date 13/07/2022 18:38
File PLOT 8+9_KAREN UPDATES.MDX

Innovyze

Designed by CSKRS
Checked by

Network 2020.1.3

Page 3



30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
4.004	16	30 Winter	30	+0%	2/15 Summer				93.867
4.005	17	30 Winter	30	+0%	100/240 Winter				92.820
9.000	21	15 Winter	30	+0%	100/15 Summer				93.519
9.001	22	15 Winter	30	+0%	30/15 Summer				92.867
1.007	18	480 Winter	30	+0%	30/15 Summer				92.578
10.000	22	15 Winter	30	+0%	30/15 Summer				93.572
10.001	23	15 Winter	30	+0%	30/15 Summer				93.573
1.008	19	480 Winter	30	+0%	2/240 Winter				92.576

PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
4.004	16	0.612	0.000	0.31		23	19.4	SURCHARGED	
4.005	17	-0.365	0.000	0.08			19.4	OK	
9.000	21	-0.106	0.000	0.53			29.8	OK	
9.001	22	0.041	0.000	1.08		3	54.5	SURCHARGED	
1.007	18	0.468	0.000	0.22			45.7	SURCHARGED	
10.000	22	0.047	0.000	0.02			0.8	SURCHARGED	
10.001	23	0.115	0.000	1.64			62.4	SURCHARGED	
1.008	19	0.601	0.000	0.03			4.9	SURCHARGED	

©1982-2020 Innovyze

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:38	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze		Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 435950 295750 SP 35950 95750
Data Type	Catchment
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow
1.000		1 15 Winter	100	+40%	100/15 Winter		
1.001		2 15 Winter	100	+40%	30/15 Summer		
2.000		3 15 Winter	100	+40%			
1.002		4 15 Winter	100	+40%	30/15 Summer		
3.000	Dummy Rainfall	L 15 Winter	100	+40%	100/15 Summer		
3.001		20 15 Winter	100	+40%	100/15 Summer		
1.003		5 15 Winter	100	+40%	100/15 Summer		
1.004		6 15 Winter	100	+40%	30/15 Summer		
1.005		7 960 Winter	100	+40%	100/15 Summer		
1.006		8 960 Winter	100	+40%	30/15 Winter		
4.000		9 60 Winter	100	+40%			
4.001		10 60 Winter	100	+40%	100/15 Summer		
5.000		11 60 Winter	100	+40%			
4.002		12 60 Winter	100	+40%	30/15 Summer		
6.000		13 15 Winter	100	+40%	100/15 Summer		
7.000		x 60 Winter	100	+40%	100/30 Winter		
4.003		14 60 Winter	100	+40%	2/15 Summer		
8.000		15 60 Winter	100	+40%			

©1982-2020 Innovyze

Waterman Group								Page 3																																																																																											
Pickfords Wharf Clink Street London, SE1 9DG																																																																																																			
Date 13/07/2022 18:38					Designed by CSKRS																																																																																														
File PLOT 8+9_KAREN UPDATES.MDX					Checked by																																																																																														
Innovyze					Network 2020.1.3																																																																																														
<u>100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>																																																																																																			
<table><tr><th>PN</th><th>US/MH Name</th><th>Storm</th><th>Return Period</th><th>Climate Change</th><th>First (X) Surge</th><th>First (Y) Flood</th><th>First (Z) Overflow</th><th>Overflow Act.</th><th>Water Level (m)</th></tr><tr><td>4.004</td><td>16</td><td>60 Winter</td><td>100</td><td>+40%</td><td>2/15 Summer</td><td></td><td></td><td></td><td>94.138</td></tr><tr><td>4.005</td><td>17</td><td>960 Winter</td><td>100</td><td>+40%</td><td>100/240 Winter</td><td></td><td></td><td></td><td>93.955</td></tr><tr><td>9.000</td><td>21</td><td>15 Winter</td><td>100</td><td>+40%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>93.907</td></tr><tr><td>9.001</td><td>22</td><td>960 Winter</td><td>100</td><td>+40%</td><td>30/15 Summer</td><td></td><td></td><td></td><td>93.736</td></tr><tr><td>1.007</td><td>18</td><td>960 Winter</td><td>100</td><td>+40%</td><td>30/15 Summer</td><td></td><td></td><td></td><td>93.960</td></tr><tr><td>10.000</td><td>22</td><td>15 Winter</td><td>100</td><td>+40%</td><td>30/15 Summer</td><td></td><td></td><td></td><td>93.797</td></tr><tr><td>10.001</td><td>23</td><td>15 Winter</td><td>100</td><td>+40%</td><td>30/15 Summer</td><td></td><td></td><td></td><td>93.798</td></tr><tr><td>1.008</td><td>19</td><td>960 Winter</td><td>100</td><td>+40%</td><td>2/240 Winter</td><td></td><td></td><td></td><td>93.989</td></tr></table>										PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	4.004	16	60 Winter	100	+40%	2/15 Summer				94.138	4.005	17	960 Winter	100	+40%	100/240 Winter				93.955	9.000	21	15 Winter	100	+40%	100/15 Summer				93.907	9.001	22	960 Winter	100	+40%	30/15 Summer				93.736	1.007	18	960 Winter	100	+40%	30/15 Summer				93.960	10.000	22	15 Winter	100	+40%	30/15 Summer				93.797	10.001	23	15 Winter	100	+40%	30/15 Summer				93.798	1.008	19	960 Winter	100	+40%	2/240 Winter				93.989
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)																																																																																										
4.004	16	60 Winter	100	+40%	2/15 Summer				94.138																																																																																										
4.005	17	960 Winter	100	+40%	100/240 Winter				93.955																																																																																										
9.000	21	15 Winter	100	+40%	100/15 Summer				93.907																																																																																										
9.001	22	960 Winter	100	+40%	30/15 Summer				93.736																																																																																										
1.007	18	960 Winter	100	+40%	30/15 Summer				93.960																																																																																										
10.000	22	15 Winter	100	+40%	30/15 Summer				93.797																																																																																										
10.001	23	15 Winter	100	+40%	30/15 Summer				93.798																																																																																										
1.008	19	960 Winter	100	+40%	2/240 Winter				93.989																																																																																										
<table><tr><th>PN</th><th>US/MH Name</th><th>Depth (m)</th><th>Volume (m³)</th><th>Flow / Cap.</th><th>Overflow (l/s)</th><th>Half Drain Time (mins)</th><th>Pipe Flow (l/s)</th><th>Status</th><th>Level Exceeded</th></tr><tr><td>4.004</td><td>16</td><td>0.883</td><td>0.000</td><td>0.36</td><td></td><td></td><td>42</td><td>22.2</td><td>SURCHARGED</td></tr><tr><td>4.005</td><td>17</td><td>0.770</td><td>0.000</td><td>0.05</td><td></td><td></td><td></td><td>11.3</td><td>SURCHARGED</td></tr><tr><td>9.000</td><td>21</td><td>0.282</td><td>0.000</td><td>0.84</td><td></td><td></td><td></td><td>47.4</td><td>FLOOD RISK</td></tr><tr><td>9.001</td><td>22</td><td>0.910</td><td>0.000</td><td>0.15</td><td></td><td></td><td>304</td><td>7.5</td><td>SURCHARGED</td></tr><tr><td>1.007</td><td>18</td><td>1.850</td><td>0.000</td><td>0.22</td><td></td><td></td><td></td><td>45.8</td><td>SURCHARGED</td></tr><tr><td>10.000</td><td>22</td><td>0.272</td><td>0.000</td><td>0.03</td><td></td><td></td><td></td><td>1.3</td><td>SURCHARGED</td></tr><tr><td>10.001</td><td>23</td><td>0.340</td><td>0.000</td><td>2.39</td><td></td><td></td><td></td><td>91.2</td><td>SURCHARGED</td></tr><tr><td>1.008</td><td>19</td><td>2.014</td><td>0.000</td><td>0.04</td><td></td><td></td><td></td><td>6.0</td><td>SURCHARGED</td></tr></table>										PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded	4.004	16	0.883	0.000	0.36			42	22.2	SURCHARGED	4.005	17	0.770	0.000	0.05				11.3	SURCHARGED	9.000	21	0.282	0.000	0.84				47.4	FLOOD RISK	9.001	22	0.910	0.000	0.15			304	7.5	SURCHARGED	1.007	18	1.850	0.000	0.22				45.8	SURCHARGED	10.000	22	0.272	0.000	0.03				1.3	SURCHARGED	10.001	23	0.340	0.000	2.39				91.2	SURCHARGED	1.008	19	2.014	0.000	0.04				6.0	SURCHARGED
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded																																																																																										
4.004	16	0.883	0.000	0.36			42	22.2	SURCHARGED																																																																																										
4.005	17	0.770	0.000	0.05				11.3	SURCHARGED																																																																																										
9.000	21	0.282	0.000	0.84				47.4	FLOOD RISK																																																																																										
9.001	22	0.910	0.000	0.15			304	7.5	SURCHARGED																																																																																										
1.007	18	1.850	0.000	0.22				45.8	SURCHARGED																																																																																										
10.000	22	0.272	0.000	0.03				1.3	SURCHARGED																																																																																										
10.001	23	0.340	0.000	2.39				91.2	SURCHARGED																																																																																										
1.008	19	2.014	0.000	0.04				6.0	SURCHARGED																																																																																										
©1982-2020 Innovyze																																																																																																			

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 10:15 File PLOT 8+9_KAREN UPDATES.MDX	Designed by CSKRS Checked by	
Innovyze Network 2020.1.3		

Summary Wizard of 360 minute 100 year Winter I+40% for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 435950 295750 SP 35950 95750
Data Type	Catchment
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Event	US/CL (m)	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)
1.000		1 360 minute 100 year Winter I+40%	94.850	94.042	-0.258	0.000
1.001		2 360 minute 100 year Winter I+40%	95.100	93.592	-0.216	0.000
2.000		3 360 minute 100 year Winter I+40%	94.850	94.000	-0.300	0.000
1.002		4 360 minute 100 year Winter I+40%	95.050	93.584	-0.019	0.000
3.000	Dummy Rainfall	L 360 minute 100 year Winter I+40%	95.100	94.000	-0.100	0.000
3.001		20 360 minute 100 year Winter I+40%	95.100	93.664	-0.209	0.000
1.003		5 360 minute 100 year Winter I+40%	95.000	93.498	0.023	0.000
1.004		6 360 minute 100 year Winter I+40%	94.450	93.494	0.454	0.000
1.005		7 360 minute 100 year Winter I+40%	94.150	93.491	0.591	0.000
1.006		8 360 minute 100 year Winter I+40%	94.600	93.487	1.057	0.000
4.000		9 360 minute 100 year Winter I+40%	95.100	94.024	-0.276	0.000
4.001		10 360 minute 100 year Winter I+40%	94.850	93.896	-0.054	0.000
5.000		11 360 minute 100 year Winter I+40%	95.100	94.000	-0.225	0.000
4.002		12 360 minute 100 year Winter I+40%	94.850	93.893	0.268	0.000
6.000		13 360 minute 100 year Winter I+40%	94.950	93.897	-0.078	0.000
7.000		x 360 minute 100 year Winter I+40%	94.950	93.900	-0.225	0.000
4.003		14 360 minute 100 year Winter I+40%	94.700	93.886	0.491	0.000
8.000		15 360 minute 100 year Winter I+40%	94.850	94.000	-0.225	0.000
4.004		16 360 minute 100 year Winter I+40%	94.700	93.870	0.615	0.000

©1982-2020 Innovyze

Waterman Group		Page 2
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 10:15	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

Summary Wizard of 360 minute 100 year Winter I+40% for Storm


PN	US/MH Name	Flow / Overflow		Discharge		Pipe Flow	Status
		Cap.	(l/s)	Vol	(m³)	(l/s)	
1.000		1	0.05		43.532	5.1	OK
1.001		2	0.09		85.805	10.1	OK
2.000		3	0.00		0.000	0.0	OK
1.002		4	0.09		85.816	10.0	OK
3.000	Dummy Rainfall L		0.00		0.000	0.0	OK
3.001		20	0.20		222.313	25.9	OK
1.003		5	0.23		307.481	35.8	SURCHARGED
1.004		6	0.50		449.962	53.5	SURCHARGED
1.005		7	0.34		447.957	53.3	SURCHARGED
1.006		8	0.34		438.978	49.9	SURCHARGED
4.000		9	0.02		17.101	2.0	OK
4.001		10	0.03		36.501	4.0	OK
5.000		11	0.00		0.000	0.0	OK
4.002		12	0.08		88.812	7.7	SURCHARGED
6.000		13	0.09		45.089	5.1	OK
7.000		x	0.00		0.000	0.0	OK
4.003		14	0.22		217.664	20.1	SURCHARGED
8.000		15	0.00		0.000	0.0	OK
4.004		16	0.31		215.564	19.3	SURCHARGED

Waterman Group		Page 3
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 10:15	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

Summary Wizard of 360 minute 100 year Winter I+40% for Storm

PN	US/MH Name	Event	Water Surcharged Flooded				Flow / Cap.
			US/CL (m)	Level (m)	Depth (m)	Volume (m³)	
4.005	17	360 minute 100 year Winter I+40%	94.700	93.485	0.300	0.000	0.08
9.000	21	360 minute 100 year Winter I+40%	94.150	93.488	-0.137	0.000	0.16
9.001	22	360 minute 100 year Winter I+40%	94.300	93.486	0.660	0.000	0.34
1.007	18	360 minute 100 year Winter I+40%	94.500	93.483	1.373	0.000	0.48
10.000	22	360 minute 100 year Winter I+40%	94.600	93.481	-0.044	0.000	0.00
10.001	23	360 minute 100 year Winter I+40%	94.600	93.481	0.023	0.000	0.64
1.008	19	360 minute 100 year Winter I+40%	94.300	93.481	1.506	0.000	0.03

PN	US/MH Name	Overflow (l/s)	Discharge Vol (m³)	Pipe Flow	
				(l/s)	Status
4.005	17		213.750	19.1	SURCHARGED
9.000	21		77.733	9.1	OK
9.001	22		141.721	17.1	SURCHARGED
1.007	18		922.663	98.3	SURCHARGED
10.000	22		-0.005	0.0	OK
10.001	23		205.906	24.4	SURCHARGED
1.008	19		211.734	5.7	SURCHARGED

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 10:21 File PLOT 8+9_KAREN UPDATES.MDX		
Designed by CSKRS Checked by		
Innovyze		Network 2020.1.3

Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	20.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s) Summer and Winter

Duration(s) (mins)	15, 30
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
1.000		1 15 Winter	100	+40%	100/15 Summer		
1.001		2 15 Winter	100	+40%	30/15 Summer		
2.000		3 15 Winter	100	+40%	100/15 Winter		
1.002		4 15 Winter	100	+40%	2/15 Summer		
3.000	Dummy Rainfall L	15 15 Winter	100	+40%	100/15 Summer		
3.001		20 15 Winter	100	+40%	100/15 Summer		
1.003		5 15 Winter	100	+40%	100/15 Summer		
1.004		6 15 Winter	100	+40%	30/15 Summer		
1.005		7 15 Winter	100	+40%	30/15 Summer		
1.006		8 15 Winter	100	+40%	30/15 Summer		
4.000		9 30 Winter	100	+40%			
4.001		10 30 Winter	100	+40%	100/15 Summer		
5.000		11 30 Winter	100	+40%			
4.002		12 30 Winter	100	+40%	2/15 Summer		
6.000		13 15 Winter	100	+40%	100/15 Summer		
7.000		x 30 Winter	100	+40%	100/30 Winter		
4.003		14 30 Winter	100	+40%	2/15 Summer		
8.000		15 30 Winter	100	+40%			
4.004		16 30 Winter	100	+40%	2/15 Summer		
4.005		17 30 Winter	100	+40%			
9.000		21 15 Winter	100	+40%	100/15 Summer		
9.001		22 15 Winter	100	+40%	30/15 Summer		

©1982-2020 Innovyze

Waterman Group							Page 2	
Pickfords Wharf Clink Street London, SE1 9DG								
Date 13/07/2022 10:21 File PLOT 8+9_KAREN UPDATES.MDX			Designed by CSKRS Checked by					
Innovyze			Network 2020.1.3					
Summary of Critical Results by Maximum Level (Rank 1) for Storm								
PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)
1.000		1	94.381	0.081	0.000	0.29		
1.001		2	94.363	0.555	0.000	0.37		15
2.000		3	94.352	0.052	0.000	0.01		
1.002		4	94.352	0.749	0.000	0.19		13
3.000	Dummy Rainfall L		94.845	0.745	0.000	0.80		
3.001		20	94.948	1.075	0.000	1.05		5
1.003		5	94.510	1.035	0.000	0.80		
1.004		6	94.243	1.203	0.000	2.05		
1.005		7	93.931	1.031	0.000	1.33		
1.006		8	93.096	0.666	0.000	1.42		
4.000		9	94.212	-0.088	0.000	0.09		
4.001		10	94.210	0.260	0.000	0.05		
5.000		11	94.206	-0.019	0.000	0.00		
4.002		12	94.206	0.581	0.000	0.12		24
6.000		13	94.250	0.275	0.000	0.59		
7.000		x	94.197	0.072	0.000	0.00		
4.003		14	94.197	0.802	0.000	0.49		32
8.000		15	94.176	-0.049	0.000	0.00		
4.004		16	94.176	0.921	0.000	0.36		
4.005		17	92.828	-0.357	0.000	0.09		
9.000		21	94.081	0.456	0.000	0.91		
9.001		22	93.398	0.572	0.000	1.68		4
				Pipe Flow (l/s)		Level Exceeded		
	PN	US/MH Name		Status				
	1.000		1	30.4	SURCHARGED			
	1.001		2	41.8	SURCHARGED			
	2.000		3	0.6	SURCHARGED			
	1.002		4	20.7	SURCHARGED			
	3.000	Dummy Rainfall L	6.0	FLOOD RISK				
	3.001		20	135.7	FLOOD RISK			
	1.003		5	122.0	SURCHARGED			
	1.004		6	219.7	FLOOD RISK			
	1.005		7	210.2	FLOOD RISK			
	1.006		8	207.7	SURCHARGED			
	4.000		9	10.7	OK			
	4.001		10	6.7	SURCHARGED			
	5.000		11	0.2	OK			
	4.002		12	12.2	SURCHARGED			
	6.000		13	32.5	SURCHARGED			
	7.000		x	0.2	SURCHARGED			
	4.003		14	44.1	SURCHARGED			
	8.000		15	0.2	OK			
	4.004		16	22.6	SURCHARGED			
	4.005		17	22.6	OK			
©1982-2020 Innovyze								

Waterman Group			Page 3	
Pickfords Wharf Clink Street London, SE1 9DG				
Date 13/07/2022 10:21		Designed by CSKRS		
File PLOT 8+9_KAREN UPDATES.MDX		Checked by		
Innovyze		Network 2020.1.3		
<u>Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>				
PN	US/MH Name	Pipe Flow (l/s)	Status	Level Exceeded
9.000		21 51.2	FLOOD RISK	
9.001		22 85.1	SURCHARGED	
©1982-2020 Innovyze				

Waterman Group		Page 4
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 10:21 File PLOT 8+9_KAREN UPDATES.MDX	Designed by CSKRS Checked by	
Innovyze		Network 2020.1.3

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH		Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level
	Name	Storm							(m)
1.007	18	30 Winter	100	+40%	30/15 Summer				92.514
10.000	22	15 Winter	100	+40%	30/15 Winter				93.760
10.001	23	15 Winter	100	+40%	30/15 Summer				93.761
1.008	19	30 Winter	100	+40%	30/30 Summer				92.506

PN	US/MH Name	Surcharged		Flooded		Flow / Overflow Cap.	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow (l/s)	Overflow (l/s)					
1.007	18	0.404	0.000	1.76				360.6	SURCHARGED	
10.000	22	0.235	0.000	0.02				0.9	SURCHARGED	
10.001	23	0.303	0.000	2.29				87.3	SURCHARGED	
1.008	19	0.531	0.000	0.03				4.9	SURCHARGED	

Waterman Group		Page 1
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:36	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	47.602	0.492	96.8	0.056	5.00	0.0	0.600	o	300	Pipe/Conduit	
1.001	9.840	0.205	48.0	0.056	0.00	0.0	0.600	o	300	Pipe/Conduit	
2.000	54.149	0.647	83.7	0.000	5.00	0.0	0.600	o	300	Pipe/Conduit	
1.002	14.126	0.203	69.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
3.000	13.295	0.227	58.6	0.000	5.00	0.0	0.600	o	100	Pipe/Conduit	
3.001	23.407	0.400	58.5	0.286	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.003	65.470	0.435	150.5	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.004	9.522	0.065	146.5	0.195	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.005	66.961	0.470	142.5	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.006	51.326	0.320	160.4	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
4.000	24.742	0.350	70.7	0.022	5.00	0.0	0.600	o	300	Pipe/Conduit	
4.001	19.975	0.325	61.5	0.026	0.00	0.0	0.600	o	300	Pipe/Conduit	
5.000	34.013	0.600	56.7	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit	
4.002	21.028	0.230	91.4	0.069	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.50	94.000	0.056	0.0	0.0	0.0	1.60	113.0	7.6
1.001	50.00	5.57	93.508	0.112	0.0	0.0	0.0	2.28	160.8	15.2
2.000	50.00	5.52	94.000	0.000	0.0	0.0	0.0	1.72	121.6	0.0
1.002	50.00	5.69	93.303	0.112	0.0	0.0	0.0	1.89	133.4	15.2
3.000	50.00	5.22	94.000	0.000	0.0	0.0	0.0	1.01	7.9	0.0
3.001	50.00	5.41	93.573	0.286	0.0	0.0	0.0	2.06	145.6	38.7
1.003	50.00	6.43	93.100	0.398	0.0	0.0	0.0	1.47	162.9	53.9
1.004	50.00	6.54	92.665	0.593	0.0	0.0	0.0	1.49	165.1	80.3
1.005	50.00	7.28	92.525	0.593	0.0	0.0	0.0	1.52	167.4	80.3
1.006	50.00	7.87	92.055	0.593	0.0	0.0	0.0	1.43	157.7	80.3
4.000	50.00	5.22	94.000	0.022	0.0	0.0	0.0	1.87	132.4	3.0
4.001	50.00	5.39	93.650	0.048	0.0	0.0	0.0	2.01	142.0	6.5
5.000	50.00	5.33	94.000	0.000	0.0	0.0	0.0	1.74	69.2	0.0
4.002	50.00	5.60	93.325	0.117	0.0	0.0	0.0	1.64	116.3	15.8

Waterman Group											Page 2	
Pickfords Wharf Clink Street London, SE1 9DG												
Date 13/07/2022 18:36 File PLOT 8+9_KAREN UPDATES.MDX						Designed by CSKRS Checked by						
Innovyze						Network 2020.1.3						
<u>STORM SEWER DESIGN by the Modified Rational Method</u>												
<u>Network Design Table for Storm</u>												
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design	
6.000	47.934	0.580	82.6	0.058	5.00	0.0	0.600	o	225	Pipe/Conduit		
7.000	14.472	0.125	115.8	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit		
4.003	14.669	0.140	104.8	0.112	0.00	0.0	0.600	o	300	Pipe/Conduit		
8.000	53.294	0.920	57.9	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit		
4.004	15.956	0.070	227.9	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit		
4.005	69.428	0.434	160.0	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit		
9.000	63.880	0.799	79.9	0.100	5.00	0.0	0.600	o	225	Pipe/Conduit		
9.001	28.870	0.316	91.4	0.089	0.00	0.0	0.600	o	225	Pipe/Conduit		
1.007	23.007	0.135	170.4	0.194	0.00	0.0	0.600	o	450	Pipe/Conduit		
10.000	6.723	0.067	100.0	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit		
10.001	7.313	0.073	100.2	0.271	0.00	0.0	0.600	o	225	Pipe/Conduit		
1.008	7.851	0.055	142.7	0.041	0.00	0.0	0.600	o	450	Pipe/Conduit		
<u>Network Results Table</u>												
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)		
6.000	50.00	5.56	93.750	0.058	0.0	0.0	0.0	1.44	57.2	7.9		
7.000	50.00	5.20	93.900	0.000	0.0	0.0	0.0	1.21	48.3	0.0		
4.003	50.00	5.76	93.095	0.287	0.0	0.0	0.0	1.54	108.6	38.9		
8.000	50.00	5.52	94.000	0.000	0.0	0.0	0.0	1.72	68.5	0.0		
4.004	50.00	6.01	92.955	0.287	0.0	0.0	0.0	1.04	73.3	38.9		
4.005	50.00	6.74	92.735	0.287	0.0	0.0	0.0	1.60	255.2	38.9		
9.000	50.00	5.73	93.400	0.100	0.0	0.0	0.0	1.46	58.2	13.5		
9.001	50.00	6.08	92.601	0.189	0.0	0.0	0.0	1.37	54.4	25.6		
1.007	50.00	8.12	91.660	1.263	0.0	0.0	0.0	1.55	247.2	171.0		
10.000	50.00	5.09	93.300	0.000	0.0	0.0	0.0	1.31	52.0	0.0		
10.001	50.00	5.18	93.233	0.271	0.0	0.0	0.0	1.31	51.9	36.7		
1.008	50.00	8.20	91.525	1.575	0.0	0.0	0.0	1.70	270.3	213.3		
©1982-2020 Innovyze												

Waterman Group		Page 3
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:36	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.056	0.056	0.056
1.001	-	-	100	0.056	0.056	0.056
2.000	-	-	100	0.000	0.000	0.000
1.002	-	-	100	0.000	0.000	0.000
3.000	-	-	100	0.000	0.000	0.000
3.001	-	-	100	0.286	0.286	0.286
1.003	-	-	100	0.000	0.000	0.000
1.004	-	-	100	0.195	0.195	0.195
1.005	-	-	100	0.000	0.000	0.000
1.006	-	-	100	0.000	0.000	0.000
4.000	-	-	100	0.022	0.022	0.022
4.001	-	-	100	0.026	0.026	0.026
5.000	-	-	100	0.000	0.000	0.000
4.002	-	-	100	0.069	0.069	0.069
6.000	-	-	100	0.058	0.058	0.058
7.000	-	-	100	0.000	0.000	0.000
4.003	-	-	100	0.112	0.112	0.112
8.000	-	-	100	0.000	0.000	0.000
4.004	-	-	100	0.000	0.000	0.000
4.005	-	-	100	0.000	0.000	0.000
9.000	-	-	100	0.100	0.100	0.100
9.001	-	-	100	0.089	0.089	0.089
1.007	-	-	100	0.194	0.194	0.194
10.000	-	-	100	0.000	0.000	0.000
10.001	-	-	100	0.271	0.271	0.271
1.008	-	-	100	0.041	0.041	0.041
				Total	Total	Total
				1.575	1.575	1.575

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
Return Period (years)	100
FEH Rainfall Version	1999
Site Location GB 435950 295750 SP 35950 95750	
C (1km)	-0.026

Waterman Group		Page 4
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:36	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze		Network 2020.1.3
<u>Synthetic Rainfall Details</u> D1 (1km) 0.357 D2 (1km) 0.322 D3 (1km) 0.235 E (1km) 0.302 F (1km) 2.394 Summer Storms Yes Winter Storms Yes Cv (Summer) 0.750 Cv (Winter) 0.840 Storm Duration (mins) 30		
©1982-2020 Innovyze		

Waterman Group		Page 5
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:36	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze		Network 2020.1.3

Online Controls for Storm

Orifice Manhole: 4, DS/PN: 1.002, Volume (m³): 6.3

Diameter (m) 0.100 Discharge Coefficient 0.600 Invert Level (m) 93.303

Orifice Manhole: 16, DS/PN: 4.004, Volume (m³): 5.0

Diameter (m) 0.100 Discharge Coefficient 0.600 Invert Level (m) 92.955

Hydro-Brake® Optimum Manhole: 19, DS/PN: 1.008, Volume (m³): 7.7

Unit Reference	MD-SHE-0098-6000-2200-6000
Design Head (m)	2.200
Design Flow (l/s)	6.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	98
Invert Level (m)	91.525
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	2.200	6.0
Flush-Flo™	0.428	4.9
Kick-Flo®	0.876	3.9
Mean Flow over Head Range	-	4.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.2	1.200	4.5	3.000	6.9	7.000	10.4
0.200	4.5	1.400	4.9	3.500	7.5	7.500	10.7
0.300	4.8	1.600	5.2	4.000	7.9	8.000	11.0
0.400	4.9	1.800	5.5	4.500	8.4	8.500	11.4
0.500	4.9	2.000	5.7	5.000	8.8	9.000	11.7
0.600	4.8	2.200	6.0	5.500	9.2	9.500	12.0
0.800	4.3	2.400	6.2	6.000	9.6		
1.000	4.2	2.600	6.5	6.500	10.0		

©1982-2020 Innovyze

Waterman Group		Page 6
Pickfords Wharf Clink Street London, SE1 9DG		
Date 13/07/2022 18:36	Designed by CSKRS	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by	
Innovyze	Network 2020.1.3	

Storage Structures for Storm

Porous Car Park Manhole: 2, DS/PN: 1.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	2.3
Membrane Percolation (mm/hr)	1000	Length (m)	110.0
Max Percolation (l/s)	70.3	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	94.000	Cap Volume Depth (m)	0.400

Porous Car Park Manhole: 4, DS/PN: 1.002

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	5.0
Membrane Percolation (mm/hr)	1000	Length (m)	40.0
Max Percolation (l/s)	55.6	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	94.000	Cap Volume Depth (m)	0.400

Trench Soakaway Manhole: 20, DS/PN: 3.001

Infiltration Coefficient Base (m/hr)	0.00000	Trench Width (m)	1.5
Infiltration Coefficient Side (m/hr)	0.00000	Trench Length (m)	20.0
Safety Factor	2.0	Slope (1:X)	80.0
Porosity	0.30	Cap Volume Depth (m)	0.500
Invert Level (m)	93.573	Cap Infiltration Depth (m)	0.000

Complex Manhole: 10, DS/PN: 4.001

Porous Car Park

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	40.0
Membrane Percolation (mm/hr)	1000	Length (m)	2.0
Max Percolation (l/s)	22.2	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	93.650	Cap Volume Depth (m)	0.400

Porous Car Park

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	2.0
Membrane Percolation (mm/hr)	1000	Length (m)	40.0
Max Percolation (l/s)	22.2	Slope (1:X)	100.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	93.650	Cap Volume Depth (m)	0.400

Waterman Group		Page 7																																																																																																																
Pickfords Wharf Clink Street London, SE1 9DG																																																																																																																		
Date 13/07/2022 18:36	Designed by CSKRS																																																																																																																	
File PLOT 8+9_KAREN UPDATES.MDX	Checked by																																																																																																																	
Innovyze	Network 2020.1.3																																																																																																																	
<u>Porous Car Park Manhole: 12, DS/PN: 4.002</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>3.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>90.0</td></tr><tr><td>Max Percolation (l/s)</td><td>75.0</td><td>Slope (1:X)</td><td>100.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>93.800</td><td>Cap Volume Depth (m)</td><td>0.400</td></tr></table> <u>Porous Car Park Manhole: 14, DS/PN: 4.003</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>4.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>104.0</td></tr><tr><td>Max Percolation (l/s)</td><td>115.6</td><td>Slope (1:X)</td><td>100.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>93.600</td><td>Cap Volume Depth (m)</td><td>0.400</td></tr></table> <u>Porous Car Park Manhole: 16, DS/PN: 4.004</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>2.7</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>40.0</td></tr><tr><td>Max Percolation (l/s)</td><td>30.0</td><td>Slope (1:X)</td><td>100.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>93.600</td><td>Cap Volume Depth (m)</td><td>0.400</td></tr></table> <u>Infiltration Trench Manhole: 22, DS/PN: 9.001</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Trench Width (m)</td><td>1.2</td></tr><tr><td>Infiltration Coefficient Side (m/hr)</td><td>0.00000</td><td>Trench Length (m)</td><td>120.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Slope (1:X)</td><td>100.0</td></tr><tr><td>Porosity</td><td>0.30</td><td>Cap Volume Depth (m)</td><td>1.000</td></tr><tr><td>Invert Level (m)</td><td>93.000</td><td>Cap Infiltration Depth (m)</td><td>0.000</td></tr></table> <u>Tank or Pond Manhole: 23, DS/PN: 10.001</u> Invert Level (m) 93.233 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>15.0</td><td>1.000</td><td>162.0</td></tr></table> <u>Tank or Pond Manhole: 19, DS/PN: 1.008</u> Invert Level (m) 91.525 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>530.0</td><td>2.000</td><td>530.0</td><td>2.001</td><td>0.0</td></tr></table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	3.0	Membrane Percolation (mm/hr)	1000	Length (m)	90.0	Max Percolation (l/s)	75.0	Slope (1:X)	100.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	93.800	Cap Volume Depth (m)	0.400	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.0	Membrane Percolation (mm/hr)	1000	Length (m)	104.0	Max Percolation (l/s)	115.6	Slope (1:X)	100.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	93.600	Cap Volume Depth (m)	0.400	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	2.7	Membrane Percolation (mm/hr)	1000	Length (m)	40.0	Max Percolation (l/s)	30.0	Slope (1:X)	100.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	93.600	Cap Volume Depth (m)	0.400	Infiltration Coefficient Base (m/hr)	0.00000	Trench Width (m)	1.2	Infiltration Coefficient Side (m/hr)	0.00000	Trench Length (m)	120.0	Safety Factor	2.0	Slope (1:X)	100.0	Porosity	0.30	Cap Volume Depth (m)	1.000	Invert Level (m)	93.000	Cap Infiltration Depth (m)	0.000	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	15.0	1.000	162.0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	530.0	2.000	530.0	2.001	0.0
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	3.0																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	90.0																																																																																																															
Max Percolation (l/s)	75.0	Slope (1:X)	100.0																																																																																																															
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																															
Invert Level (m)	93.800	Cap Volume Depth (m)	0.400																																																																																																															
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.0																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	104.0																																																																																																															
Max Percolation (l/s)	115.6	Slope (1:X)	100.0																																																																																																															
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																															
Invert Level (m)	93.600	Cap Volume Depth (m)	0.400																																																																																																															
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	2.7																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	40.0																																																																																																															
Max Percolation (l/s)	30.0	Slope (1:X)	100.0																																																																																																															
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																															
Invert Level (m)	93.600	Cap Volume Depth (m)	0.400																																																																																																															
Infiltration Coefficient Base (m/hr)	0.00000	Trench Width (m)	1.2																																																																																																															
Infiltration Coefficient Side (m/hr)	0.00000	Trench Length (m)	120.0																																																																																																															
Safety Factor	2.0	Slope (1:X)	100.0																																																																																																															
Porosity	0.30	Cap Volume Depth (m)	1.000																																																																																																															
Invert Level (m)	93.000	Cap Infiltration Depth (m)	0.000																																																																																																															
Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																																																																															
0.000	15.0	1.000	162.0																																																																																																															
Depth (m)	Area (m²)	Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																																																																													
0.000	530.0	2.000	530.0	2.001	0.0																																																																																																													
©1982-2020 Innovyze																																																																																																																		


E. Proposed Overland Flow Exceedance Routes

Appendices

MIRA Technology Park – Plot 8 & 9 part of the LIF 2 Northern Masterplan

Project Number: EED13833-120

Document Reference: EED13833-120-R-1.1.2-FRA



This drawing should not be scaled. Dimensions to be verified on site. Any discrepancies should be referred to the Engineer prior to work being put in hand.

This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied, reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited
Pickfords Wharf, Clink Street, London SE1 9DG 1 020 7928 7898 1 03333 444 501

GENERAL NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEER'S, ARCHITECT'S OR OTHER RELEVANT DRAWINGS AND SPECIFICATIONS.
- ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
- THE CONTRACTOR MUST ENSURE AND WILL BE HELD RESPONSIBLE FOR THE OVERALL STABILITY OF THE BUILDING/STRUCTURE/EXCAVATION AT ALL STAGES OF THE WORK.
- ALL WORK BY THE CONTRACTOR MUST BE CARRIED OUT IN SUCH A WAY THAT ALL REQUIREMENTS UNDER THE HEALTH AND SAFETY AT WORK ACT ARE SATISFIED.
- ALL WORK IS TO BE CARRIED OUT IN COMPLIANCE WITH THE REQUIREMENTS OF THE RELEVANT STATUTORY AUTHORITIES AND REGULATIONS.

KEY:

RED LINE BOUNDARY

PROPOSED OVERLAND FLOW PATH

REV	08.07.22	FIRST ISSUE	AS	SP
Status	Date	Description	By	Cik
Amendments				
Project				
PLOT 8 & 9 - POLESTAR				
Title				
PROPOSED OVERLAND FLOW EXCEEDANCE ROUTES AND LEVELS				
Client				
SWANVALE DEVELOPMENTS LTD				
5th Floor One Cornwall Street Birmingham B3 2DX t 0121 212 7700 mail@watermangroup.com www.watermangroup.com				
Status				
PRELIMINARY				
Designed By	AS	Director	SP	Waterman Ref
				WIE13833
Drawn By	AS	Date	JULY 2022	Scales @ A1
				1:500
Project - Originator - Volume - Level - Type - Role - Number				Revision
13833-WIE-ZZ-XX-DR-D-92202				P01


F. Severn Trent Asset Location Records

Appendices

MIRA Technology Park – Plot 8 & 9 part of the LIF 2 Northern Masterplan

Project Number: EED13833-120

Document Reference: EED13833-120-R-1.1.2-FRA



Reference	Cover Level	Invert Level Upstream	Invert Level Downstream	Purpose	Material	Pipe Shape	Max Size	Min Size	Gradient	Year Laid
SP36951354	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP36951350	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP35945950	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	<UNK>	31/12/1899 00:00:00
SP36950350	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP35959150	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP36950351	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP36951351	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP36951352	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00
SP35948950	<UNK>	<UNK>	<UNK>	F	VC	C	225	<UNK>	0	31/12/1899 00:00:00

LEGEND

LandlineLine

Polygon Closing Line

Property Closing Line

Bottom Of Slope

Top Of Slope

Step

Mean High Water

Traffic Calming

Standard Gauge Track

Bottom Of Cliff

Top Of Cliff

Mean Low Water

Path

Overhead Construction

Culvert

Pylon

Ridge Or Rock Line

Narrow Gauge Track

Railway Buffer

Tunnel Edge

Line Of Posts

Drain

Default Line

Building Outline

Edge Line

Road Or Track

Building Division

Inland water Line

General Surface Natural Line

Building Overhead Line

Landform Natural Line

Historic Interest Line

Landform Manmade Line

Unclassified

LandlineArea

Other

Mixed Woodland Fill

Nonconiferous Tree Fill

Coniferous Tree Fill

Orchard Fill

Coppice Or Osier Fill

Scrub Fill

Boulders Fill

Rock Fill

Scree Fill

Rough Grassland Fill

Heath Fill

Saltmarsh Fill

Marsh Fill

Reeds Fill

Slope Fill

Cliff Fill

Ancillary

Balancing Lagoon

Grass Trap

Interceptor

Screen

Chamber

Flushing Chamber

Scalway

Overflow

Fitting

Blind Shaft

Facility Connector

Head Node

Lamphole

Sewerage Air Valve

Sewerage Chemical Injection Point

Sewerage Hatch Box

Sewerage Pressure Washout

Vent Column

Waste Water Outfall

Control Valve

Hydrobrake

Penstock

Sewerage Isolation Valve

Sewerage Non Return Valve

Manhole

Foul Effluence Manhole

Combined Effluence Manhole

Surface Water Effluence Manhole

Dual Manhole

Foul Single Manhole

Combined Single Manhole

Surface Water Single Manhole

Twin Manhole

Foul Adopted Manhole

Combined Adopted Manhole

Surface Adopted Manhole

Transfered Manhole

Unsurveyed Manhole

Operational Site

Waste Water Pump

S104

Transfered Asset

S102

Null STW

Adopted Sewer

None

Highway Drain

Null Private

S24

Storage

Disposal Site

Off-Line Waste Water Storage

On-Line Waste Water Storage

Wet Wall

Waste Water Process Structure

STP

STP

STP

Sludge Treatment Point

Sludge Treatment Structure

Gravity Sewer Pipe

Foul Gravity Sewer

Combined Gravity Sewer

Surface Water Gravity Sewer

S104 Surface Water Gravity Sewer

S104 Combined Gravity Sewer

S104 Foul Gravity Sewer

Private Surface Water Gravity Sewer

Private Combined Gravity Sewer

Private Foul Gravity Sewer

Surface Water Unserved Pipe

Combined Unserved Pipe

Foul Unserved Pipe

Transfered Surface Water Sewer

Transfered Combined Sewer

Transfered Foul Sewer

Disposal Pipe

Overflow Pipe

Culverted Water Course

Waste Internal Site Pipe

Sewer Service Connection

Gravity Sewer Others

Pressure Sewer Pipe

Surface Water Pressure Sewer

Combined Pressure Sewer

Foul Pressure Sewer

S104 Surface Water Pressure Sewer

S104 Combined Pressure Sewer

S104 Foul Pressure Sewer

Private Surface Water Pressure Sewer

Private Combined Pressure Sewer

Private Foul Pressure Sewer

Surface Water Vacuum Sewer

Foul Vacuum Sewer

Combined Vacuum Sewer

S104 Surface Water Vacuum Sewer

S104 Combined Vacuum Sewer

S104 Foul Vacuum Sewer

Private Surface Water Vacuum Sewer

Private Combined Vacuum Sewer

Private Foul Vacuum Sewer

Surface Water Siphon

Combined Siphon

Foul Siphon

Private Surface Water Siphon

Private Combined Siphon

Private Foul Siphon

S104 Surface Water Siphon

S104 Combined Siphon

S104 Fc

Surface

Combki

Foul Uf

Dispos

Service Pipe

Surface

Combki

S104 Sl

S104 Gf

S104 Fc

Private

Private

Private

Tandfe

Tandfe

Tandfe

Print500mLine

MATERIALS

- NONE

AC - ASBESTOS CEME

BR - BRICK

CC - CONCRETE BOX CULVERT

CI - CAST IRON

CO - CONCRETE

CSB - CONCRETE SEGMENTS (BOLTED)

CSU - CONCRETE SEGMENTS (UNBOLTED)

DI - DUCTILE IRON

GRP - GLASS REINFORCED PLASTIC

MAC - MASONRY IN REGULAR COURSES

MAR - MASONRY RANDOMLY COURSED

PE - POLYETHYLENE

PF - PITCH

PP - POLYPROPYLENE

PSC - PLASTIC STEEL COMPOSITE

PVC - POLYVINYL CHLORIDE

RPM - REINFORCED PLASTIC MATRIX

SI - SPUN (GREY) IRON

ST - STEEL

U - UNKNOWN

VC - VITRIFIED CLAY

XXX - OTHER

CATEGORIES

W - WEIR

C - CASCADE

DB - DAMBOARD

SE - SIDE ENTRY

FV - FLAP VALVE

BD - BACK DROP

S - SIPHON

D - HIGHWAY DRAIN

S104 - SECTION 104

SHAPE

C - CIRCULAR

E - EGG SHAPED

O - OTHER

R - RECTANGLE

S - SQUARE

T - TRAPEZOIDAL

U - UNKNOWN

PURPOSE

C - COMBINED

E - FINAL EFFLUENT

F - FOUL

L - SLUDGE

S - SURFACE WATER



Severn Trent Water Limited
Asset Data Management
PO Box 5344
Coventry
CV3 9FT
Telephone: 0345 601 6616

SEWER RECORD (Tabular)

O/S Map Scale: 1:5,000

This map is centred upon:

Date of Issue: 09-06-21

X: 436019.23

Y: 294994.16

Disclaimer Statement

1 Do not scale off this Map.

2 This plan and any information supplied with it is furnished as a general guide, is only valid at the date of issue and no warranty as to its correctness is given or implied. In particular this plan and any information shown on it must not be relied upon in the event of any development or works (including but not limited to excavations) in the vicinity of SEVERN TRENT WATER assets or for the purposes of determining the suitability of a point of connection to the sewerage or distribution systems.

3 On 1 October 2011 most private sewers and private lateral drains in Severn Trent Water's sewerage area, which were connected to a public sewer as at 1 July 2011, transferred to the ownership of Severn Trent Water and became public sewers and public lateral drains. A further transfer takes place on 1 October 2012. Private pumping stations, which form part of these sewers or lateral drains, will transfer to ownership of Severn Trent Water on or before 1 October 2016. Severn Trent Water does not possess complete records of these assets. These assets may not be displayed on the map.

4 Reproduction by permission of Ordnance Survey on behalf of HMSO. Crown Copyright and database right 2004. All rights reserved.

5 Ordnance Survey licence number: 100031673

6 Document users other than SEVERN TRENT WATER business users are advised that this document is provided for reference purpose only and is subject to copyright, therefore, no further copies should be made from it.

G. Borehole Ground Information

Appendices

MIRA Technology Park – Plot 8 & 9 part of the LIF 2 Northern Masterplan

Project Number: EED13833-120

Document Reference: EED13833-120-R-1.1.2-FRA



Figure 1 – Site Location Map

Job Number
20188

Project
MIRA, Watling Street, Nuneaton, CV10 0TU

Client
Swan Vale Developments

Date
May 2022



Figure 2 – Trial Hole Location Plan

Job Number

20188

Project


MIRA, Watling Street, Nuneaton, CV10 0TU


Client

Swan Vale Developments

Date

May 2022





		Soils Limited Newton House, Cross Road, Tadworth KT20 5SR Tel: 01737 814221 Email: admin@soilslimited.co.uk			Trial Pit Log		Trial Pit No. TPSK4 Sheet 1 of 1		
Project Name: MIRA, Watling Street, Nuneaton, Leicestershire CV10 0TU				Project No.: 20188		Method:		Hole Type TP	
Location: MIRA, Watling Street, Nuneaton, Leicestershire CV10 0TU				Support:		Scale 1:25		Logged By JC	
Client: HORIBA MIRA Ltd				Trial Pit Length: m		Trial Pit Width: m			
Dates: 24/05/2022			Level:		Co-ords:				
Water Strike	Samples & In Situ Testing			Depth (m)	Level (mAOD)	Legend	Stratum Description		
	Depth	Type	Results						
	0.20	D ES		0.30			Grass over brown, slightly sandy, slightly gravelly SILT. Gravel is well rounded fine to coarse flint. Roots and rootlets. TOPSOIL		
	0.50	D ES						Brown, slightly gravelly CLAY. Gravel is well rounded fine to coarse flint. roots and rootlets	
	1.00	D ES			LAND DRAIN				
	1.50	D ES			Reddish brown and grey mottled, slightly gravelly CLAY. Gravel is well rounded fine to coarse flint. roots and rootlets.				
							End of Pit at 1.500m		
General Remarks:							Sample Type D: Disturbed B: Bulk J: Jar W: Water		
Roots encountered to depth. No groundwater encountered									
Groundwater Remarks:									

		Soils Limited Newton House, Cross Road, Tadworth KT20 5SR Tel: 01737 814221 Email: admin@soilslimited.co.uk			Trial Pit Log		Trial Pit No. TPSK6 Sheet 1 of 1		
Project Name: MIRA, Watling Street, Nuneaton, Leicestershire CV10 0TU				Project No.: 20188		Method:		Hole Type TP	
Location: MIRA, Watling Street, Nuneaton, Leicestershire CV10 0TU				Support:		Scale 1:25		Logged By JC	
Client: HORIBA MIRA Ltd				Trial Pit Length: m		Trial Pit Width: m			
Dates: 25/05/2022			Level:		Co-ords:				
Water Strike	Samples & In Situ Testing			Depth (m)	Level (mAOD)	Legend	Stratum Description		
	Depth	Type	Results						
	0.20	D ES		0.35			Grass over brown, slightly sandy, slightly gravelly SILT. Gravel is well rounded fine to coarse flint. Roots and rootlets. TOPSOIL		
	0.50	D ES					Brown, slightly gravelly CLAY. Gravel is well rounded fine to coarse flint. roots and rootlets		
	1.00	D ES					Reddish brown and grey mottled, slightly gravelly CLAY. Gravel is well rounded fine to coarse flint. roots and rootlets.		
	1.50	D ES		1.50			End of Pit at 1.500m		
General Remarks: Roots encountered to depth. No groundwater encountered								Sample Type D: Disturbed B: Bulk J: Jar W: Water	
Groundwater Remarks:									

Appendix B. Infiltration Soakage Data

Soakaway Calculations

Soakaway Test No.	TPSK1
Site Name.	MIRA, Watling Street, Nuneaton
Job No.	20188

Field Test

Trial Pit Log (include details of groundwater):
See trial Pit

Depth of Pit	1.50 m bgl
Width of Pit	0.60 m
Length of Pit Top	2.40 m
Length of Pit Base	2.00 m
Depth of First Reading	0.31 m bgl

Calculations for Area of Trapezoid Side

Length at top of soak	2.3173
Length at 75% of soak	2.24
Length at 25% of soak	2.08

Area of middle 50% of one trapezoid side 1.2844

Calculations of length of one angled short side

Length of angled short side	1.2316
-----------------------------	--------

Depth of Pit Soaked	1.19 m
ap50	4.748 m2
Vp75-25	0.770644 m3
t75-25	0.0 min
Amount of water used total	1.5413 m3
Flow rate	#DIV/0! m/sec.

Field Data

Depth to Water (m)	Elapsed Time (min)	Head of Water (% of Ho)
0.31	0	100
0.32	3.0	99
0.32	12.0	99
0.33	36.0	98
0.34	54.0	97
0.36	69.0	96
0.37	73.0	95
0.37	117.0	95
0.37	172.0	96
0.37	232.0	96
0.50	1266.0	85
0.51	1341.0	84

Total drain	0.20		
T75	0.000	0.6075	75% effective storage depth
T25	0.000	1.2025	25% effective storage depth
T75-25	0.000	Derived from Best Fit	

Comments


BRE Digest 365:2016

SOILS LIMITED

Newton House, Cross Road, Tadworth
Surrey, KT20 5SR

Telephone: 01737 814 221

Infiltration Rate Plot



Notes: The horizontal dashed black line represents the top of the water i.e. first reading

The light grey dashed represents 75% of the effective storage depth, The dark grey represents 25% of the effective storage depth.
The blue line is the depth to water with time. Where a red line is present it is extrapolated data.

Soakaway Calculations

Soakaway Test No.	TKSK2
Site Name.	MIRA, Watling Street, Nuneaton
Job No.	20188

Field Test

Trial Pit Log (include details of groundwater):
See trial Pit

Depth of Pit	1.50 m bgl
Width of Pit	0.60 m
Length of Pit Top	2.30 m
Length of Pit Base	1.80 m
Depth of First Reading	0.63 m bgl

Calculations for Area of Trapezoid Side

Length at top of soak	2.09
Length at 75% of soak	2.02
Length at 25% of soak	1.87

Area of middle 50% of one trapezoid side 0.8461

Calculations of length of one angled short side

Length of angled short side 0.9171

Depth of Pit Soaked	0.87 m
ap50	3.622 m2
Vp75-25	0.507645 m3
t75-25	0.0 min
Amount of water used total	1.0153 m3
Flow rate	#DIV/0! m/sec.

Field Data

Depth to Water (m)	Elapsed Time (min)	Head of Water (% of Ho)
0.63	0	100
0.64	6.0	99
0.68	12.0	94
0.72	16.0	90
0.75	27.0	86
0.79	36.0	82
0.81	41.0	79
0.82	44.0	78
0.82	67.0	79
0.82	105.0	79
0.82	151.0	79
0.83	208.0	78
0.83	265.0	78
0.85	1301.0	76
0.85	1375.0	76
0.85	1510.0	76

Total drain	0.22	
T75	0.000	0.8475 75% effective storage depth
T25	0.000	1.2825 25% effective storage depth
T75-25	0.000	Derived from Best Fit

Comments


BRE Digest 365:2016

SOILS LIMITED

Newton House, Cross Road, Tadworth
Surrey, KT20 5SR

Telephone: 01737 814 221

Infiltration Rate Plot



Notes: The horizontal dashed black line represents the top of the water i.e. first reading

The light grey dashed represents 75% of the effective storage depth, The dark grey represents 25% of the effective storage depth.
The blue line is the depth to water with time. Where a red line is present it is extrapolated data.

Soakaway Calculations

Soakaway Test No.	TPSK4
Site Name.	MIRA, Watling Street, Nuneaton
Job No.	20188

Field Test

Trial Pit Log (include details of groundwater):
See trial Pit

Depth of Pit	1.50 m bgl
Width of Pit	0.60 m
Length of Pit Top	2.00 m
Length of Pit Base	1.80 m
Depth of First Reading	0.63 m bgl

Calculations for Area of Trapezoid Side

Length at top of soak	1.916
Length at 75% of soak	1.89
Length at 25% of soak	1.83

Area of middle 50% of one trapezoid side 0.8082

Calculations of length of one angled short side

Length of angled short side 0.8777

Depth of Pit Soaked	0.87 m
ap50	3.343 m2
Vp75-25	0.484938 m3
t75-25	0.0 min
Amount of water used total	0.9699 m3
Flow rate	#DIV/0! m/sec.

Field Data

Depth to Water (m)	Elapsed Time (min)	Head of Water (% of Ho)
0.87	0	100
0.88	1.0	98
0.88	4.0	98
0.88	9.0	98
0.88	46.0	98
0.88	90.0	98
0.88	109.0	98
0.88	147.0	98
0.88	196.0	100
0.88	246.0	100
0.88	307.0	100
0.91	1347.0	95
0.91	1422.0	95
0.91	1542.0	95

Total drain	0.04	
T75	0.000	0.8475 75% effective storage depth
T25	0.000	1.2825 25% effective storage depth
T75-25	0.000	Derived from Best Fit

Comments


BRE Digest 365:2016

SOILS LIMITED

Newton House, Cross Road, Tadworth
Surrey, KT20 5SR

Telephone: 01737 814 221

Infiltration Rate Plot



Notes: The horizontal dashed black line represents the top of the water i.e. first reading

The light grey dashed represents 75% of the effective storage depth, The dark grey represents 25% of the effective storage depth. The blue line is the depth to water with time. Where a red line is present it is extrapolated data.

Soakaway Calculations

Soakaway Test No.	TPSK6
Site Name.	MIRA, Watling Street, Nuneaton
Job No.	20188

Field Test

Trial Pit Log (include details of groundwater):
See trial Pit

Depth of Pit	1.50 m bgl
Width of Pit	0.60 m
Length of Pit Top	2.60 m
Length of Pit Base	1.80 m
Depth of First Reading	0.63 m bgl

Calculations for Area of Trapezoid Side

Length at top of soak	2.264
Length at 75% of soak	2.15
Length at 25% of soak	1.92

Area of middle 50% of one trapezoid side 0.8839

Calculations of length of one angled short side

Length of angled short side	0.986
-----------------------------	-------

Depth of Pit Soaked	0.87 m
ap50	3.919 m2
Vp75-25	0.530352 m3
t75-25	0.0 min
Amount of water used total	1.0607 m3
Flow rate	#DIV/0! m/sec.

Field Data

Depth to Water (m)	Elapsed Time (min)	Head of Water (% of Ho)
0.63	0	100
0.63	14.0	100
0.63	29.0	100
0.63	60.0	100
0.64	102.0	99
0.64	130.0	99
0.64	163.0	99
0.64	221.0	99
0.64	461.0	99

Total drain	0.01	
T75	0.000	0.8475 75% effective storage depth
T25	0.000	1.2825 25% effective storage depth
T75-25	0.000	Derived from Best Fit

Comments


BRE Digest 365:2016

SOILS LIMITED

Newton House, Cross Road, Tadworth
Surrey, KT20 5SR

Telephone: 01737 814 221


Infiltration Rate Plot



Notes: The horizontal dashed black line represents the top of the water i.e. first reading

The light grey dashed represents 75% of the effective storage depth, The dark grey represents 25% of the effective storage depth. The blue line is the depth to water with time. Where a red line is present it is extrapolated data.

	Contract Name: MIRA, Watling Street, Nuneaton, Leicestershire				Client: HORIBA MIRA Ltd				Hole ID: WS1					
	Contract Number: 20188		Start and End Date: 25/05/22		Logged By: CF		Checked By: LW		Status: PRELIM		Hole Type: WS			
	Easting:		Northing:		Ground Level:		Plant Used: Premier 3		Print Date: 01/06/2022		Scale: 1:50			
Weather: Cloudy				Termination: No penetration, reached maximum safe blow count								Sheet 1 of 1		
Samples & In Situ Testing					Strata Details							Groundwater		
Depth	Type	Results	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description						Water Strike	Backfill/Installation	
0.20	D			(0.30)		Firm brown slightly gravelly sandy desiccated CLAY. Gravel is sub-rounded fine to coarse igneous. Frequent rootlets. TOPSOIL. Stiff becoming very stiff orangish brown, reddish brown and brown mottled slightly sandy silty CLAY. Sand is predominantly fine. Occasional black speckling. Occasional rootlets. Very stiff light grey mottled reddish brown slightly gravelly very sandy CLAY. Sand is predominantly fine. Gravel is angular fine siltstone. Frequent thin interlaminated fine light grey sand and silty clay. Rare band of siltstone/mudstone. Rare rootlets. <i>Band of light grey very weak siltstone.</i> Very stiff reddish brown mottled red, slightly gravelly slightly sandy CLAY. Gravel is angular fine to coarse very weak to weak mudstone and fine very weak siltstone. Occasional lens and thin to thick laminations of light grey fine sand. <i>Band of orangish brown strong siltstone/mudstone.</i>						1		
0.40	D		0.30											
0.60	D		0.55											
0.90	D		0.75											
1.40	D		(1.55)											
1.90	D					Very stiff reddish brown mottled red slightly sandy gravelly CLAY. Gravel is angular to sub-angular fine to coarse very weak mudstone. <i>Band of orangish brown and red mudstone.</i>						2		
2.40	D			2.30										
					2.50	End of Borehole at 2.50m						3		
												4		
												5		
												6		
												7		
												8		
												9		
												10		
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:					
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)	Rootlets observed to 0.70m bgl.					
Chiselling					Installation				Water Strikes					
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)	Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks
												0	0.00	No groundwater encountered.
Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.														



Weather: Cloudy	Termination: No penetration, reached maximum safe blow count	Sheet 1 of 1
-----------------	--	--------------

Samples & In Situ Testing			Strata Details						Groundwater			
Depth	Type	Results	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description			Water Strike	Backfill/ Installation		
0.20	D			(0.35)		Firm becoming stiff brown slightly gravelly sandy desiccated CLAY. Gravel is sub-rounded to well-rounded fine to coarse flint and igneous. Frequent rootlets. TOPSOIL.			1			
0.50	D			0.35		Very stiff reddish brown mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular fine to medium extremely weak to very weak mudstone. Occasional rootlets becoming rare. Rare light grey fine sand inclusions.						
1.00	D			(1.53)		Light grey mottled red extremely weak to weak SILTSTONE. Occasional interbedded silty clay and gravelly sand. Gravel is angular fine to medium extremely weak siltstone. Very stiff reddish brown mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular fine to coarse extremely weak to very weak mudstone. Occasional rootlets becoming rare. Rare light grey motting and fine sand inclusions.						
1.50	D											
1.90	D			1.88								
2.10	D				1.96		Band of light grey motting. Fine gravel-sized fine sand inclusions.				2	
2.60	D			(1.54)		Band of light grey very weak siltstone.						3
3.10	D											
3.50	D			3.50		End of Borehole at 3.50m					4	
							5					
								6				
							7					
								8				
							9					
								10				

Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Water Strikes <table><tr><th>Strike (m)</th><th>Casing (m)</th><th>Sealed (m)</th><th>Time (mins)</th><th>Rose to (m)</th><th>Remarks</th></tr><tr><td></td><td></td><td></td><td>0</td><td>0.00</td><td>No groundwater encountered.</td></tr></table> Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.	Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks				0	0.00	No groundwater encountered.
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks																
			0	0.00	No groundwater encountered.																
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)													
Chiselling					Installation																
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)													

	Contract Name: MIRA, Watling Street, Nuneaton, Leicestershire				Client: HORIBA MIRA Ltd				Hole ID: WS3					
	Contract Number: 20188		Start and End Date: 24/05/22		Logged By: CF		Checked By: LW		Status: PRELIM		Hole Type: WS			
	Easting:		Northing:		Ground Level:		Plant Used: Premier 3		Print Date: 01/06/2022		Scale: 1:50			
Weather: Cloudy				Termination: No penetration, reached maximum safe blow count								Sheet 1 of 1		
Samples & In Situ Testing					Strata Details							Groundwater		
Depth	Type	Results	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description						Water Strike	Backfill/Installation	
0.10	D			0.15		Firm becoming stiff brown slightly gravelly sandy desiccated CLAY. Gravel is sub-rounded to well-rounded fine to coarse flint and igneous. Frequent rootlets. Rare coarse sand-sized red brick (<5%). TOPSOIL. Very stiff orangish brown mottled red, slightly gravelly sandy CLAY. Gravel is sub-angular to well-rounded fine to medium extremely weak mudstone and flint. Occasional rootlets. Rare black speckling. Very stiff reddish brown mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular fine to medium extremely weak mudstone. Occasional rootlets. Rare light grey fine sand inclusions. Stiff dark brown mottled reddish brown slightly sandy silty CLAY. Sand is predominantly fine. Occasional black speckling. Occasional rootlets. Very stiff reddish brown mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular fine to coarse extremely weak to very weak mudstone. Occasional very weak to weak siltstone band. Rare black speckling in upper boundary. Rare light grey mottling and fine sand inclusions. Rare rootlets. Rare desiccated rootlets with black mottling. Occasional dark reddish brown mottling. Band of light grey mottling. Fine gravel-sized fine sand inclusions. Band of orangish brown and red mudstone.						1		
0.30	D		(0.35)											
0.60	D		0.50											
0.80	D		0.75											
1.00	D		0.90											
1.50	D													
2.00	D			(2.10)								2		
2.30	D													
2.50	D													
3.00	D			3.00		End of Borehole at 3.00m						3		
												4		
												5		
												6		
												7		
												8		
												9		
												10		
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:					
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)	Rootlets observed to 1.30m bgl. Desiccated rootlet noted at 2.55m bgl.					
Chiselling					Installation				Water Strikes					
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)	Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks
												0	0.00	No groundwater encountered.
									Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.					




Contract Name: MIRA, Watling Street, Nuneaton, Leicestershire			Client: HORIBA MIRA Ltd			Hole ID: WS4
Contract Number: 20188	Start and End Date: 24/05/22	Logged By: CF	Checked By: LW	Status: PRELIM	Hole Type: WS	
Easting:	Northing:	Ground Level:	Plant Used: Premier 3	Print Date: 01/06/2022	Scale: 1:50	

Weather: Cloudy	Termination: No penetration, reached maximum safe blow count	Sheet 1 of 1
-----------------	--	--------------


Samples & In Situ Testing			Strata Details				Groundwater	
Depth	Type	Results	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill/Installation
0.20	D			0.20 (0.40)		Dark brown clayey very gravelly SAND. Gravel is angular fine to medium igneous, flint, fine red brick, sandstone and clinker. Frequent rootlets. MADE GROUND.		
0.30	ES/D					Brown clayey very gravelly SAND. Gravel is angular to well-rounded fine to coarse flint, concrete, red brick, clinker and igneous. Occasional flint and concrete cobbles. Occasional glass and plastic fragments. Occasional rootlets. MADE GROUND.		
0.40	D			0.50		Stiff becoming very stiff brown mottled reddish brown, slightly sandy slightly gravelly CLAY. Gravel is angular to well-rounded fine to coarse flint, concrete, red brick, clinker and igneous. Occasional plastic fragments. Occasional rootlets. MADE GROUND.		
0.60	ES/D			(0.35)				
0.70	D			0.85		Very stiff reddish brown mottled red, slightly sandy slightly gravelly CLAY. Gravel is angular fine to medium extremely weak mudstone. Occasional rootlets becoming rare. Rare light grey fine sand inclusions.	1	
1.00	D							
1.50	D			(1.65)		Light grey mottled red very weak to medium strong SILTSTONE. Occasional interbedded silty clay and gravelly sand. Gravel is angular fine to medium very weak siltstone.	2	
2.00	D							
2.40	D			2.50		Very stiff reddish brown mottled red, slightly sandy slightly gravelly becoming gravelly CLAY. Gravel is angular fine to coarse extremely weak to very weak mudstone and weak siltstone. Rare light grey mottling and fine sand inclusions.	3	
2.55	D			2.60				
2.80	D			(0.40)				
				3.00		End of Borehole at 2.90m		
							4	
							5	
							6	
							7	
							8	
							9	
							10	

Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:							
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)								
									Rootlets observed to 1.15m bgl.							
Chiselling					Installation				Water Strikes							
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)	Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks		
												0	0.00	No groundwater encountered.		
Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.																



Weather: Cloudy	Termination: No penetration, reached maximum safe blow count	Sheet 1 of 1
-----------------	--	--------------

Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)	
Chiselling					Installation				Water Strikes
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)	Strike (m)
									Casing (m)
									Sealed (m)
									Time (mins)
									Rose to (m)
									Remarks
									No groundwater encountered.
									Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.




Weather: Cloudy	Termination: Reached required depth (4.0m)	Sheet 1 of 1
-----------------	--	--------------

[illegible]

Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth (m)	Dia (mm)	
Chiselling					Installation				Water Strikes
From (m)	To (m)	Duration	Remarks		Top (m)	Base (m)	Type	Dia (mm)	Strike (m) 3.20 Casing (m) Sealed (m) Time (mins) 20 Rose to (m) 3.20 Remarks Groundwater struck at 3.20m bgl.
									Hand vane (HV), Hand penetrometer (HP) reported in kPa. PID reported in ppm.

UK and Ireland Office Locations



Remediation and Discovery Strategy



MIRA Technology Park – LIF 2 Infrastructure, Land North of A5

Remediation and Discovery Strategy

September 2022

Waterman Infrastructure & Environment Limited

Pickfords Wharf, Clink Street, London, SE1 9DG
www.watermangroup.com



Client Name: Swanvale Developments Limited
Document Reference: WIE13833-117-RS-4.1.1-RJM
Project Number: WIE13833

Quality Assurance – Approval Status

This document has been prepared and checked in accordance with Waterman Group's IMS (BS EN ISO 9001: 2015, BS EN ISO 14001: 2015 and BS EN ISO 45001:2018)

Issue	Date	Prepared by	Checked by	Approved by
First	September 2022	Robbie J Moore Senior Contaminated Land Consultant	Carl Slater Technical Director	Carl Slater Technical Director

A handwritten signature in black ink, appearing to read 'Carl Slater', with a long horizontal flourish extending to the right.

Comments

Disclaimer

This report has been prepared by Waterman Infrastructure & Environment Limited, with all reasonable skill, care and diligence within the terms of the Contract with the client, incorporation of our General Terms and Condition of Business and taking account of the resources devoted to us by agreement with the client.

We disclaim any responsibility to the client and others in respect of any matters outside the scope of the above.

This report is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the report at its own risk.

Contents

Executive Summary

1. Introduction	1
1.1 Objectives	1
1.2 Proposed Development	1
1.3 Planning Context	1
1.4 Regulatory Context.....	1
1.5 Constraints	3
2. Ground Conditions	4
2.1 Site History	4
2.2 Geology and Hydrogeology	4
2.3 Observations During Ground Investigation.....	4
2.4 Variations of Proposed Ground Investigation Methodology	5
3. Remediation Strategy	6
3.1 Protection of Workers and the General Public.....	6
3.1.1 Construction Workers.....	6
3.1.2 Surrounding Site Receptors.....	6
3.2 Buried Services	6
3.3 Material Management.....	6
3.3.1 Materials Management Plan	6
3.3.2 Management Measures	7
3.3.3 Validation of Ground Conditions	7
3.3.4 Asbestos Management Plan	7
3.3.5 Imported Materials.....	7
3.3.6 Surplus Material	8
3.3.7 Topsoil for Soft Landscaping	8
3.3.8 Protection of Groundwater during the Works.....	8
3.4 Laboratory Testing and Accreditation.....	8
3.5 Discovery Strategy for Unforeseen Contamination	9
3.6 Statutory Approvals	9
4. Validation Report.....	10

Appendices

Appendix A	Site Plans
Appendix B	Validation Criteria
Appendix C	Factual Ground Investigation Report

Executive Summary

Objectives

Remediation Strategy for ground contamination risks at MIRA Technology Park LIF 2 Infrastructure Site, Land North of the A5, Nuneaton. This report is to support a future planning application for redevelopment of the site for commercial use.

Mitigation Measures

Boundary Treatment	Sealing of buried services at the Site boundary.
Treatment of Soils	Assessment of excavated soils for re-use, and treatment if necessary to ensure they meet criteria for the proposed end use
Materials Management	Materials Management Plan for the earthworks. Stockpile management, dust prevention, leachate management and waste classification for materials to be removed.
Decommissioning of Surface Drainage	Decommissioning of any redundant drainage encountered during demolition and Site stripping works.
Unforeseen Contamination	Addendum Remediation Method Statement to be prepared if unforeseen contamination is encountered during the works.
Imported Materials	All materials to be from a known source and appropriate for their intended use, with sampling, testing, and certification to be provided.
Soft Landscaping	Imported soils for soft landscaping areas to be from a known source and appropriate for their intended use, with sampling, testing, and certification to be provided.
Buried Services	Installation of new services in clean service corridors. Water supply pipes to be suitable for use on brownfield sites.
Protection of Groundwater	Adequate measures will be put in place to protect the aquifers underlying the Site. Fuel storage will be adequately bunded and drip trays and spill kits will be provided, with Site workers familiar with their use.
Laboratory Testing	Chemical analysis of soils and groundwater to be undertaken by UKAS and MCERTS accredited laboratories.
Discovery Strategy	Watching brief to be maintained at all points of excavation throughout the development works. Contractor to prepare addendum remedial method statement for any unanticipated contamination encountered, with this included within the Validation Report.
Statutory Approvals	Hinkley and Bosworth Borough Council, Leicestershire County Council, the Environment Agency, and the local water company to be consulted and approvals obtained for the works.
Validation	Validation Report to be prepared and submitted to the statutory authorities for approval.

1. Introduction

1.1 Objectives

Waterman Infrastructure & Environment Limited (“Waterman”) was instructed by Waterman Structures Limited on behalf of Swanvale Developments Limited to undertake a Preliminary Risk Assessment (PERA) for ground contamination at the MIRA Technology Park LIF 2 Infrastructure Site, Land North of the A5, Nuneaton (hereafter termed “the Site”).

This assessment follows on from the Ground Conditions and Contamination, Flood Risk Assessment and Outline Drainage Strategy desk study report prepared by Waterman in April 2022 (*report reference EED13833-117-R-2.4.2-FRA*) and ground investigation factual report prepared for the Site by Soils Ltd in May 2022 (*report reference 20188/FDLR*).

The Remediation Strategy covers the approach to management of contamination risk on the Site and sets out outline mitigation measures to reduce any identified risk to an acceptable level. A Discovery Strategy for actions to be undertaken should any potential contamination be identified during redevelopment works is also set out in this document.

1.2 Proposed Development

The Site (Red Line boundary) covers an area of approximately 15.6 hectares (ha) and currently forms part of the MIRA Technology Park including currently undeveloped land to the north-west of the park, farmland and farm buildings in the east.

The proposed development has not been finalised but will involve demolition of all existing structures and construction of new commercial buildings, with car parking, soft landscaping, and attenuation ponds. An outline development layout is included in Appendix A.

1.3 Planning Context

The purpose of this report is to support a future masterplan planning application for development of the Site as an expansion to the adjacent MIRA complex.

1.4 Regulatory Context

National Planning Policy Framework 2021

The National Planning Policy Framework (NPPF) 2021 sets out Government planning policy for England and how this is expected to be applied to development. Paragraph 120 of Section 11 – Making effective use of land and paragraphs 174, 183, 184 and 188 of Section 15 – Conserving and enhancing the natural environment of the NPPF relate to contaminated land matters and state the following:

120. Planning policies and decisions should:

c) give substantial weight to the value of using suitable brownfield land within settlements for homes and other identified needs, and support appropriate opportunities to remediate despoiled, degraded, derelict, contaminated or unstable land;

174. Planning policies and decisions should contribute to and enhance the natural and local environment by:

e) preventing new and existing development from contributing to, being put at unacceptable risk from, or being adversely affected by, unacceptable levels of soil, air, water or noise pollution or land instability. Development should, wherever possible, help to improve local environmental conditions such as air and water quality, taking into account relevant information such as river basin management plans; and

f) remediating and mitigating despoiled, degraded, derelict, contaminated and unstable land, where appropriate.

183. Planning policies and decisions should ensure that:

a) a site is suitable for its proposed use taking account of ground conditions and any risks arising from land instability and contamination. This includes risks arising from natural hazards or former activities such as mining, and any proposals for mitigation including land remediation (as well as potential impacts on the natural environment arising from that remediation);

b) after remediation, as a minimum, land should not be capable of being determined as contaminated land under Part IIA of the Environmental Protection Act 1990; and

c) adequate site investigation information, prepared by a competent person, is available to inform these assessments.

184. Where a site is affected by contamination or land stability issues, responsibility for securing a safe development rests with the developer and/or landowner.

188. The focus of planning policies and decisions should be on whether proposed development is an acceptable use of land, rather than the control of processes or emissions (where these are subject to separate pollution control regimes). Planning decisions should assume that these regimes will operate effectively. Equally, where a planning decision has been made on a particular development, the planning issues should not be revisited through the permitting regimes operated by pollution control authorities.

[Environmental Protection Act 1990 and Contaminated Land Statutory Guidance 2012](#)

In order to assess the contamination status of the Site, with respect to the proposed end use, it is necessary to assess whether the Site could potentially be classified as “Contaminated Land”, as defined in Part IIA of the Environmental Protection Act 1990 and Contaminated Land Statutory Guidance 2012. This is assessed by the identification and assessment of potential contaminant linkages. The linkage between the potential sources and potential receptors identified needs to be established and evaluated.

To fall within this definition, it is necessary that, as a result of the condition of the land, substances may be present in, on or under the land such that:

- a) significant harm is being caused or there is a significant possibility of such harm being caused; or
- b) significant pollution of controlled waters is being caused, or there is significant possibility of such pollution being caused.

It should be noted that DEFRA has advised (Ref. Section 4, DEFRA Contaminated Land Statutory Guidance 2012) Local Authorities that land should not be designated as “Contaminated Land” where:

- a) the relevant substance(s) are already present in controlled waters;
- b) entry into controlled waters of the substance(s) from land has ceased; and
- c) it is not likely that that further entry will take place.

These exclusions do not necessarily preclude regulatory action under the Environmental Permitting (England and Wales) Regulations 2016, which make it a criminal offence to cause or knowingly permit a water discharge of any poisonous, noxious or polluting matter to controlled waters. In England and Wales, under The Water Resources Act 1991 (Amendment) (England and Wales) Regulations 2009, a works notice may be served by the regulator requiring appropriate investigation and clean-up.

1.5 Constraints

The assessment was undertaken in accordance with the scope agreed between Waterman and Waterman Structures Ltd, as documented in Waterman's fee letter (*reference STR17364-211206-SC-Fee Proposal, dated 22 December 2021*), and with Waterman's standard Terms of Appointment.

The benefit of this report is made to Swanvale Developments Ltd.

The information contained in this report is based on the findings of the previous environmental risk assessment, observations made on-Site, exploratory hole records and laboratory test results undertaken by Soils Ltd.

Constraints to the investigation include:

- The ground conditions reported relate only to the point of excavation and do not necessarily guarantee a continuation of the ground conditions throughout the non-inspected area of the Site. Whilst such exploratory holes would usually provide a reasonable indication as to the general ground conditions, these cannot be determined with complete certainty;
- The Soils Ltd ground investigation report provided did not include sampling or testing of soils or groundwater at the Site;
- Waterman has endeavoured to assess all information provided to them during this investigation but makes no guarantees or warranties as to the accuracy or completeness of this information;
- The scope of this investigation includes an assessment of the presence of asbestos containing materials in the ground at the Site but not within buildings or structures or below ground structures (basements, buried service ducts and the like); and
- The conclusions resulting from this study are not necessarily indicative of future conditions or operating practices at or adjacent to the Site.

2. Ground Conditions

2.1 Site History

Earliest available mapping information in 1887-1902 identifies the historical land use at the Site as farmland, with a railway line intersecting the north-eastern corner. From 1934 the area became occupied by the RAF and developed as Lindlay Airfield. In 1905 a shooting range was present on part of the Site, and by 1961 the airfield was disused and the area in use by MIRA as a vehicle testing facility.

Recorded land uses within 500m of the Site include factories and works including an oil factory, cement works, print works, garages, power station and various wharfs.

2.2 Geology and Hydrogeology

Geology on-Site has been established from British Geological Survey (BGS) mapping, nearby BGS borehole logs and findings of the Soils Ltd ground investigation at the Site. Geology and hydrogeology are summarised in Table 1.

Table 1: Site Geology

Stratum	Area Covered	Estimated Thickness	Hydrogeological Classification
Topsoil, or gravel surfacing in farm buildings area	Entire Site	0.3-1.3m	Not classified
Boulder Clay (Lacustrine and Glaciofluvial deposits)	Western area of the Site only	0.3-0.4m	Secondary A Aquifer
Mercia Mudstone	Entire Site	Base not proven at 6.1m bgl	Secondary B Aquifer

A single groundwater strike was encountered at one window sample location during the Soils Ltd. works at 3.2m bgl. This level did not change after 20 minutes observation. Groundwater was not encountered at the remaining five window sample holes.

Surface Waters

Drainage ditches surround the Site and run north to south adjacent to the hedgerows separating the eastern and western fields. This ditch outflows to the nearby River Anker off-site to the west, and at the time of the walkover was observed to be dry. Two ponds are in the centre-east of the Site. The northern of these was found to be dry at the time of the walkover, with water present in the southern feature.

The nearest recorded surface waters to the Site are a series of rivers and surface ponds at Caldecote Brook located 480m north. The River Anker is 575m west.

The drainage ditches, ponds and Caldecote Brook have not been classified for Ecological Potential by the EA under the Water Framework Directive. The River Anker has been assessed with a 'good' ecological and chemical rating.

No surface water abstractions are recorded within 1km of the Site. A single discharge consent is detailed, 56m north-east authorising trade discharge to Caldecote Brook.

2.3 Observations During Ground Investigation

Ground investigation works comprised six window sample holes to depths between 2.5m bgl and 4.0m bgl, and four trial pits to 1.5m bgl.

Soil and Groundwater Chemical Quality

Chemical soil and groundwater sampling was not undertaken as part of the investigation works. During excavation of the exploratory holes, no visual or olfactory evidence for contamination was observed in the holes or arisings.

Asbestos

Visible fragments of asbestos or asbestos containing materials (ACMs) were not identified at the Site.

Ground Gas and Vapours

Considering the identified geology beneath the Site and proposed development design, the Site is considered very low risk for ground gas issues.

Soil and groundwater observations during excavation works do not indicate any potential vapour risk at the Site. The potential for vapour risk to new development structures is low.

2.4 Variations of Proposed Ground Investigation Methodology

The Environmental Assessment prepared by Waterman as part of the wider Ground Conditions and Contamination, Flood Risk Assessment and Outline Drainage Strategy included recommendations for further work to determine the risk posed by potential land contamination. Recommendations relating to ground conditions are reproduced below:

- Although the risk of encountering contamination on the Site is low, confirmatory environmental chemistry testing will be undertaken during the geotechnical investigation to be done to inform future building design. The chemical test suite will include asbestos, metals, speciated total petroleum hydrocarbons (TPH) and polyaromatic hydrocarbons (PAHs);
- Construction workers should be provided with, and use appropriate PPE while undertaking works at the Site;
- Works at the Site should be completed in-line with the Control of Asbestos Regulations (2012);
- Construction workers should be asbestos awareness trained; and
- Construction materials and stockpiled soils during the works should be appropriately stored to prevent dust emissions to nearby roads, farms and the wider MIRA complex;

Soils Ltd. undertook the ground investigation works across the Site, which comprised six window sample holes and four trial pits. However, soil and groundwater sampling was not undertaken as part of this investigation, with a visual inspection of arisings completed instead. This inspection did not identify any contamination in soils or groundwater encountered.

As set out in the previous reports, the risk of ground contamination is low. Potential contamination sources identified for the Site were primarily related to use of the nearby land as an airfield, with risk of hydrocarbon contamination to soils and groundwater. Therefore, gross contamination resulting from this land use would be readily identifiable by visual inspection in lieu of soils and groundwater chemical testing. Furthermore, the proposed land use as commercial buildings will reduce the potential for future Site users to contact soils at the Site, limiting the pathways for any contamination to these receptors.

To fully reduce the risk to the Site, a watching brief for evidence of ground contamination will be undertaken as part of the validation measures. A discovery strategy for dealing with any contamination encountered during the watching brief is set out in Section 3.5.

3. Remediation Strategy

This strategy is designed to ensure the contaminant linkages identified in the ground conditions section of the desk study are adequately mitigated both during, and on completion of the development.

The Contractor appointed to complete the Development will undertake the mitigation works. All remediation works will be documented in a Validation Report. This report will provide details of the mitigation measures implemented and any remediation work undertaken. Full details to be included within the Validation Report are outlined in Section 4.

3.1 Protection of Workers and the General Public

3.1.1 Construction Workers

The health and safety of all construction workers and visitors on-Site will be managed during the development works through provision of appropriate welfare facilities, decontamination facilities, appropriate storage of fuels, chemicals, and construction materials.

The Waterman PRA and Soils Ltd ground investigation report detailing the Site history, ground conditions and the potential for contaminated soils and groundwater will be provided to the Contractor.

Personal protective equipment (PPE) suitable for the activities being undertaken will be provided where necessary. The Contractor will complete a method statement for all demolition and construction activities, which will be appended to this report once available. All works will be progressed in line with the approved method statements.

3.1.2 Surrounding Site Receptors

Mitigation measures will be employed to minimise airborne dust emissions or surface run-off from stockpiled materials. The appointed Contractor will determine the methods for appropriate handling and storage of materials, which may include use of hoardings, damping down and covering of stockpiles where necessary. Where material is sent off-Site via highways, wheel washing facilities and road sweeping may be employed to prevent material being tracked into the road. These measures will ensure the public are protected throughout the duration of the works.

On-Site fuel storage will be adequately bunded, with drip trays and spill kits provided as necessary. Site workers will be familiar with the use of spill kits, and any leaks or spills will be recorded and reported to Site management regardless of volume.

3.2 Buried Services

All new underground services will be situated in clean service corridors. Drinking water supply pipes used will be resistant to chemical attack, in consultation with the local water authority. Redundant services encountered during the ground works shall be appropriately decommissioned and capped at the Site boundary.

3.3 Material Management

3.3.1 Materials Management Plan

Where it is proposed to re-use material on-Site, the Contractor will be responsible for determining the most appropriate framework through which the soils are re-used. This is likely to be through the CL:AIRE 'Definition of Waste' Code of Practice (DoWCoP), or alternatively through a waste exemption permit sought from the Environment Agency.

Should approval be sought via DoWCoP, the Contractor will prepare a Materials Management Plan (MMP) which will collate all the relevant information to demonstrate the soils are not waste (quantities, quality, and certainty of use) and will include details of the tracking system, contingency, and verification requirements. The MMP will also state what works are due to be undertaken, how they have been assessed and who will be carrying them out. The MMP will be signed off by a Qualified Person (QP) who is not part of the design team.

Any material re-used on-Site will be confirmed free of visual and olfactory evidence of contamination, including (but not limited to) the visual presence of asbestos containing materials, bituminous materials containing coal-tar, and hydrocarbon staining and odours.

The total volume of material re-used on-Site, types of material and location of emplacement will be documented in the Validation Report.

3.3.2 Management Measures

Stockpiling of soil arisings will be managed in a controlled manner, with different material types segregated and clearly labelled. Each stockpile will be identified according to assumed or confirmed categorisation, source, type and deposition date, and details of any chemical analyses.

Stockpiles will be physically separated to avoid cross contamination and temporary road access provided for placement and loading. Stockpiles of contaminated material will be positioned on impervious surfaces to prevent any potential leachate to ground.

3.3.3 Validation of Ground Conditions

Sampling of soils and groundwater was not undertaken during ground investigation at the Site, however no evidence for contamination was identified during visual inspection of arisings. As identified in the desk study for the Site, potential contamination is limited to hydrocarbons from use of nearby land as an airfield.

An environmental engineer will regularly attend Site during ground works to examine arisings and confirm any visual evidence for contamination identified. The engineer will keep a photographic record of the works as excavation progresses, which will be included in the Validation Report.

Visual inspection of pile arisings and exposed soils at formation level within the new building and attenuation ponds footprints will be undertaken to confirm unanticipated gross hydrocarbon contamination is not evident. If encountered, the process for removal and validation of unanticipated contamination is set out in Section 3.5.

3.3.4 Asbestos Management Plan

Ground works by Soils Ltd. did not identify any visual evidence for asbestos contamination. Should potential asbestos be encountered during the redevelopment, works in the affected area will cease and the Contractor shall make the environmental engineer aware.

3.3.5 Imported Materials

Where secondary aggregates are brought to or generated on-Site these will be completed in accordance with the Waste and Resources Action Group (WRAP) Quality Protocol for the production of aggregates from inert waste and confirmed free of visual and olfactory evidence of contamination, including (but not limited to) the visual presence of asbestos containing materials and bituminous materials containing coal-tar, and hydrocarbon staining and odours. Alternatively, a waste exemption or environmental permit will be obtained from the Environment Agency for the re-use of Site-won soils and/or aggregates.

Imported materials will be sampled on Site to confirm their suitability, at the rates detailed in Section 3.3.7. Chemical criteria for imported material are set out in Appendix B.

Records will be collected detailing the total volume of imported soils for inclusion in the Validation Report.

3.3.6 Surplus Material

The waste hierarchy will be followed for surplus materials, as follows:

- Re-use of suitable materials on-Site where possible;
- Processing or treatment of unsuitable materials to allow re-use on-Site;
- Re-use off-Site;
- Processing or treatment to allow re-use off-Site;
- Transport to an off-Site waste recovery facility; or
- Disposal to landfill.

Most excavated materials will need to be disposed of off-site. Surplus soils will be subjected to analysis to confirm the correct waste classification of the material and identify a suitable licensed disposal facility. Copies of all relevant licences for the disposal / treatment facility will be provided prior to the waste being taken off-Site.

Quantities of materials disposed off-Site, and the receiving facilities will be recorded during the works. All consignment notes for the materials transferred will be collated and a selection provided in the Validation Report.

3.3.7 Topsoil for Soft Landscaping

The new development buildings will be surrounded by grass landscaping and trees. It is assumed that existing topsoil across the Site will be re-used for this purpose, however, should additional topsoil/subsoil be imported it will be certified as clean, uncontaminated, and suitable for use, and will be from a known source.

A minimum of three samples of soil per source will be submitted for analysis to confirm its suitability. Samples will be taken in-situ following soil placement and submitted for the chemical analysis listed in Appendix B2 and will comply with the limits in the table. If the volume of soil from any source exceeds 1500m³, samples at a rate of one sample per 500m³ over and above 1500m³ should be submitted to confirm suitability.

3.3.8 Protection of Groundwater during the Works

The Boulder Clay and Mercia Mudstone are classified as Secondary (A) Aquifer and Secondary (B) Aquifers respectively. Whilst it is not anticipated that development works will expose this groundwater, measures will be required to protect these water bodies underlying the Site.

Any fuel storage on-Site will be adequately bunded, with drip trays and spill kits provided. Site workers will be familiar with their use. Any leaks or spills will be reported to Site management, regardless of volume.

Access to the fuel storage will be locked and restricted. Fuel dispenser pumps with “hold open latches” will not be permitted on Site.

3.4 Laboratory Testing and Accreditation

Any further chemical analysis required at the Site will be undertaken by UKAS and MCERTS accredited laboratories.

3.5 Discovery Strategy for Unforeseen Contamination

The Contractor shall maintain a watching brief at all points of excavation throughout the development works. Should unforeseen contaminated materials or liquids be encountered, work in the area will be stopped to assess the extent and nature of the contamination. The Contractor will prepare an addendum remedial method statement for dealing with the encountered contamination, likely to involve excavation and removal of all visually impacted material from the Site. Depending on the nature of the contamination identified, verification samples may also be collected from the base and sides of the excavations with appropriate chemical testing to demonstrate the material has been effectively remediated.

The addendum remedial method statement and chemical analysis of validation samples will be included within the Validation Report.

3.6 Statutory Approvals

All necessary approvals from the statutory authorities, including Hinkley and Bosworth Borough Council, Leicestershire County Council, the Environment Agency and local water company will be obtained for the works undertaken.

A watching brief will be undertaken throughout the works, with documentary evidence collected demonstrating compliance with this Remediation Strategy.

A Validation Report will be prepared upon completion of the below-ground development works and submitted for statutory approval. The scope of this Validation Report is set out in Section 4.

The works will be carried out and comply with all current applicable standards, codes, regulations, planning conditions, guidance notes, legislation and health and safety conditions.

4. Validation Report

A Validation Report will be prepared detailing all contaminated land works undertaken as part of the development. The Validation Report will include the following information:

- For materials imported, re-used or exported from the Site;
 - Material source location, type and volumes;
 - Details of any processes undertaken on the material, such as remediation processes or generation of secondary aggregates;
 - Records to demonstrate the material has been procured or produced in accordance with appropriate protocols;
 - Location and details of validation samples collected;
 - Laboratory chemical test results for validation samples collected;
 - Details for any locations in which re-used or imported materials have been emplaced, including final thicknesses and total area covered; and
 - Locations where material has been exported, including volumes sent and relevant documentation. Exported material data should be separated based on the waste classification of the materials;
 - Summary of consignment notes and chain of custody documents relating to the disposal of soils, groundwater and asbestos containing materials from the Site;
- Details of any unanticipated contamination encountered during the works in accordance with the discovery strategy;
- Photographic record and visual inspection record of the formation level for the new building slab;
- As-built drawings showing final levels, excavated/infilled areas, and other relevant details; and
- Relevant approvals from Leicestershire Council, the Environment Agency and the local water authority for the works carried out.

APPENDICES

A. Site Plans

- **Site Location Plan**
- **Site Plan**
- **Proposed Outline Development Plans**

