

	PROPOSED TREES <i>Extra Heavy/Heavy Standard</i> See Schedule
	ORNAMENTAL HEDGE See Schedule
	NATIVE HEDGE See Schedule
	PROPOSED PLANTING <i>Shrubs/Herbaceous/Grasses</i> See Schedule
	TURF <i>with area (m²)</i>
	AMENITY GRASS AREA <i>Wear Tolerant Turfgrasses Mixture</i> <i>Emorgate EG22 sown at 25kg/ha</i> <i>Kepi mown short to 40mm</i>
	WILDFLOWER MEADOW <i>Special General Purpose Meadow</i> <i>Emorgate EMS sown at 4 g/m²</i> <i>(seeding prescribed to be re-sown and/or reseeded as required see above)</i>
	SEASONAL WETLANDS <i>Meadow Mixture for Seasonal</i> <i>Emorgate EMS sown at 4 g/m²</i>
	SENSORY MIX See Schedule
	GRAVEL BEDS <i>Regional Specification</i>

	1. FUN PANEL As Supplied by Prolific Ref. J3401 Or similar approved		CLIMBING FRAME As Supplied by Prolific Ref. J1651 Or similar approved
	2. CLIMBING BARS As Supplied by Prolific Ref. J4909 Or Similar Approved		3. SWINGS As Supplied by Prolific Ref. J490 Or similar approved
	3. INTERACTIVE PANEL As Supplied by Prolific Ref. J5424 Or Similar Approved		4. MULTI PLAY As Supplied by Prolific Ref. J4832 Or similar approved
	4. ROUNDABOUT As Supplied by Prolific Ref. J5601 Or similar approved		POST AND RAIL FENCE 1.2m High Regional Specification
	5. STRAWBERRY SPRINGER As Supplied by Prolific Ref. J660 Or similar approved		SELF-CLOSING GATES x1 1.2m High Double Pedestrian & Vehicle Gates x1 1.2m High Single Gate As Supplied by Wicksteed Playgrounds Ltd Ref: NPLGATE12 & NPLPGWATE12 Or Similar approved
	5. BALANCING BARS As Supplied by Prolific Ref. J4912 Or similar approved		FURNITURE As Supplied by Brozap Ltd x02 Ashbourne Seat Ref. BX 720 x02 Derby Standard Litter Bin Ref. BX45 2550-S Or similar approved

DRAWING NOTES

All tree and shrub locations and species must be approved by the City Engineer, in consideration by the project Structural Engineer to ensure that the foundation design accords with the specifications set out in Chapter 4 of the NHBG Standards.

The Landscape Contractor must ensure that all plant material is planted in the locations shown and with NO SUBSTITUTIONS made without consulting the Group Landscape Design Department. It is the Landscape Contractor's responsibility to ensure that all underground services have been located and identified in advance of tree pit excavation so that no services are damaged or compromised by tree planting. Any changes to tree positions, species or specifications must be approved by the Group Landscape Design Department. Underground service strips are to be kept free of all plant material.

Contractors must comply with all Health and Safety regulations and be aware of project/site specific information including referring to the information set out in the NHBG drawings.

NOT TO SCALE

The map shows the outline of the state of Illinois. A dashed rectangular box is drawn in the north-central part of the state, representing the study area. Three points are marked within this box: '-014' at the top left, '-023' at the top right, and '-015' at the bottom center. A north arrow is located in the top right corner of the map.

Symbol	Brief description of risk
	Caution overhead / underground services.
	Gas/electrical services.
	Trees have protection order in place, guarding required.

NOTES:
Principal contractor to ensure all health and safety procedures are being correctly followed in relation to all temporary works.

EM100-LS-014 (Plots 1-48)
EM100-LS-015 (Plots 49-97)

Revision	Date
a	Updated to the most recent layout.
b	Updated to the most recent layout.
c	Updated to the most recent layout.
d	Updated to the most recent layout.
e	Updated to the most recent layout.
f	Updated to the most recent layout.
g	Updated to the most recent engineering layout.

POS/Plot/Site
Landscaping

THIS DRAWING AND THE BUILDING WORKS DEPICTED ARE THE COPYRIGHT OF J.S.BLOOR (SERVICES) LIMITED AND MAY NOT BE REPRODUCED OR AMENDED EXCEPT BY WRITTEN PERMISSION. NO LIABILITY WILL BE ACCEPTED FOR AMENDMENTS MADE BY OTHER PERSONS.

Drawing No. EM100-LS-02

HINCKLEY WEST PH4