The Material List

71 Manor Road
Desford
LE9 9JQ

Proposal: Rear Single Storey Detached Building.

Ref:11/00157/FUL

The material list to the above proposal will be, as follows:

Wall construction to be: Cavity wall consisting of Common facing bricks outer skin – matching existing house brickwork – 100mm cavity fully filled with Dritherm32 & Thermalite blocks inner skin.

Roof tiles to be: Concrete roof tiles closely matching the existing main house roof tiles in colour. Note: the roof construction is truss rafters insulated with 400mm of rock-wool quilt at the horizontal ceiling line of roof – 200mm between rafters & further 200mm over.

Fascias & down pipes to be: UPVC black, matching main house.

White PVCu Triple glazed doors & windows to be installed.