



DESIGN & ACCESS STATEMENT

Site: Peggs Close, Earl Shilton, Leicestershire.

Reason: Demolition of disused flats and erection of a range of modern housing.

Job No: 2724

Client: Hinckley and Bosworth Borough Council.

Architect: Pelham Architects

Date: December 2025

Revision: - A July 2026

1.0 INTRODUCTION.

The existing buildings were built in 1977 and have a history of voids and hard to let flats since the introduction of the bedroom tax. This together with rising antisocial behaviour caused the authority to seek a solution.

These requirements have been addressed in the proposed design and the reports that accompany the planning application.

2.0 EXISTING SITE.

A feasibility study with a range of options including refurbishment and re modelling as well as part demolition and part new build were considered. It was found that the most economical way to achieve a more lettable, diverse range of accommodation and help to resolve the anti-social issues was to demolish the flats and design new affordable housing.

The client has undertaken a feasibility study resulting in this planning application, that shows that should the existing be demolished, a diverse range of modern apartments and family accommodation can be achieved on the site.



View of the existing redundant buildings.

The image from @Google (Copyright) shows the extent of the existing buildings and open space that currently occupy the site.

3.0 LOCATION.

The site is located in Earl Shilton between Peggs Close, Candle Lane and Astley Road, with vehicular access to a communal car park available from Peggs Close. A range of existing trees and shrubs surround the existing buildings. This space has very little boundary treatment with undefined open spaces up to the existing building footprints.

Immediately to the North of the site is a playing field belonging to St Simon and St Jude Primary school. Adjacent to this is a modern three storey block of apartments. The remainder of the boundaries have tradition suburban streets with two storey semi-detached and terraced housing.



Location Plan.



View of existing property from Peggs Close.



View of existing property from Candle Lane.



View of existing property from Astley Road.

3.1 Local services.

The site is located towards the edge of an existing residential area on the Southern edge of Earl Shilton; it is approximately an eleven-minute walk from the main commercial area on Wood Street, where a full range of services and amenities are available, including bus stop links to Nuneaton, Hinckley and Leicester.

3.2 Education & Healthcare provision.

The site is well served by an existing provision of local nurseries, primary and secondary schools. Barwell Medical Centre is a 7 minute drive away while Heath Lane Surgery is a 16 minute walk.

3.3 Retail facilities.

Located within a 1.5km walk from the edge of the site lie:

- A choice of mini markets
- Fast food and takeaway outlets
- Convenience stores, hairdressers and barbers
- Pharmacy

3.4 Places of Worship.

There are multiple places of worship within easy walking distance of the site.

3.5 Access to Transport – connectivity.

3.5.1 Walking.

Good quality pedestrian footways are provided on all sides of the carriageways on all key routes within the vicinity of the site.

3.5.2 Cycling.

There are currently no designated cycle paths in the area but the existing road network is residential in nature.

3.5.3 Bus Network.

The nearest bus stops are located on Peggs Close with others located on Wood Street, close to the site, giving regular access to Nuneaton, Hinckley and Leicester.

3.5.5 Road Network.

The site is linked to the A47 route to Hinckley and the M69 to further outlying towns and cities including Leicester and Coventry.

4.0 SITE CONDITIONS & LOCAL CHARACTER.

To ensure the physical, social and economic integration of development proposals, the areas immediately adjacent to the site, together with the site itself have been the subject of appraisal.

4.1 Existing Built Form

The site sits within Earl Shilton, Leicestershire.

The immediate housing here is characterised by pitched tiled roofs, a mix of red brick housing in semi-detached and terraced format. A mix of on plot and on street parking. Front gardens are not clearly defined but have a range of soft landscaping with shrubs and grassed lawns. Streets tend to be made up of semi-detached houses and terraces of up to four houses long, with a mix of council owned social housing and privately owned family homes. The housing is interspersed sparingly with larger blocks of flats.

This housing forms the majority of the local context of the site, with mostly two storey housing adjacent to the site, set back from the road with open front gardens. The housing design varies but is generally 1970s in style. The area is suburban in density with mature public open space dispersed throughout the area.

4.2 Site Boundary and Edges.

The site has no physical boundary to the three main streets. The site is dominated by the three storey flats. A range of mature trees within well kept lawns help to soften the street scene.

4.3 Topography.

The site is steeper to the Northern boundary with a drop of approximately 3m across the site from North to South.


4.4 Views.

Due to the relatively flat surrounding terrain, and suburban housing, there are no longer range views out from (or into) the site. The site is triangular and currently there are views across the northern edge of the site interrupted by a range of mature trees.


4.5 Flood Risk & Drainage.

The flood risk map indicates that the site is not within a flood risk area and that a risk of flooding from surface water is present but potentially due to a dip on the topography. The Severn Trent Water records show no drains within this flood area which supports this hypothesis.

The Severn Trent Water records show a combined sewer running across the corner of the Southern end of the site.



Flood risk map.



Surface water.



(c) Crown copyright and database rights 2021 Ordnance Survey 100031673 Date: 24/03/21 Scale: 1:1250 Map Centre: 446879.297573 Data updated: 14/03/21 Our Ref: 527351 - 3 Wastewater Plan A3

Do not scale off this Map. This plan and any information supplied with it is furnished as a general guide, is only valid at the date of issue and no warranty as to its correctness is given or implied. In particular this plan and any information shown on it must not be relied upon in the event of any development or works (including but not limited to excavations) in the vicinity of SEVERN TRENT WATER assets or for the purposes of determining the suitability of a point of connection to the sewerage or distribution systems. On 1 October 2011 most private sewers and private lateral drains in Severn Trent Water's sewerage area, which were connected to a public sewer as at 1 July 2011, transferred to the ownership of Severn Trent Water and became public sewers and public lateral drains. A further transfer takes place on 1 October 2012. Private pumping stations, which form part of these sewers or lateral drains, will transfer to ownership of Severn Trent Water on or before 1 October 2016. Severn Trent Water does not possess complete records of these assets. These assets may not be displayed on the map. Reproduction by permission of Ordnance Survey on behalf of HMSO. © Crown Copyright and database right 2004. All rights reserved. Ordnance Survey licence number: 100031673. Document users other than SEVERN TRENT WATER business users are advised that this document is provided for reference purpose only and is subject to copyright, therefore, no further copies should be made from it.

Public Foot Gully/Lateral Drain	Public Combined Overhead/Lateral Drain	Public Surface Water Gully/Lateral Drain	Private Foot	Private Combined	Private Surface Water
Highway Drain	Overflow Pipe	Disposal Pipe	Coloured Water Course	Pumping Station	Filling
Watercourse Foot	Watercourse Surface	Standard Pipe	Severely Silted Sewers (see advice to inspectors)	Private sewers are shown in red/pink	

helen@ncha.org.uk

Peggie Close, East S

2724

SEVERN

TRENT



Extract from Severn Trent Water records.

5.0 PROPOSAL.

5.1 Use.

The proposal is for a range of new family homes and apartments which will all be for rent and will be managed and maintained by the applicant Hinckley and Bosworth Borough Council.

Four of the ground floor apartments will be fully wheelchair accessible to Building Regulations standard M4(3).

5.2 Amount.

The site area is approximately 0.46Ha gives a density 39.1 homes per hectare.

5 x 2b4p houses to 100% NDSS standard @ 79m²

5 x 3b5p houses to 100% NDSS standard @ 93m²

4 x 1b2p wheelchair flats to M4(3) standard @ 59.5m²

4 x 1b2p general needs flats to 126.6% NDSS standard @ 63.3m²

Total 18 homes.

5.3 Parking.

Family Housing.

Each house will have at least two parking spaces on plot or in the parking court. Only Plot 1 to 3 is served by a parking court In total the family housing parking standard will be 200% .

Apartments.

The four ground floor wheelchair apartments will have a dedicated wheelchair parking space each. An additional 4 spaces will be provided on site for the upper floor apartments. In total the apartments parking standard will be 100%.

EVCP

Electric vehicle charging will be provided in line with current Building Regulations.

On street parking.

There is no parking permit system in place for on street parking. Local streets have ample space for occasional visitor parking.

5.4 Layout.

The layout takes advantage of the existing road network so that no new roads are required. This will help to make the scheme more economical but also increase density as much of the available land is maximised for housing.



Proposed site plan.

The start point for the layout was to look at the constraints and opportunities. A sewer running across the Southern end of the site will require any new development to have an easement, so we have positioned the new homes to allow for this. The other constraints take the form of trees across the site. These are mature trees which we want to keep and will form opportunities for biodiversity and give the finished scheme a sense of establishment from the start. Housing has been positioned to address the existing streets but also set back behind the tree line, or in between the trees.


A two-storey apartment block of 8 apartments sits at the Southern end. The apartments all have private entrances with the first-floor flats served by private stairs. The ground floor wheelchair apartments have parking as close to their front doors as possible. The apartments look out onto communal areas either side with short views onto Peggs Close, Candle Lane and Astley Road. The communal areas will be maintained by the client Hinckley and Bosworth Borough Council. With the new housing overlooking the existing surrounding streets, the design provides the best opportunities for natural street surveillance which will encourage safe secure streets.

6.0 LANDSCAPE.

The proposal aims to retain as many of the existing mature trees as possible so that existing biodiversity is retained.

An outline landscape proposal is indicated on the site plan which shows a minimum of 31 new trees being planted along with new hedges and shrubs. These will count towards the BNG +10.38% within the site. See the Biodiversity Net Gain Report and Metric Calculation by Elite Ecology (July 2026)

In addition, low timber knee rails will help to define plots at front gardens while the hedges and shrubs become established and eventually form natural boundaries.



Tree survey plan.

7.0 CHARACTER.

7.1 Form and Massing.

The design responds to the local street scenes, constraints and opportunities.

The local housing typology is of terraced or semi detached housing. The new development will follow this typology with any mid-terraced housing having ginnels for rear access so that all bins are stored in respective rear gardens. The ginnels as well as steps in elevation which correspond to the site topography, and fenestration, will all help to break the form into smaller domestic proportions.

7.2 Appearance.

The local housing is of a traditional red brick and grey tiled pitched roof appearance. The new housing will follow this principal with the addition of some embellishment in the form of soldier coursing and render to help form 'book ends' to each section of the development.

8.0 ACCESS.

The design of the homes is in accordance with Building Regulations Part M4(1), which means that the homes are visitable in a wheelchair. Door widths are set at certain minimum clear widths & the front door has level access.

The ground floor is also provided with a WC that has a door arrangement to allow transfer from a Wheelchair.

Corridor and turning are also designed to ensure minimums are achieved.

Section 1B: Private entrances and spaces within the dwelling

Application

1.13 Except where noted, the provisions of Section 1B apply to the **principal private entrance** and to key areas within the **entrance storey** (or where there are no **habitable rooms** on the **entrance storey**, the **principal storey**) of the dwelling. This applies to all **dwelling types**, including upper floor flats.


Private entrances

- 1.14** The **principal private entrance** to the **dwelling** (or the alternative entrance where the **approach route** is not to the **principal private entrance**) should comply with all of the following.
- The door has a minimum **clear opening width** of 775mm, when measured in accordance with Diagram 1.1.
 - Any threshold is an **accessible threshold**.
 - Where a step into the **dwelling** is unavoidable, the rise is a maximum 150mm and is aligned with the outside face of the door threshold.

Circulation areas and internal doorways

Door and hall widths

- 1.15** To facilitate access into **habitable rooms** and to a WC in the **entrance storey**, door and hall widths should comply with all of the following (see Diagram 1.2).
- Every door to a **habitable room** and the room containing the WC has a minimum **clear opening width** as set out in Table 1.1, when measured in accordance with Diagram 1.1.
 - Any **localised obstruction**, such as a radiator, does not occur opposite or close to a doorway, and is no longer than 2m in length; and the corridor is not reduced below a minimum 750mm width at any point.



9.0 SUMMARY.

The proposals will provide for a mix of apartment and family home sizes including Four wheelchair apartments and will provide much needed affordable provision. The scheme will include common open space, with planting to assist in the bio-diversity of the area.

On foot and by cycle the development provides a friendly environment, as the routes are clear, open and over-looked by the new homes to promote safety.

The application site is in a sustainable location for development and the proposals are in compliance with the principles of sustainable design.

Residential development is also considered to be an appropriate use for the site and compatible with the character of the surrounding area.

The proposed development represents a viable and deliverable prospect which would be wholly in keeping with the local built environment, building on the positive characteristics of the area to propose a responsive and sustainable residential scheme.