Foul Water Network STRUCTURE TABLE

Manhole Name	Cover Level (m)	MH Depth (m)	Chamber Type	Manhole Diam (mm)	Manhole Easting (m)	Manhole Northing (m)	Pipe Out PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	Pipes In PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Pipes In Backdrop (mm)	Notes
FW 19	119.980	0.500	PPIC	450	442,929.711	293,716.028	7.000	119.480	150					
FW 20	119.980	0.669	PPIC	450	442,931.173	293,702.957	7.001	119.311	150	7.000	119.311	150		
FW 21	119.980	0.851	PPIC	450	442,933.022	293,688.496	7.002	119.129	150	7.001	119.129	150		
FW 22	119.980	0.917	PPIC	450	442,927.783	293,687.864	7.003	119.063	150	7.002	119.063	150		
FW 23	119.980	0.948	PPIC	450	442,928.078	293,685.401	7.004	119.032	150	7.003	119.032	150		
FW 24	119.980	1.100	PPIC	450	442,904.934	293,684.970	7.004A	118.880	150	7.004	118.880	150		
FW 25	119.980	1.112	PPIC	450	442,907.178	293,682.705	7.005	118.768	150	7.004A	118.768	150		
FW 27	120.050	1.050	PPIC	450	442,896.743	293,706.519	8.000	119.000	150					
FW 28	120.100	1.141	PPIC	450	442,897.231	293,702.882	8.001	118.959	150	8.000	118.959	150		
FW 29	120.200	1.296	PPIC	450	442,897.855	293,698.005	8.002	118.821	150	8.001	118.821	150		
FW 30	120.500	1.675	PPIC	600	442,898.903	293,691.045	7.006	118.622	150	7.005	118.622	150		
										8.002	118.622	150		
EX MH	120.070	1.680	Existing Manhole		442,892.267	293,688.815	OUTPUT	118.390		7.006	118.390	150		Connection to Existing CW Manhole

This drawing should not be scaled. Dimensions to be verified on site.
Any discrepancies should be referred to the Engineer prior to work being put in hand.

This drawing is the property of Waterman Infrastructure & Environment Limited, and the drawing is issued on the condition that it is not copied reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the consent in writing of Waterman Infrastructure & Environment Limited
Pickfords Wharf, Clink Street, London SE1 9DG t 020 7928 7888 f 03333 444 501

GENERAL NOTES

1. DO NOT SCALE THIS DRAWING.
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, ENGINEER'S, SERVICES AND SPECIALIST DRAWINGS AND SPECIFICATIONS.
3. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
4. ANY DISCREPANCIES IN DIMENSIONS OR DETAILS ON OR BETWEEN THESE DRAWINGS SHOULD BE DRAWN TO THE ATTENTION OF THE ARCHITECT AND/OR THE ENGINEER.
5. ALL COVER AND INVERT LEVELS ARE SHOWN IN METRES AND PIPE DIAMETERS ARE IN MILLIMETRES.
6. REFER TO DRAINAGE LAYOUT DRAWING NUMBER 19849-WIE-ZZ-XX-DR-D-92-001 FOR OTHER NOTES.
7. ALL DIMENSIONS AND LEVELS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO PREPARING ANY WORKING DRAWINGS OR COMMENCING ON SITE.
8. REFER TO DRAINAGE CONSTRUCTION DETAIL DRAWING NUMBER FOR 19849-WIE-ZZ-XX-DR-D-92-007 FOR FLOW CONTROL DETAILS.
9. REFER TO DRAINAGE CONSTRUCTION DETAIL DRAWING NUMBER FOR 19849-WIE-ZZ-XX-DR-D-92-005 FOR PIPE BEDDING DETAILS.
8. ALL MANHOLE COVERS TO BE RECESSED COVERS AS PER ARCHITECT'S RECOMMENDATIONS, DUCTILE IRON LOAD CLASS D400 WITH MINIMUM CLEAR OPENING 600mm AND COVER FRAME DEPTH 100mm.
9. COVER LEVEL SHOWN FOR REFERENCE AND TO BE IN LINE WITH THE FINAL GROUND LEVELS, TO BE CONFIRMED ON SITE
10. ANY DISCREPANCIES IN THE LEVELS TO BE REPORTED TO THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.

Rev	Date	Description	By	Chk
C03	16.12.24	MH SCHEDULE UPDATED	SM	PE
C02	21.06.24	MH DIAMETER UPDATED	TY	PE
C01	30.05.24	STAGE 4 ISSUE	AS	SS

Amendments

Project
HINCKLEY CDC AND ENDOSCOPY

Title
FOUL WATER MANHOLE SCHEDULE

Client
DARWIN GROUP

5th Floor One Cornwall Street Birmingham B3 2DX
t 0121 212 7700
mail@watermangroup.com www.watermangroup.com

Work Stage: STAGE 4 Technical Design — RIBA
Suitability: STAGE COMPLETE — A1

Designed By	Director	Waterman Ref
AS	SS	WIE19849
Drawn By	**Date**	**Scales @ A1**
AS	JUNE 2024	NTS

Project | Originator | Functional | Spatial | Form | Discipline | Number: 19849-WIE-XX-ZZ-DR-D-92-011
Revision: C03

File Path: \\waterman-consulting.com\legacy\file\BM_WIE\Projects\WIE19849 Hinckley Daycare\1007_CAD\92_Drainage\